

1.0 INTRODUCTION

- 1.1 A full planning application has been submitted for proposed residential development at Paddock Lane, Holbcach Bank. Spalding, Lines.
- 1.2 A Flood Risk Assessment is required to accompany the planning application and meet the requirements and general principles contained in Paragraph 9 of the Technical Guidance to the National Planning Policy Framework (NPPF) and for approval by the Environment Agency.

The site, as situated, is located within Flood Zone 3. of the Environment Agency's Flood Zone Maps. The latest Agency Flood Maps have been created as a tool to raise awareness of flood risk with the public and our partner organisations, such as Local Authorities, Emergency Services and Drainage Authorities. The Maps do not take into account any flood defences.

The site however is also shown in Flood Zone 1 and outside of any 1 hazard Zone of the South Holland District Council's Strategic Flood Risk Assessment Maps (2010).

The site is also located in the South Holland IDB drainage district.

2.0 LOCATION

- 2.1 The development site is located south of Roman Bank, Holbeach Bank.
- 2.2 The position and extent of the site is shown on Fig 1 - Location & Site Layout Plans at the end of the document.
- 2.3 The site, located within the South Holland Internal Drainage Board district is shown within Flood Zone 3 as detailed on the Environment Agency Flood Zone Maps but in Flood Zone 1 of the Council's Strategic Flood Risk Assessment Maps (2010) as defended by the Agency's tidal defences and the Internal Drainage Board system.

3.0 THE SITE AND SEQUENTIAL TEST

- 3.1 The site is currently a paddock.
- 3.2 The area of development is approximately 1.20 hectare.
- 3.3 The proposed site layout consists the construction of two storey houses with existing land level varying between 2.79m and 2.97m aOD and

Roman Bank carriageway level varying between 3.73m and 4.06m

- 3.4 The Sequential Test and Exception Test will require to be applied by the Local Planning Authority but the development may be permitted as the site is protected against both the 1 in 200 year return period tidal event and the 1 in 100 year return period fluvial event. The Sequential Test is met as the site is in Flood Zone 1 of the Council's Strategic Flood Risk Assessment Maps (2010).

4.0 EXISTING FLOOD ALLEVIATION MEASURES

- 4.1 The site is within a defended floodplain, as defined in Appendix 1 of the Environment Agency's 'Policy for the Protection of Floodplains*' and is considered to be passive until such time as a flood greater than that for which the defences were designed occurs. The likelihood of Hooding due to overtopping or failure of a Hood defence embankment is considered to be small.

The development site within the South Holland Internal Drainage Board is protected by the Wash tidal defences to the Holbeach Marsh frontage with embankment levels of a minimum of 7.00m aOD.

- 4.2 The site and the surrounding land drains by gravity to the Board's Peartree Drain and via the Peartree Drain Pumping Station to the Holbeach River Outfall Sluice.

- 4.3 The existing standard of drainage for the South Holland Internal Drainage Board is 1 in 50 years return period, compatible with the Department of the Environment, Food and Rural Affairs target level of sendee for rural drainage and Hood defence works. Freeboard of 900 mm is provided to the lowest land levels.

- 4.4 Current maintenance standards within the South Holland Internal Drainage Board and of the Environment Agency defences are generally very good.

During the operation and maintenance of its pumping stations, associated structures and channel systems, particularly those that could affect property, (he Board seeks to maintain a general standard capable of providing flood protection to its district. A routine maintenance programme is in place to ensure that the Boards assets are commensurate with the standard of protection that is sought. however, bank slips, blocked culverts etc may occur from time to time and these matters are usually dealt with promptly.

5.0 POTENTIAL SOURCES OF FLOODING

- 5.1 Four potential sources of flooding have been identified as a result of this assessment:

local blockages to IDB main drain system.

storm return period of 1 in 50 years being exceeded

failure of Peartree Drain Pumping Station

overtopping and breaching of defences of the Wash tidal defences

- 5.2 The probability of flooding from source a) is low due to the maintenance standards already achieved and managed by the 1D8.

The probability of flooding from b) is also low due to the South Holland 1DB main drain design standard incorporating a minimum 900 mm freeboard to the lowest land level which provides adequate storage in events greater than 1 in 50 years.

Previous historic rainfall events of 1968 and 1978, estimated to be greater than 1 in 100 year events, caused no flooding to any residential properties at the time and the Boards policy is to provide a standard of drainage which satisfies NPPF requirements of a 1 in 100 year return period for fluvial protection inclusive of the effects of climate change and developments to the arterial system enables a flexible approach to be adopted and meet the criteria for "sustainable urban drainage".

- 5.3 Failure of Peartree Drain Pumping Station may occur due to long term mechanical breakdown or power supply being disrupted. However, in these circumstances, if conditions were such as to put properties and land at risk of flooding, the Internal Drainage Board would take emergency action to maintain the drainage level of sendee by utilising temporary pumping equipment. The probability of such an occurrence is also considered to be low.

- 5.4 The flood embankments to the Wash tidal defences provide a 1 in 200 year return period level of protection.

The 1 in 200 year tidal event to the Holbeach Marsh frontage inclusive of climate change to 2115 is estimated to be 7.20m aOD as against existing embankment levels of a minimum of 7.00m aOD.

There is a low risk during such an event for wave and wind action to cause overtopping and/or breaching of the first line defences. However, the site is further protected by second line defences with embankment levels of 6.00m aOD.

More recent Tidal Hazard mapping produced by the Environment Agency in Fig 4 shows the site could be affected by floodwaters of up to 500mm as a result of a breach to The Wash primary defences.

It is necessary to mitigate against this remote risk and finished floor levels have been raised 500mm above existing ground level with flood resilient construction incorporated to a height of 300mm above finished floor level.

- 5.6 Surface water drainage from the development site will be to soakaways designed to BRE365 requirements and Building Regulations approval.

6.0 EXTENT OF KNOWN FLOODING

- 6.1 During the preparation of this assessment, no evidence was discovered of the site being flooded or of any adjoining properties.

7.0 PROBABILITIES AND TRENDS OF FLOODING

- 7.1 The probability of this development flooding from localised drainage systems is very low.
- 7.2 The probability of the site flooding with water from any South Holland 1DB main drain is less than 1% because of the standards of the existing flood defence systems, storage within existing drainage channels and the location of the site.
- 7.3 The probability of the site flooding with tidal waters from any main river system is less than 1% because of the standards of the existing flood defences and the location of the site.
- 7.4 If under very extreme events, levels of floodwater from the South Holland 1DB main drains or arterial systems rose to such an extent that the site was affected, the situation would not be sudden. It is very probable that sufficient time would be available to take precautionary actions to limit the extent and potential impact of flooding.
- 7.5 The water levels in the drainage channels will tend to rise as a result of the impacts of climate change. However the existing systems and defences together with the proposed floor levels at 500mm above surrounding ground level will be appropriate for the design life of the development (i.e. 100 years). Safe refuge is available at first floor level with all sleeping accommodation.

8.0 IMPACTS OF FLOODING

- 8.1 No significant impacts of flooding are anticipated.
- 8.2 Floor levels of the development will be at 500mm above surrounding ground levels which together with the proposed soakaway drainage system will offer additional protection against impacts arising from any extreme short duration, localised events.
- 8.3 The general location of the site within the catchment is such that if flooding occurred from any of the South Holland 1DB main drain systems, then probably 2 to 3 days warning time would be available.
- 8.4 No displacement of water from the site will affect any adjoining properties as existing soakaway drainage system will be utilised.
- 8.5 Safe and dry access/egress is available to and from the site onto Roman Bank in a southerly direction to Holbeach town centre with carriageway level between 3.74m and 4.00m aOD and surrounding land in Flood Zone 1.

- 8.6 The developer should ensure that the eventual occupiers of the dwellings are sufficiently aware of the risk of Flooding, and the standard of the existing defences. The Environment Agency provides a Flood Warning Service which includes Flood Warning Codes and uses direct warning methods where the risks and impacts of Hooding are high. Indirect warnings are provided to all flood risk areas, even those at low risk of Hooding. The main method is media broadcasts via local radio and also by television.

In addition to direct and indirect Flood warnings, the Environment Agency operates a 24 hour a day Floodline Service providing advice and information on flooding, contact tel no: 0845 088 118S and the occupiers of the new dwellings should register with the Floodline Direct Warnings Service to receive future flood warnings.

9.0 RESIDUAL RISK - EXTREME EVENTS

- 9.1 The residual risk from extreme events is very low on this site, because of its location, within the South Holland 1DB area and its location 7.00 kms from The Wash tidal defences with secondary defences between the marsh frontage and the site.
- 9.2 The site is within Flood Zone 1 according to NPPF classification, the site actually has a very low risk of flooding due to the current standards of drainage and flood defence and land levels. The site is not located within a Functional Flood Plain of any ' main river' or ' main drain' . The Environment Agency Flood Zone Maps have been produced irrespective of existing flood defences and standards of protection.
- 9.3 South Holland District Council in conjunction with the Environment Agency and the local IDB' s within the Council area have carried out a Strategic Flood Risk Assessment (2010) of the whole District by appointed Consulting Engineers.

The Strategic Flood Risk Assessment (2010) has produced more definitive Flood Risk Maps than those published by the Environment Agency and at the same time has analysed Hood return periods of all tidal and fluvial defences to account for the effects of climate change.

Breach scenarios of embankments failing and/or being overtopped have also been carried out to establish Flood Risk Zones. As a result of the Strategic Flood Risk Assessment (2010) the site is outside any Hazard Zone and defended by tidal defences and tidal doors.

10.0 CONCLUSIONS AND RECOMMENDATIONS

10.1 As a result of the assessment, the following conclusions have been reached:-

- . The proposed development is in a Defended Floodplain. It is located in the Passive Floodplain protected by defences to a 1 in 200 year return period, (1.0%)
- . The site is in Flood Zone I with the actual risk of site flooding from any Environment Agency river system being very low (less than 0.5%).
- . Although the site is located within an Internal Drainage District with a minimum standard of drainage of 1 in 50 years, this accords with Defra guidelines for rural development. Freeboard to design water level of 900mm to lowest land level is available for events greater than 1 in 50 years providing further storage within the drainage channels.
- . On site rainwater from the development will be discharged via soakaway drainage to BRE365 design requirements.
- . Floor levels of the development will be at a minimum of 500mm above existing ground level with flood resilient construction up to 300 mm above finished floor level and all sleeping accommodation with safe refuge at first floor level.
- . All development has been located outside the 9.00m Byelaw distance of the adjoining Peartree Drain to meet with South Holland Drainage Board requirements.