PLANTING NOTES

The beech hedge is to be planted in a single row at 450 mm centres.

The native mixed hedges are to be planted in 2 rows 250mm apart and at 450mm centres (6 plants /linear metre). Hollies to be planted in groups of no less than 3no. and blackthorn in groups of no less than 5no.

The woodland edge mixes A & B are to be no closer than 1m to the adjacent boundary fencing.

For additional information & specifications please refer to the accompanying Landscape Management Plan (LMP).

KEY.

- SPECIMEN TREE.
- SHRUB BED.
- HEDGEROW.
- GRASS/LAWN.
- BULB PLANTING.

N.B. This drawing has been prepared without the benefit of information or drawings showing the location of underground services & easements. It is therefore the responsibility of the main contractor identify these prior to landscape operations on site.

Please do not scale from this Drawing.

HEDGE 'A'.
50 No. Acer campestre (A.cam)
50 No. Corylus avellana (C.av)
165 No. Crataegus Laevigata (Cr.lae)
400 No. Crataegus monbyuna (Cr.mon.)
50 No. Cornus sanguinea (C.san.)
50 No. Ilex aquifolium (I.aq.)
165 No. Prunus spinosa (P.sp.)
50 No. Rosa canina (Ro.can)
50 No. Ulmus procera (U.pr)
50 No. Viburnum opulus (V.op).
TOTAL: 1,080 No.

AREA 'A': SPECIES RICH WILDFLOWER MEADOW. Emorsgate Seeds Mix EN1 Spatial pollen & nectar meadow mix sown @ a rate of 4gm/m².

HEDGE 'C'.
30 No. A.cam.
30 No. C.av.
90 No. C.lae.
180 No. C.mon.
30 No. C.san.
30 No. I.aq.
90 No. P.sp.
30 No. Ro.can.
30 No. U.pr.
30 No. V.op.
TOTAL: 570 No.

HEDGE 'D': 185 No. Fagus sylvatica.

HEDGE 'B'.
40 No. Ilex aquifolium.

AREA 'B': PUBLIC OPEN SPACE
Emorsgate Seed mix EG22 c/ Strong lawn grass mixture & clovers, sown @ 25g/m².

AREA 'C': PUBLIC OPEN SPACE
Emorsgate Seeds mix EH1 Grass & Wildflower mixture for Hedgerows & Woodlands, sown @ 4gm/m².

HEDGE 'E'.
35 No. A.cam.
350 No. Cr.mon.
70 No. Cr.lae.
140 No. P.sp.
35 No. I.aq.
35 No. U.pr.
35 No. V.op.
TOTAL: 700 No.

WOODLAND EDGE MIX 'A'.
Rows A & B @ 1m ctrs, Row C @ 500mm ctrs.
Rows A & B: 30 No. A.cam, 30 No. C.av, 20 No. Cr.lae, 20 No. Cr.mon, 30 No. C.san, L.vulg 20 No., 10 No. Malus sylvestris, 20 No. P.av, 10 No. P.sp, 10 No. Prunus communis, 10 No. Ro.can, 10 No. Sorbus torminalis, 20 No. U.pr, 30 No. V.op. Total: 260 No.
Row C: 120 No. Cr.mon, 20 No. Cr.lae, 100 No. P.sp, 10 No. I.aq. Total: 260 No.

WOODLAND EDGE MIX 'B'
5 No. rows set 1m apart, transplants @ random/staggered 1m ctrs.
20 No. A.cam, 10 No. C.av, 20 No. C.san, 10 No. Malus sylvestris, 100 No. P.sp, 20 No. Ro.can, 20 No. V.op. TOTAL: 200 No.

3 No. Juniperus communis 'Hibernica'
1 No. Pinus sylvestris.
1 No. Pinus pinea.
1 No. Pinus mugo
100 No. Narcissus pseudonarcissus
1 No. Pinus nigra.
1 No. Pinus ayrshirii
200 No. Tulipa mixed.
N.B. NO TREE OR SHRUB PLANTING DUE TO PROXIMITY OF MAIN SERVICE RUN.
1 No. Prunus 'Amanogawa'
1 No. Sorbus aria 'Lutescens'
1 No. Acer japonicum 'Aconitifolium'
1 No. Acer pensylvanicum
1 No. Crataegus oxyacantha 'Paul's Scarlet'
1 No. Sorbus xkewensis
1 No. Sorbus aria 'Lutescens'
1 No. Amelanchier Lamarckii
1 No. Malus 'Profusion'
1 No. Taxus baccata 'Aurea'
1 No. Sorbus 'Joseph Rock'
1 No. Malus 'Golden Hornet'
1 No. Malus floribunda
1 No. Acer japonicum
1 No. Pyrus nivalis
3 No. Betula utilis.
1 No. Malus eschenaskii
1 No. Amelanchier lamarckii
1 No. Prunus x hillieri 'Spire'.
1 No. Betula utilis.
1 No. Laurus nobilis.
1 No. Acer palmatum
2 No. Amelanchier Lamarckii
1 No. Malus trilobata
3 No. Sorbus aucuparia 'pendula'
1 No. Acer japonicum 'Aureum'
1 No. Prunus dulcis
3 No. Amelanchier lamarckii
1 No. Malus 'Golden Hornet'
1 No. Malus 'Profusion'
1 No. Prunus 'Ta Haku'
1 No. Acer pensylvanicum
1 No. Prunus sargentii
1 No. Pyrus nivalis
1 No. Prunus avium 'Plena'
1 No. Malus floribunda
2 No. Sorbus aucuparia 'pendula'
1 No. Betula utilis
1 No. Prunus x hillieri 'Spire'.
1 No. Malus 'John Downie'
1 No. Acer davidii 'Serpentine'
1 No. Acer pensylvanicum
1 No. Acer ginnala
1 No. Prunus avium 'Plena'
1 No. Taxus baccata 'pendula'
1 No. Betula utilis
1 No. Cotoneaster frigida
1 No. Prunus x hillieri 'Spire'.
1 No. Juniperus communis 'Hibernica'
1 No. Malus trilobata.
1 No. Prunus dulcis
1 No. Crataegus x lavallei.
1 No. Pyrus nivalis.
1 No. Pinus sylvestris
1 No. Crataegus x lavallei.
1 No. Acer campestre
1 No. Fagus sylvatica.
1 No. Tilia cordata.
1 No. Quercus robur.
1 No. Alnus glutinosa.
1 No. Salix alba.
1 No. Corylus colurna.
1 No. Quercus robur.
1 No. Alnus glutinosa 'Imperialis'
350 No. Narcissus pseudonarcissus
1 No. Sorbus aria 'Lutescens'
1 No. Acer campestre
1 No. Carpinus betulus 'Columnaris'
1 No. Sorbus aria.
1 No. Tilia x euchlora.
1 No. Sorbus aucuparia.
1 No. Fagus sylvatica.
1 No. Tilia x euchlora
1 No. Quercus robur.
1 No. Fagus sylvatica 'Asplenifolia'
1 No. Alnus glutinosa.
1 No. Ailanthus altissima.
5 No. Amelanchier lamarckii.
1·2m high timber post & rail fence.
Mown path.
9m I.D.B. EASEMENT.
GREEN DRAIN
OPEN DRAIN
AREA 'D'
DITCH

SCALE: IN METRES (1:500 @ A1).

JONATHAN BIGGADIKE PG Dip LA CMLI

CHARTERED LANDSCAPE ARCHITECT

Project: Planting Masterplan for residential development.

Client: D. Brown Builders Ltd.

Location: Wignals Gate, Holbeach, Lincolnshire.

Drawing No: WG/18/01. **Date:** Sept. '18.

T: 01775 680595 M: 07772 509351 E: jbiggadike@outlook.com

Trading as Dragonfly Building Conservation & Landscape Design Ltd.