

# NOTES

PROVIDE FLY SCREENS TO OPENING VENTS IN KITCHENS

PROVIDE ADDITIONAL POWER POINTS WHERE NECESSARY

TO BOTH KITCHENS PROVIDE ALTRD OR SIMILAR APPROVED SAFETY FLOORING WITH SKIRTINGS

PROVIDE 3RD ROWS OF WALL TILES ABOVE WORK SURFACES


MAKE GENERAL REPAIRS TO WALLS & CEILING TO BOTH KITCHEN AREAS

PROVIDE MECHANICAL VENTILATION TO W.C.S WITHOUT NATURAL VENT.

PROVIDE NEW SUITABLE FLOOR COVERINGS TO TOILET AREAS

PROVIDE NEW W.C. S & W.H.B. S WHERE NECESSARY TO ALTERD TOILET AREAS

CONNECT NEW FOUL DRAINS TO EXISTING WHERE SHOWN AS REQUIRED



FLOOR PLAN

**ROOF CONSTRUCTION**  
Concrete interlocking tiles (see plan) on 38 x 25 softwood treated timber battens as underfelt to BS747 (Type 1F) spaced 180mm horizontally and 100mm vertically. Prefabricated roof trusses at 600mm c/c and pitch as stated in accordance with BS5268 Part 3, 1985. Provide 25 x 100mm timber bracing and fix in accordance with truss manufacturers' instructions. All trusses and gable ladders (if any) to be strapped to 50 x 100mm timber wallplate, the gable wall at verge and ceiling level with 25 x 50mm mild steel anchor and internal restraint straps to span minimum 3 no. trusses at a maximum of 1800mm c/c. At strap positions provide pack and noggins to trusses. Main contractor to supply local authority building control with roof truss calculations 28 days prior to erection on site.

**NEW VENTILATION**  
All eaves provide proprietary ventilation equivalent to a 10mm continuous gap along eaves.

**NEW INSULATION**  
To roof space provide proprietary 100mm thick insulation ensuring a gap of 50mm between roof underfelt and quilt at all eaves.

**GUTTER AND DOWNPIPES**  
To be 25 x 175mm PSE with 50mm groove to accept 6mm thick exterior grade plywood soffit.

**UNDERGROUND DRAINAGE**  
Underground drainage to be proprietary 110mm diameter P.V.C. pipes flexible jointed to fall 1:70 bedded in 100mm pea gravel. Under building drains to be enclosed in 150mm pea gravel with listed cover pipes at wall abutments. Buried pipes at wall abutments with 50mm compressible material. 110mm diameter soil and vent pipe to extend 300mm above window head and to terminate in balloon flange. Soil and vent pipe to be fitted with covers plate at base. Provide suitably sized wastes from all appliances (in accordance with Approved Document H) complete with minimum 75mm deep sealed traps and rodding eye access points at every direction change. All above ground drainage to BS5582 and all underground drainage to BS8301.

**WATER SUPPLY DRAINAGE**  
To be proprietary 110mm diameter P.V.C. pipes flexible jointed to fall 1:70 bedded in 100mm pea gravel. Pipes to discharge into 1200mm diameter manholes sized 500mm away from buildings.

**CONSTRUCTION TO TERRACED STEPS**  
Where steps are not under road and have less than 600mm cover concrete paving slabs should be laid as bridging above the pipes on minimum 75mm pea gravel. If flexible pipes are under a road and have less than 300mm cover reinforced concrete bridging should be used instead of paving slabs.

**CONSTRUCTION CHANGING CONSTRUCTION**  
Proprietary polypropylene insipide underlay bedded on 150mm concrete. Form protective 150mm thick concrete collar around head of inspection chamber with 300mm projection from power. Covers to be Grade C light duty unless inspection chambers are in driveways where Grade B section duty covers are to be used.

**WALLS**  
All cavity bricks to be made in accordance with marked on plan to be by To be installed in strict accordance with manufacturers' instructions. For d.p.c. cavity tray above all lintels. To all exposed lintels i.e. not sheltered from overhanging eaves, etc. to have proprietary masonry to joints of brickwork at approx. 600mm c/c.

**GROUND FLOOR CONSTRUCTION**  
50mm sand/cement screed on 100mm concrete over on 1200 gauge polythene d.p.s. on minimum 150mm, minimum 600mm well blotted and compacted hardcore. Wall d.p.c. to lap floor d.p.s. by a minimum of 50mm.

**STRUCTURE WALLS**  
100mm Class A dense concrete blocks. Bricks set d.p.c. to external walls 150mm above ground level. Work mix infill to base of services to terminate 225mm below lowest d.p.c. level.

**FOUNDATIONS**  
As indicated on plan provide concrete strip foundations. To cavity walls provide 700mm wide x 225mm thick.


**CEILING**  
To all finished roof ceilings provide 12.5mm Oppos Duplex plasterboard or similar and other 50mm skin or Artec finish. To remaining ceilings provide 12.5mm Oppos plasterboard or similar with finish as above.

**ROOF/WALL JOINTS**  
Provide Code A lead flashing that fits over roof covering. Dress up wall a minimum of 150mm (stepped in pitched abutments) and provide d.p.c. cavity tray to make completely watertight.


**CONSTRUCTION CHANGING CONSTRUCTION**  
Provide the above to the design as shown on elevations plus any other details that are shown on the plans.

**NEW/OLD WALLS**  
Where new walls meet old provide proprietary vertical flexible wall starters.


**WALL CONSTRUCTION**  
150mm cavity walls to be built up of 100mm face brickwork (see also plan for details). 65mm cavity to be filled with Brown Bricks full fill insulation in accordance with BS 5611/1978 or similar approved. 100mm internal skin of 100mm hollow blockwork. Cavity walls to be built up using galvanized iron or plastic sheet linc spaced 900mm horizontally and 500mm vertically to BS1243, 1978. Internal blockwork walls to receive 10mm sand/cement render and this finish.



FRONT




SIDE



REAR

WOOF PITCH TO BE APPROX 35 CHECK ON SITE



SECTION THRO

REAR SOUTH ROYAL HOUSING & PLANNING 09 JAN 1996 Ref: 0017/96

DETERMINED PLAN

**Status**  
CONSULTANTS IN ARCHITECTURE & PLANNING

PROPOSED ALTERATIONS & EXTENSION TO LONG SUTTON CHURCH HALL, MARKET PLACE, LONG SUTTON FOR

THE TRUSTEES OF THE CHURCH HALL

£2500

1:50 1:100


NOV-95

A - GEN ALTS - 15.12.95

771865/2

B.G.L.H.A.M.

Status House, 4 Princes Street, Hobbech, Lincs. PE12 7BB Tel: 01406 424343 Fax: 01406 440702



EXISTING FLOOR PLAN

**DETERMINED  
PLAN**

SOUTH EAST  
HOUSING  
09 JAN 1996  
Ref: 0017/96

**STATUS**  
DESIGN  
CONSULTANTS IN ARCHITECTURE & PLANNING

**PROPOSED ALTERATIONS &  
EXTENSION TO LONG  
SUTTON CHURCH HALL,  
MARKET PLACE, LONG  
SUTTON FOR**

**THE TRUSTEES OF THE  
CHURCH HALL**

**PLAN AS EXISTING**

**£50 771865/1  
NOV-95 B.GILHAM**

Status House, 4 Prince Street,  
Hobbesch, Lincs. PE12 7BB  
Tel: 01406 424343 Fax: 01406 480702