



22. TRUSS BRACING
Bracing to comply with BS5268 Part 3 1998.
All bracing 25 x 100mm timber graded to min. SC3.
2 No. binders on ceiling tie running full length.
3 No. longitudinal bracing member on webs - full length.
Diagonal bracing under rafter set at 45° to wall both sides and both ends.
Short bracing on internal members at full length.
All bracing to be securely fixed using min. 63mm galvanised nails, and as per manufacturers recommendations and details.

TRUSS

MAX 600mm x 60mm

17.5mm CYCLIC WALLBOARD
OR EXT. GRADE PLYWOOD

CONCRETE SLAB

FOOTING

SECTION 104 P. 2

10. GROUND FLOOR CONSTRUCTION (SOLID)
Lay minimum of 150mm clean stone hardcore/aggregate (graded 75mm down).
Thoroughly compact in layers not exceeding 230mm.
Blind surface with clean sand, compact and bring to flat level surface.
Lay 1200g polythene D.P.M. and link to D.P.C. at junctions.
Lap D.P.M. 300mm and tape.
Lay 125mm thick concrete floor slab grade con.3.

16. DAMP PROOF COURSES
Provide and lay damp proof courses as appropriate in compliance with BS6515 in heavy duty polythene with embossed faces, or equivalent to be used in horizontal dpcs and cavity trays.
DPC to inner leaf of cavity walling and internal walls built from a foundation to be linked with damp proof membrane in floor slab.
D.P.C. to be positioned minimum 150mm above external ground/path level.

35. LINTELS
 Pressed steel lintels to be Catnic, I.G. or Keystone – see opening schedule for details.
 All lintels to comply with BS5977 and to be installed in strict accordance with manufacturers instructions.
 End bearing of not less than 150mm each end.
 Provide cavity trays over lintels in external walls.
 Cavity trays to be drained with proprietary weep vents.

OPENING SCHEDULE						
No	Position	Width	Height	Lintel Ref	Length	Background Ventilators
1	S4ED	3000	3000	SBL244	3344	—
2	"	944	2100	SBL200 H5	1200	—

Assess the risks and take appropriate precautions for the following:

1. Ensure the safety of all visitors to the site
2. Truss and beam handling.

11/11/2016

A		

67 St. Peters Road, Upwell, Wisbech, Cambs PE14 9EJ
Telephone/Fax (01945) 772632 Mobile (07799) 833359
Email: gseaton-wellcreek@tiscali.co.uk
Directors: G A Seaton MBE Eng. ACIOB R I Seaton

Job Title

PROPOSED STORAGE SHED
ON PADDOCK LAND
EAST OF 64 LIME WALK
LONG SUTTON

FULL DETAILS

Drg No.	10/1/1629	Rev.
---------	-----------	------

A PRODUCT OF THE UNO RANGE ARCHITECT DAT. N° 7311

594 x 841mm

A