



EXTENT OF HIGHWAY ADOPTION

9.0M IDB BUILD EXCLUSION LIMIT

S104 ADOPTABLE FOUL WATER PIPE-RUN DIAMETER/GRADIENT

S104 ADOPTABLE FOUL MANHOLE

S104 ADOPTABLE FOUL RISING MAIN

S104 ADOPTABLE STORM WATER PIPE-RUN DIAMETER/GRADIENT

S104 ADOPTABLE STORM WATER MANHOLE

ADOPTABLE HEADWALL

1.5M MAINTENANCE STRIP

ADOPTABLE ROAD GULLY

ATTENUATION BASIN GREEN RESURFACE BLUE: EARTHWORKS

POROUS PAVING

CELLULAR STORAGE TANK

UNDERDRAINED SWALE

FILTER TRENCH

FINISHED FLOOR LEVEL

PROPOSED RETAINING WALL (LEVEL RETAINED)

PROPOSED GRAVEL BOARD (MAX-450MM)

1500 1/150 1.000

4500 1/400 1.000

1.5m

FFL 3.450

RTW900

GB450

Copyright Barter Hill Partnership. This drawing shall not be copied in whole or part without the written permission of The Barter Hill Partnership.

Notes

1. PRELIMINARY DRAWING: This drawing should be read as a PRELIMINARY issue and should NOT be used for construction under any circumstances.

1. All adoptable drainage to be installed/constructed to 'Code For Adoption' standards and in accordance with Anglian Water's additions and deletions document.

2. Connections to the existing sewers shall be subject to the approval of Anglian Water and shall be carried out by a contractor approved by Anglian Water. The contractor shall comply with the requirements of Anglian Water with regards to submitting method statements, risk assessments etc for obtaining a 'permit to work' on the existing sewer.

3. Where drainage is to be adopted, manhole covers are to be permanently and visibly badged with the AW logo and the lettering 'SW' for surface water and 'FW' for foul water.

4. Where possible orientation of manhole access covers to be orthogonal with adjacent kerb line.

5. Manhole covers to be set flush with binder course on new road construction and raised to final levels when surface course is laid at later date.

6. Sulphate resisting cement and concrete products to be used for foul sewerage.

7. All pipes entering or leaving manholes shall be laid with their soffits level, unless shown or agreed otherwise.

8. Gully connections to be 150mm Dia at a gradient no flatter than 1 in 150 unless stated otherwise.

PROTECTION TO ADOPTABLE SEWERS:-

15. Type S bedding to be used in non-trafficked areas.

16. Type S bedding to be used in trafficked areas where the cover to the crown of the sewer is greater than or equal to 1200mm.

17. Concrete Slab Protection to be provided in trafficked areas where the cover to the crown of the sewer is less than 1200mm.

F	Revised to suit new site layout 202 P8 and IDB comments.	NR	JR	27/07/23
E	Redline boundary amended fronting plots 23-26. Site access culvert design revised.	NR	JR	21/07/23
D	Site access culvert detail revised to suit IDB comments. Culvert long section added.	NR	JR	12/07/23
C	Foul drainage revised to suit Phase 2. Amended to suit site layout 202 P4.	NR	JR	14/02/23
B	Extent of adoptable highway boundary amended.	NR	JR	17/11/22
A	Extent of adoptable highway boundary added to drawing.	NR	JR	10/11/22
-	Planning issue.	NR	JR	24/10/22

Rev.	Description	By	Chk.	Date

barterhill

Barter Hill Partnership Limited
Greenway Business Centre
Greenway
Harlow Business Park
Essex CM19 5QE
t: 01279 430888
e: mail@barterhill.co.uk

Consulting Structural & Civil Engineers

15 Meridian Way
Meridian Business Park
Norwich NR7 0TA
t: 01603 300360
e: mail@barterhill.co.uk

Client

Stinders Homes SPV1 Ltd

Project

Maggie Close,
Long Sutton

Drawing Title

Preliminary Drainage Strategy
Phase 1

Designed by	Drawn by	Checked by
NR	NR	JR

Scale @ A1	Date
1:500	October 2022

Drawing No.	Revision	Job Ref
8939-102-001	F	8939

Status

PLANNING ISSUE

Cad file	Contact Office
P:8939/Civils/Drawings/8939-102	Norwich