

CHURCH GREEN
LONDON ROAD
LANCASTER DRIVE

FOUNDATIONS.
Concrete strip foundations width to match existing 1m where subsoil is of a shrinkable nature,
Founds to be 250mm thick.Reinforced to soft spots as necessary

FLOOR.
Ground bearing floor slab.
150mm consolidated and blinded hardcore laid over removed vegetable soil.
to internal foundations.50mm Jablite insulation with 100mm upstand around edges.1200 Ploythene dpm linked to dpc.
100mm site concrete.50mm cement sand screed.

D.P.M
Provide 1200g Polythene DPM over floor insulation turned up at sides and linked to DPC.

D.P.C
Install Astos/High Load or similar dpc min 150mm above finished ground level and to sides of all openings in cavity walls.Tray d.p.c over all IG Lintels with weepholes to outer leaf.
Dpc,s to reveals to be insulated type, Damcore or similar.
Dpc to chimney above roof intersection to be of 2 courses of class B Engineering bricks..

STUDWORK.
100x38mm studs at 400mm max c-c Off 100x75mm sole plates and incorperating 2 rows of horizontal nogginns at 1/3 height
Doors and frames as indicated and clad both sides with 12.5 mm Plasterboard and skim.Fill void with Superglass insulation.


INSULATION.
100mm fibre glass between roof joists,100mm fibre glass across joists. Cavity wall insulation 65mm Superglass.
Loft hatch to be insulated.
All pipework outside insulated areas to be fully lagged with 12mm Neoprene foam.
Pvc vent trays to be incorporated between rafters at eaves

D.P.M
Provide 1200g Polythene DPM over floor insulation turned up at sides and linked to DPC.

D.P.C
Install Astos/High Load or similar dpc min 150mm above finished ground level and to sides of all openings in cavity walls.Tray d.p.c over all IG Lintels with weepholes to outer leaf.
Dpc,s to reveals to be insulated type, Damcore or similar.
Dpc to chimney above roof intersection to be of 2 courses of class B Engineering bricks..

WALL.
Outer leaf of Facing bricks,65mm cavity with 65mm Superglass insulation. 6no stainless steel wire ties per 1m sq and cavity closed at roof and reveals with blockwork.
Inner leaf of 100mm aeroated blocks maximum density 1100kg/m
Movement joints as indicated. Incorporate bricktor or similar expanded metal to mortar coarsing 215mm below all windows
Inner face of all blockwork rendered and skimmed. Internal faces of steel lintels to be covered with min 15mm lightweight plaster.
Cavity to extend min 150mm below dpc at perimeters.

Code 4 stepped lead
flashing at roof wall abutments and internal cavity stepped dpc tray.Trusses fixed to 75x100mm sw wall plate with galvanised ms truss clips.Plate strapped to blockwork with Catnic straps 1200x5mm at 2m c-c.Rafters strapped to gables with 1200x5mm straps spanning min 3no rafters and fixed to 75x38 mm noggins between rafters.Ceiling joists strapped likewise.
Water Tank supports To BS,5268 Part 3 19852 should consist of 150x25 T&G BOARDING on 2 No 75x47mm bearers 400mm apart over 2No 200x47mm bearers on 2 No 75x47mm runners over min of 4 No trusses,as close to node points as possible.All timber SC3 Graded
Flashings code 4 Lead at all roof wall/chimney abutments.
Area beneath roof tank to be uninsulated to prevent freezing.



TYPICAL SECTION

ROOF.
Tiles laid to manufacturers instructions and specification on sarking felt and tile battens 25x38mm. on Trussed Rafters designed and fabricated to BS.5268 at 600mm c-c
Braced together to BS.5268 1985 pt3. 100x25mm binders at joist and ridge nodes and at plane of truss webs.
Pitch as specified,contractors are reminded that where roofs have to join adjacent structures,the pitch Must be checked on site
Manufacturers details/dimensions to be checked on site before ordering

Deminishing trusses/layboards and valley trays or tiles to roof intersections and manufacturers compound truss as appropriate.

Diagonal bracing 100x25mm running from eaves to inner binders on top of ceiling joists and inner truss plane.75x100mm wall plates

Facia board offset 250mm from brickwork.6mm masterboard soffit with continuous Glidevale soffit vent strip. Equivalent to 25mm
Ridge ventilation where necessary to give equivalent of 10mm continuous gap full length of roof

GLAZING.
All windows double glazed with 28mm sealed units. All opening windows and doors to have full draft seals including the loft hatch, (loft hatch to be fitted with suitable fastening to compress seal)
Opening lights to give 1/20th floor area in ventilation
All glass to be Hardened or toughened to B.S 6262 with safety glass to B.S 6206 CLASS B.
All glazing in critical locations to be of a type unlikely to cause injury to people upon impact ,the following types as indicated
All glass lower than 1,500mm above floor,to doors adjacent side lights and windows

SOIL WASTES.
Sink wastes in 40mm dia PVC
Wastes exceeding 2m in length to be 50mm dia
~~All with 75mm deep seal~~ P traps.All wastes routed seperately to connect to svp. Svp's in 110mm dia pvc and terminating min 1000mm above opening windows.
Shower trays to be raised 100mm to allow access to trap
Branch connections from waste appliances to connect to discharge pipe either above or 200mm below wc connection
Connect to svp. Svp's in 110mm dia pvc and terminating min 1000mm above opening windows with baloon cover.and flashing collar as appropriate at roof junction

FIRST FLOOR.
Floor joists as indicated on drawing all timber SC3 graded.All joists at max 400mm c-c with ends having min 100mm bearing.
Joists parallel to walls, strapped to walls at max 2m c-c with 30x5x1200mm straps and fixed to softwood noggins between joists.
Spans over 2m to have Herringbone bracings at mid span in 38x 38mm timber or Catnic h/b.Spans over 4.5m same but at 1third c-c Double joists beneath all studwork partitions and fix together with 12mm dia coach bolts and washers at 1.5m c-c, and 150mm from ends.Incorporate joist size block bondings between joists where partitions are perpendicular to joist span.Treble joists to Stair trimmers,infills and ends fixed with M/S hangers.
Floor of 18mm Moisture resistant chipboard t&g with P.V.A glued joints and ducted for access to all pipework.Provide support noggins beneath all joints.


CEILINGS.
Ceilings of 12.5mm Plasterboard and skim or Artex finish through out to BS. 1230 part 1 with sealed and supported cross joints and timber noggins to edges of boards size 30x47mm.
Ramped ceilings to have foil backed plasterboard

CEILINGS.to integral garages.
Two layers of 12.5mm Plasterboard and skim or Artex finish.
All joints mocked/staggered

DAVID BROKER DESIGN SERVICES
2000 CONCEPT
COMPUTER AIDED DESIGN
ARCHITECTURE

CLIENT
R MARCHETTI

No 10 LANCASTER DRIVE LONG SUTTON



BLOCK PLAN 1=200

HEALTH AND SAFETY C.D.M REGULATIONS 1995
THE CLIENT/DEVELOPER AND BUILDING CONTRACTOR/SUB CONTRACTOR ARE ADVISED TO AQUAINT THEMSELVES WITH THE IMPLICATIONS AND REQUIREMENTS OF THIS BUILDING PROJECT

DRAWING/FILE No 582JRM1

PROJECT PROPOSED EXTENTION TO EXISTING DWELLING NOTES & DETAILS

SCALE	1=50 1=100
DATE	03/03/2001
DRAWN	M.D.BROKER
Issued	
Revisions	

DETERMINED PLAN


SOUTH HOLLAND DC
HOUSING & PLANNING
15 MAY 2001
H/1058/01

ARCHITECTURAL TECHNICIANS
DANBROOKE HOUSE STATION ROAD
WISBECH ST MARY
WISBECH CAMBS.PE13 4RW
Telephone 01945410421
Facsimile 01945410400


File: \\Archie\drive-c\WINDOWS\work\582JRM2.dwg Plotted: 1997-05-05 11:36:30

DAVID BROKER DESIGN SERVICES
2000 CONCEPT
COMPUTER AIDED DESIGN
ARCHITECTURE


CLIENT
J R MARCHETTI
No 10 LANCASTER DRIVE LONG SUTTON




EXISTING REAR ELEVATION




EXISTING SIDE ELEVATION




EXISTING FRONT ELEVATION




EXISTING SIDE ELEVATION



PROPOSED SIDE ELEVATION




PROPOSED REAR ELEVATION




PROPOSED SIDE ELEVATION




PROPOSED FRONT ELEVATION




PROPOSED GROUND FLOOR PLAN



PROPOSED FIRST FLOOR PLAN



EXISTING GROUND FLOOR PLAN



EXISTING FIRST FLOOR PLAN

CONDITIONAL APPROVALS.
Required for:
Non standard roof trusses.
The main Contractor will be responsible for obtaining and sub mitting for approval, Calculations from the truss manufacturer to the building inspector, before trusses are installed.

STORM DRAINS.
All drains as specified for soil drains to 1m cube rubble filled soakaways min 5m from buildings.
Gutters 110mm square line UPVC. Down pipes in 65mm dia. pvc.

MECHANICAL VENTILATION.
Bathrooms/Ensuites and WCs to have mechanical extractors giving min 15 litres sec extraction,ducted to open air.Kitchen/Utility rooms. to have extraction at a rate of 60litres sec(or ducted cooker hood at 30litres sec)
Rooms with no windows to have fans controlled via light switch with 15min overun facility
All habitable rooms to have background ventilation of 8,000mm sq and kitchen/utility,toilets/bathrooms 4,000mm sq.respectively (Provided by trickle vents in window heads).

ELECTRICS.
Electrical installation to comply with 16th Edition IEE wiring regulations.Note provide lighting in roof space for safe access and working to roof tanks(close to hatch).

SOIL DRAINS.
All drains in 110mm dia. pvc with flexible joints and laid to 1-40 falls in 150 mm pea gravel bed and surrounds.Cap trenches beneath driveway with 1:3:6 concrete.Sleeve all pipes through or under raft/walls with 150mm dia. pvc pipes. Bridge with 100x50mm pre stressed conc lintels
Inspection chambers of D.S.M.A type universal to suit manuf acturers instructions and installation details,for depth and dia.

HEALTH AND SAFETY C.D.M REGULATIONS 1995
THE CLIENT/DEVELOPER AND BUILDING CONTRACTOR/SUB CONTRACTOR ARE ADVISED TO AQUAINT THEMSELVES WITH THE IMPLICATIONS AND REQUIREMENTS OF THIS BUILDING PROJECT

DRAWING/FILE No 582JRM1
PROJECT PROPOSED EXTENTION TO EXISTING DWELLING

DETERMINED PLAN

SCALE	1=50 1=100
DATE	03/03/2001
DRAWN	M.D.BROKER
Issued	
Revisions	

SOUTH HOLLAND DC HOUSING & PLANNING
10 MAY 2001
Ref: 0580/01

ARCHITECTURAL TECHNICIANS
DANBROOKE HOUSE STATION ROAD
WISBECH ST MARY
WISBECH CAMBS.PE13 4RW
Telephone 01945410421
Facsimile 01945410400

DO NOT SCALE ALL DIMENSIONS TO BE VERIFIED ON SITE

THIS DRAWING AND DESIGN REMAINS THE COPYRIGHT OF DAVID BROKER AND MAY NOT BE REPRODUCED WITHOUT PERMISSION.

Plotted: 1997-05-08 11:03:32 | Plotter: HP DesignJet 650C | Drawing: c:\WINDOWS\work\582JRM2.dwg