

NCR SelfServ™ 25

Through-the-wall Cash Dispenser

Do you want your self-service network to be as versatile as possible?

YES

A small footprint that delivers outstanding accessibility, efficiency and versatility

The NCR SelfServ 25 is an exterior through-the-wall and vestibule ATM with a small footprint and complete hole-in-the-wall compatibility, ideal for locations where space is at a premium. Offering cash dispense and a range of revenue-generating services, the NCR SelfServ 25 will deliver your brand to the broadest possible audience in the broadest possible range of locations.

• Redefined availability

Real availability is about delivering the transactions that consumers want, where and when they need them. With new "self-healing" technology, easy-to-use service lead-through application, and front, rear and side service access, NCR SelfServ redefines availability.

• Informed manageability

NCR SelfServ provides best-in-class data for network management. Clear visibility to configurations, software versions and the activity levels of each module results in more accurate, timely management decisions and operational excellence.

• Committed responsibility

Low-energy LED lighting, 25% less cabling and reduced requirements for on-site service visits are just some of the ways we've lowered the carbon footprint of each ATM. NCR SelfServ will be a valuable asset in achieving the environmental goals for your business.

• Intuitive usability

NCR SelfServ enables consumers, cash-in-transit companies, branch staff and service engineers to become experts after the very first use, resulting in better operational efficiency, staff utilisation and consumer satisfaction.

• Intrinsic security

Incorporating a unique protected USB architecture and a range of antifraud and physical security solutions, NCR SelfServ reduces fraud risk and maintains the integrity of your self-service channel for you and your customers.



For more information, visit www.ncr.com,
or email financial@ncr.com.



Experience a new world of interaction

NCR SelfServ 25

Key Features

- Provides a broad range of services such as bill payment, funds transfer, mobile phone top-up, couponing and vouchers and mini-statements
- PCI compliant Encrypting PIN Pad
- High capacity cash dispenser
- 12.1" and 15" LCD touchscreen
- Card reader with built-in fraud prevention

Why NCR?

With over 125 years of experience and knowledge, NCR is a leading global provider of payments, assisted- and self-service solutions. NCR has been the global number one manufacturer of ATMs for more than 22 consecutive years. We help our clients around the world improve their customer interactions, implement change quickly and proactively, and transform their businesses to become leaders and change agents. We can help you, too.

Technical Specifications

PRODUCT DIMENSIONS

- | | | |
|-----------------|---------|------------|
| • HEIGHT | 1,498mm | (59.0") |
| • WIDTH | 704mm | (27.7") |
| Safe only | 553mm | (21.8") |
| • DEPTH | | |
| Standard sleeve | 1,301mm | (51.2") |
| Short sleeve | 1,187mm | (46.7") |
| • WEIGHT | | |
| CEN L safe | 593kg | (1,308lbs) |
| CEN III/IV safe | 711kg | (1,568lbs) |

CONSUMER INTERFACE

- Display - Choice of 12.1" or 15" LCD, FDK or touchscreen, optional privacy filter, sunlight readable displays
- Keyboard - EPP (PCI compliant), polycarbonate or stainless steel
- Card Reader - Smart Dip, IMCRW with Smart option, HiCo
- Integrated Media Entry and Exit Indicators (MEEI)
- Audio - Optional high quality public audio and/or sound jack with volume control
- Advert Panel - Standard or enhanced with backlight
- Barcode Reader - 2D Barcode supports both 1D and 2D documents

DISPENSER

- 2-4 cassettes, bunch presenter, retract and purge capability

PRINTERS

- Receipt Printer - 80mm 203dpi graphics thermal printer. Options - retract and capture, dual colour, dual roll and/or 2ST (two-sided thermal printing)
- Journal Printer - 80mm 203dpi graphics thermal printer

SECURITY

- USB Protection and Parts Validation. Options - Fraudulent Device Inhibitor, Enhanced Card Drive, Ink-staining, SolidCore for APTRA™, Camera NTSC, PAL or third party
- Uninterruptible Power Supply (UPS)
- Safes - CEN L, CEN 1, CEN III, CEN IV

SERVICING

- 264mm (10.4") LCD Graphical Operator Panel (rear load only)
- Front, rear and side service

OPERATING PLATFORM

- Intel® Conroe L440 2.0GHz 512MB - 2GB
- Core™ 2 Duo 2.13GHz 2GB
- 80GB or 160GB hard drive
- DVD and floppy disc drives

SOFTWARE

- Windows® XP Pro
- XFS 4.05 or later
- APTRA software suite

ADDITIONAL FEATURES

- Biometrics ready
- Contactless ready



Experience a new world of interaction

NCR SelfServ 25

NCR continually improves products as new technologies and components become available. NCR, therefore, reserves the right to change specifications without prior notice.

All features, functions and operations described herein may not be marketed by NCR in all parts of the world. Consult your NCR representative or NCR office for the latest information.

NCR SelfServ is either a registered trademark or trademark of NCR Corporation in the United States and/or other countries. All brand and product names appearing in this document are trademarks, registered trademarks or service marks of their respective holders.

© 2009 NCR Corporation Patents Pending

EB 5823UK-1009

www.ncr.com