LIME WALK - LONG SUTTON



Proposed External Materials

- ALLENBY MULTI
- ISSLINGTON STOCK
- WOOLWICH VINTAGE
- WEATHERED WREN (detail brick)

Garden walls to be built in facing brick to match main house
(refer to standard detail for wall design)

- MARLEY EDGEMERE INTERLOCKING CONCRETE SLATE (Smooth Grey)
- MARLEY EDGEMERE INTERLOCKING CONCRETE SLATE (Old English Dark Red)
- CEDRAL BOARDING (C50 Black) (refer to elevation drawings for locations

Windows & rear/side doors - White UPVC
Some houses with cladding to have black - refer to spec sheet
Front Doors - Black Composite (with white frame) - refer to spec sheet

House with dummy chimney(s) - These locations take precedent over house type drawings. C

DRAWING TO BE READ IN CONJUNCTION WITH EXTERNAL MATERIAL SPECIFICATION

External Surfaces

- Adoptable Road, footpaths & Shared/Parking Courts - Tarmac
- Private/Shared Drives / Car Parking Spaces - Block Paving
  Marshalls or equivalent keyblock in natural with charcoal paving denoting parking spaces.
  (Footpaths adjacent to Parking Spaces - Block paving in Charcoal)
- Communal & Private Footpaths - Riven Peak Grey Paving Slabs. (Bradstone or equivalent)

Scale : 1:200

0 5 10 15 20 30 40m

NOTES:

The details depicted on this drawing are the copyright to Seagate Homes and may not be reproduced without permission.This drawing must not be re-issued, loaned or copied without the consent. Errors omissions and discrepancies should be reported to the originator immediately.

All dimensions to be checked on site prior to construction or off-site fabrication by the Contractor, his Sub-contractor or Supplier.

Do not scale plans - use figure or grid dimensions where given.
Any deviation from the drawing is to be reported to the originator immediately.

IF IN DOUBT ASK !

N

Rev	Notes	Date	By

SEAGATE HOMES

Project: PROPOSED RESIDENTIAL DEVELOPMENT, LAND OFF LIME WALK, LONG SUTTON. PE12 9HG

Drawing: MATERIAL DISTRIBUTION PLAN

Drawn: DL Date: 19.03.25

Status: PLANNING Scale: 1:250 @A0

Drawing Number: LWLS-SH-PD-MP-1011 -