



Design and Access Statement

**PROPOSED DEMOLITION OF EXISTING DWELLING AND REPLACE WITH LARGER FAMILY DWELLING
80 WISBECH ROAD
LONG SUTTON
SPALDING
LINCS
PE12 9AQ**

This report's aim is to demonstrate how the design process has been established and created the thought process behind the planning application. The report outlines the provisions of a high standard of design with the inclusion of accessibility for all, whilst complying with planning legislation.

Design and Access Statement

1. Introduction: -

This Design and Access Statement supports the full application for the proposed demolition of existing dwelling and replace with larger family dwelling at 80 Wisbech Road, Long Sutton, Spalding, Lincs, PE12 9AQ.

2. Compliance with Planning Policies:-

National Planning Policy Framework

The National Planning Policy Framework sets out the Government's planning policies for England and how these are expected to be applied. It sets out the Government's requirements for the planning system only to the extent that is relevant, proportionate and necessary to do so. It provides a framework within which local people and their accountable councils can produce their own distinctive local and neighbourhood plans, which reflect the needs and priorities of their communities.

NPPF

Para.2 Applications should be determined in accordance with the development plan, unless material considerations indicate otherwise

Para.10 Presumption in favour of sustainable development

Para 12. Presumption in favour of sustainable development does not change the statutory status of the development plan as the starting point for decision making

Para 47. All applications for development shall be determined in accordance with the development plan, unless material considerations indicate otherwise.

Chapter 14. meeting the challenge of climate change, flooding and coastal change.

3. Use and amount:-

The site has ample private amenity space with the addition of a driveway that will be used for off road parking.

4. Design/Layout:-

For simplicity of construction, this application seeks to approve all of the client's requirements to allow the dwelling to be completed as they wish.

Foul water discharge:

Bio Disk Treatment Plant for foul water discharge, serving up to 9 people:

G140

Alexandra Design

Southfork Farm, Seadyke Bank, Murrow, Wisbech, Cambs, PE13 4SD

T: 07891175649 E: info.alexandradesign@gmail.com W: www.alexandradesign.co.uk

The Klargester BioDisc sewage treatment plant provides a reliable, efficient and environmentally safe solution to your sewage disposal needs perfect for domestic dwellings without access to mains drainage. Ideal for locations where discharge is to sub-surface irrigation (soakaway), or to a suitable watercourse where approved by the Regulator, and where a septic tank will not meet the required standards. The Klargester BioDisc is a packaged sewage treatment plant utilising Rotating Biological Contractor technology for small domestic applications. This process offers inherent cost and performance benefits with a low carbon footprint. In normal domestic situations the BioDisc will produce effluent qualities of 8mg/l BOD, 13mg/l SS, 4mg/l ammonia and 2mg/l phosphate.

Klargester BA-X Tank Features

- Low running and maintenance costs
- No noise, no odours
- Suitable for homes with up to 18 people
- Low profile covers for minimal visual impact
- Invert options to match the site
- Control panel issues an immediate alert when a problem occurs
- Single phase standard power supply
- Optional integral pump available
- Certified to European Standard EN - 12566-3
- CE marked

Technical

Population equivalent: 9

Max. Daily BOD: 0.54kg

Max. Daily Flow: 1.8m³

Overall Diameter: 1995mm

Inlet Invert Depth: 750mm

Depth Below Inlet Invert: 1400mm

Outlet Invert Depth: 1315mm

Overall Height: 2460mm

Empty Weight: 325kg

Standard Power Supply: 1 Phase

Full Load Current - Single Phase: 0.51amps

Sludge Return Pump Rating: 250W

Electrical Power Consumption: 682.55 KWH/Year

The water consumption of each dwelling hereby permitted should not exceed the requirement of 110 litres per person per day (as set out as the optional requirement in Part G of the Building Regulations 2010 and the South East Lincolnshire Local Plan, 2019). The person carrying out the work must inform the Building Control Body that this duty applies. A notice confirming the requirement for the water consumption has been met shall be submitted to the Building Control Body and Local Planning Authority, no later than five days after the completion of each dwelling.

Landscaping Scheme

-Silver Birch and Wild Cherry

--Native mixed species hedgerow

G140

Alexandra Design

Southfork Farm, Seadyke Bank, Murrow, Wisbech, Cambs, PE13 4SD

T: 07891175649 E: info.alexandradesign@gmail.com W: www.alexandradesign.co.uk

-70% hawthorn, 30% mixed species, blackthorn, hazel, field maple, holly 30-50cm in double staggered rows 5 plants per meter run planted to frontage and planted inside the 1.2m high timber post and rail fence to rear boundary. 1.8m close boarded fence to side boundaries.

5. Access:-

Site access

The existing access will be utilised for the replacement dwelling.

Inclusive access

The general topography of the site is level and will comply with Part M of the Building Regulations. The front door will have a level access threshold and all internal ground floor doors will include inward and outward opening doors to any W.C, allowing access throughout the ground floor area.

Fire appliance Turning

The close proximity of Wisbech Road allows the Fire brigade to gain access to the site should the event of a fire break out.