Contractors are responsible for checking all dimensions on site prior to work commencing.Due to areas of the structure being covered, unexposed or otherwise inaccessible the notes / specifications of existing materials are subject to confirmation of site when it is feasible to expose the relevant areas of construction. All material schedules are given in good faith and for pricing purposes only. It is the responsibility of the contractor to check their accuracy before ordering any materials. Remway Design accepts no responsibility for the accuracy of these material schedules.



VISUAL SCALE 1:100 @ a3



Elevation 01 - Front

1 : 100



Elevation 02 - Right

1 : 100

External Materials:

- Facing Brickwork - Olde Coachhouse by Traditional Brick and Stone. English Garden Wall Bond with every third to be a header course. Mortar to be buff coloured with sharp yellow/orange sand with flush 'bagged' finish

- Roof Covering to be Sandtoft Britslate Duchess Graphite and Sandtoft Greenwood Traditional Single Clay Pantile to low level roofs

- Aluminium Windows and Sliding Doors. Colour Graphite Grey RAL 7024

- Oak Timber Entrance Doors

- Black Metal Rainwater Goods with Rise and Fall Spike Brackets

55 Fengate | Moulton Chapel

Proposed Elevations

Drg No

2691 / 02 rev G

remway Design Ltd