Replace existing
Towel Ra

Bathroom
Room 19

Up

Existing Modern Plasterboard ceiling
To be removed,

Lower Landing
Room 40

Bedroom 2
Room 20

Sloped

Sloped

Bathroom
Rm 30

Replace existing
Towel Rail

En-Suite
Rm 36

DL 8.56

Up

Bedroom 7
Room 35

C'brd

Up

Up

Up

Up

Lower Hall
Landing
Room 47

Loft Hatch

Up

Hall Landing
Room 39

Upper Landing
Room 40

Room 46

Library
Rm 21

Remove Wall, Contractor To
Confirm Whether Load Bearing
Or Not & Report Back.

Bedroom 5
Room 29

Bedroom 4
Room 28

En-Suite
Rm 38

Up

Bedroom
Room 25

Bedroom 1
Room 22

Dressing Room
room 24

En-Suite
Rm 23

Areas Shaded to Have
New Floors Useing Timber
Planks From Rooms 16 & 17.



New Ceiling Rose CR3
450mm to Landing Areas
39 & 40



New Ceiling Rose CR21
535mm to Room 21



New Ceiling Rose CR9
690mm to Room 20 & 22



New Ceiling Rose CR3
450mm to Reaming Bedrooms

DO NOT SCALE

CONTRACT DETAILS

Proposed Refurbishment Of Seas End Hall.
Moulton Seas End. Spalding. PE12 6LB

For Mr M. Jarrett

DRAWING TITLE

Proposed First Floor
Plastering Details and New Flooring

SCALE 1:50			
DATE FEB 2025		DRAWN BY S.Andrews	
JOB NO.	PLOT NO.	SHEET NO.	REV
		PP/002	

1:50 0 2

Tele No. 07713003441
E-mail:-shayne@designandarchitectureltd.co.uk

ShayneAndrews@DesignAndArchitectureLtd.co.uk
Registered address:10a High Street, Market Deeping, PE6 8EB