



For information please see drawing on site and that shown from this drawing.

(c) Crown Copyright. All rights reserved. Licence Number AL100037075
The material contained in this drawing has been based upon the Ordnance Survey Map by permission of Ordnance Survey on behalf of the Controller of Her Majesty's Stationary Office.

LINCOLNSHIRE COUNTY COUNCIL

All Specification Clauses relating to S.38 construction works are taken from 'Development Road Specification & Construction Guide 2005' produced by Lincolnshire County Council.

BACK OF FOOTWAY LEVELS:
Please note that levels shown on the back of footway relate to a full faced kerb. Lincolnshire Highways require that the back of footway be lowered at vehicular crossings in accordance with detail drawing Ref.Cause 1.6(A).

KERB FACES:
Full-faced pcc kerb = 110mm
Full-faced blockwork kerb = 100mm
Vehicular Crossing = 25mm
Pedestrian Crossing = 25mm or flush if adj. tactile paving.

BLOCKWORK:
Blockwork areas are to be Marshalls 200x100x80mm blocks in Brindle colour with twin stretcher course around entire area.

Single stretcher course to be laid around all kerbs i.e. gutters and manhole covers.

PLANNING PERMISSION
15 FEB 2007
Ref. 0204/07

B	13/01/07	Plot 8 and Treatment plant changed.
A	15/10/06	Layout amended as requested by Architect.
	Date	Revisions

© copyright

Design Team

Stafford

STAFFORD I E
10 AXON, COMMERCE ROAD
PETERBOROUGH BUSINESS PARK
LYNCH WOOD
PETERBOROUGH, PE2 6LR
TEL: 01753 52288, FAX: 01753 22266, MOBILE: 07715 85245, E-MAIL: info@stafford.co.uk

Client

S & S DEVELOPMENTS Ltd.
SAND PITS FARM
WISBECH ROAD
LONG SUTTON
SPALDING
PE12 8AQ
Tel: 01406 362296
Fax: 01406 364546
E: rodney@rodneywilson3.wanadoo.co.uk

Job Title

Seas End Road
Moulton Seas End
Spalding
Lincs

DETERMINED

Drawing Title
Road Levels
PLAN

Date	DATE	Scale	1:500, 1:200	Drawn	TRS
Dwg.No.	1439-C6-19	Rev.	8383-103		B