Refer to RSK Drawing 40-14-01 For Continuation

N

318400N

318350N

318300N

318250N

Greystones

Tank

Drain

POS

2.8m

Substation to drain to soft.

BWB01

BWB02

BWB03

The details provided on this drawing are subject to comments by all the relevant approving authorities. Until such time as all comments have been received and incorporated onto the drawings, all the information provided and costings, are used at Allison Homes risk and no liability will be accepted by RSK. Scheme based on site plan L181/SITE/01 Rev I.

CIVIL / STRUCTURAL DESIGN RISK MANAGEMENT

Abnormal or unusual residual risks associated with the design outcomes shown on this drawing are:-

RSK LDE LTD has followed its Design Risk Management process for Hazard Elimination and Risk reduction in developing the designs shown on this drawing. Abnormal or unusual residual risks may be shown above where it is considered that such risk may not normally be expected by competent persons engaged on work of this nature or type.

LEGEND

- Extra Facings (measurement taken from 150mm below DPC)
- Double Damp
- Flag on Edge (Max 400mm)
- Extra Gravelboard
- +26.300 Proposed level
- +1:23 Drive/Garden Gradients
- Proposed Steps
- FFL 3.75 Finished Floor Level (FFL) relates to the finishing level of the concrete floor slab (typically 150mm above external levels)
- Banking works/Cross Fall (1 in 3 unless otherwise stated)
- +(2.57) Existing levels
- Porous Paving (design by specialists)

Notes:

1. The specification in all respects shall be in accordance with the Lincolnshire County Council Development Road and Sustainable Drainage Specification and Construction
2. Within the catchment of traditional drainage design, the minimum longitudinal fall for highways, without channel block shall be 1 in 150 and with channel blocks 1 in 250
3. General deterioration of the existing highway/footway/verges created through construction of the new Section 38 Development will be reinstated to the Development Road and Sustainable Drainage Specification and Construction at the developers' own cost at the agreement of the inspecting Development Management Officer.
4. No private surface water shall discharge onto the adoptable highway
5. No private structural features shall overhang the adoptable highway
6. No retaining walls exceeding 1.37 meters shall be within 3.66 meters of the highway boundary.

Rev.	Date	Amendment	Drawn.	Chkd.	Appd.
P10	21.05.24	Updated to suit latest layout Rev I	PO	MS	
P9	15.05.24	Updated to suit client comments received 10.05.24	LS	MS	
P8	18.04.24	Updated to suit latest site layout Rev H	DS	MS	
P7	25.07.23	Updated to suit clients comments received 18.07.23	LGS	MS	
P6	14.07.23	Updated to suit latest FFL's	LGS	MAR	
P5	06.12.22	Aquacell Units added	AP	MS	
P4	28.11.22	Updated to suit FFL's	KD	AP	
P3	14.07.22	Updated to suit clients mark up received 23.06.22	LGS	MAR	
P2	01.10.21	Updated to suit new layout dated 05.07.21 and to suit Lincolnshire County Council comments.	LGS	MAR	
P1	31.07.19	First Issue	JW	MAR	

RSK

LAND & DEVELOPMENT ENGINEERING LTD

Spring Lodge
172 Chester Road
Helsby
Cheshire, WA6 0AR
United Kingdom

Tel: +44 (0) 1928 726006
Fax: +44 (0) 1928 725633
Email: lde@rsk.co.uk
Web: www.rsk.co.uk

Client: Allison Homes

Project Title: Moulton Chapel Spalding

Status: DETAILED DESIGN

Drawing Title: External Works Sheet 2 of 2

Drawn	Date	Checked	Date	Approved	Date
JW	JUL 19	MAR	JUL 19		

Scale	Orig Size	Dimensions
1:250	A0	

Project No.: 881565

Drawing File:

Drawing No.: 40-14-02

Rev: P10

Scale 1:250

0 2.5 5 7.5 10 12.5m

File Location: L:\001_JOBS\LIVE JWO\ANM\1565 - MOULTON CHAPEL - SPALDING\ LGS\WORKFILES\T\GRAPH\PARTS\STRUCT\40-14 EXTERNAL WORKS.DWG