









CIVIL / STRUCTURAL DESIGN RISK MANAGEMENT				
Abnormal or unusual residual risks associated with the design outcomes shown on this drawing are:-				
RSK LDE LTD has followed its Design Risk Management process for Hazard Elimination and Risk reduction in developing the designs shown on this drawing. Abnormal or unusual residual risks may be shown above where it is considered that such risk may not normally be expected by competent persons engaged on work of this nature or type.				
Notes:				
General				
- All dimensions are in mm unless stated otherwise. - No works shall commence on site until all relevant technical approvals are in place and agreed in writing with the appropriate approval body, any works implemented prior to approval is at risk and is the responsibility of the Principal Contractor. - All adoptable drainage works shall comply with Sewers for Adoption 6th Edition and any Anglian Water amendments to that document. - Under any circumstances, the cutting of precast manhole ring should be avoided. Construction process and precast rings should be selected accordingly.				
Materials				
- All chamber covers and frames shall be heavy duty ductile iron, kitemarked and compliant with BS EN 124. All covers used in areas with vehicle access to be D400 classification and B125 in pedestrian areas. - All precast concrete chamber rings, covers slabs and seating rings to conform with BS EN 1917 and BS 5911-3 and shall be installed in accordance with the manufacturer's recommendations and guidance. - The high strength concrete topping as shown on this drawing shall be a granolithic concrete complying with the relevant provisions of BS 8204-2. - All insitu concrete specified on this drawing shall be compliant with BS EN 206 and BS 8500. - For requirements respective to root protection to pipe lines, refer to the Landscape Architect's drawings. - All materials to be BS kitemarked. - This drawing to be read in conjunction with Design and Construction Guidance for foul and surface water sewers offered for adoption under the Code of adoption agreements for water and sewage companies operating wholly or mainly in England, approved version 2.0 10/03/2020.				



For pipework with less than 0.9m cover, structural engineer to be consulted to confirm adequate pipe protection measures

Where rigid pipes are used, a flexible joint shall be provided as close as is feasible to the outside face of any structure into which a pipe is built, within 150mm for pipe diameters less than 300mm. The design of the joints shall be compatible with any subsequent movement.
150 to 600 - effective length 0.6m
601 to 750 - 1.0m
Over 750 - 1.25m

Rev.	Date	Amendment	Drawn	Chkd.	Appd.
P5	25.07.23	Drawing updated to Client comments		MS	
P4	29.06.23	Drawing updated to latest drainage design		PO	MS

RSK
LAND & DEVELOPMENT ENGINEERING LTD

Spring Lodge
172 Chester Road
Helsby
Cheshire, WAG 0AR
United Kingdom

Tel: +44 (0) 1928 726006
Fax: +44 (0) 1928 725633
Email: lde@rsk.co.uk
Web: www.rsk.co.uk

Client

Allison Homes

Project Title

Moulton Chapel
Spalding

Status

DETAILED DESIGN

Drawing Title

Drainage Construction Details
Sheet 1 of 2

Drawn	Date	Checked	Date	Approved	Date
JW	JUL 19	MAR	JUL 19		
Scale	Orig Size	Dimensions			
NTS	A1				
Project No. 881565		Drawing File			
Drawing No. 40-07-01				Rev. P5	

