



WALLING.
Face brickwork to B.S. 3921:1974 for clay bricks and
B.S. 1871:1978 for calcium silicate bricks: 100mm
Tarmac Hemelike insulation block to form 215mm wall

GROUND FLOOR CONSTRUCTION.
Strip all vegetable soil and lay floor as follows: 100mm
ST4 mix concrete oversite on 1200q polythene D.P.M.,
lapped continuous with D.P.C. by min. 100mm : 150
blinded and consolidated hardcore

SURFACE WATER DRAINAGE.
115 dia. half round rainwater gutters to 63 dia. rainwater pipes 82.4 dia. underground pipes flexibly joined to a fall of 1:70 pipes bedded and surrounded in pea gravel and discharge to 1.2m dia. soakaway min. 5.0m from dwelling.

STANDARDS.
All materials to be new unless otherwise stated and all components and materials etc. to be used fitted and installed etc. in strict accordance with manufacturers instruction and relevant Code of Practice.
Materials shall conform to appropriate British Standard Specification or PPA Certificate or European Code equivalent.



PLOTS 1 & 7.

AMENDED PLAN

Ref. A3

5800
Planning & Development

28 APR 2003

Ref: 0728/04

[illegible]