HEDGE 'A'.
15Nº. Corylus avellana.
25Nº. Crataegus monogyna.
20Nº. Ilex aquifolium.
10Nº. Taxus baccata.
5Nº. Viburnum lantana.
10Nº. Viburnum opulus.

KEY.
- EXISTING VEGETATION TO BE RETAINED.
- NEW SPECIMEN TREE.
- NEW SHRUB BED.
- PROPOSED NATIVE HEDGEROW.
- GRASS SEEDING/LAWN.
- SPRING BULBS.

N

0 2 4 6 8 10 12 14

SCALE IN METRES.
(1:200 @ A1).

T14 T13 T12 T11 T10 T9 T8 T7 T6 T5 T4 T3 T2 T1

· CONCRETE ROADWAY.

Min. 9m EASEMENT.

1Nº Sorbus aucuparia.

~~1Nº Betula utilis~~

1Nº Liriodendron tulipifera 'Fastigiata'.

3Nº Taxus baccata fastigiata.

· BLOCK PAVERS.

1Nº Quercus robur

1Nº Prunus avium 'Plena'

GRAVEL

1Nº Sorbus aria 'Lutescens'.

· BLOCK PAVERS

1Nº Acer platinoides 'Drummondii'.

HEDGE 'E'.
10Nº Acer campestre.
10Nº. Corylus avellana.
10Nº. Cornus sanguineum.
165Nº. Crataegus monogyna.
150Nº. " laviegata.
75Nº. Prunus spinosa.
10Nº. Rosa canina.
10Nº. Viburnum opulus.
10Nº. Ilex aquifolium.

1Nº Malus sylvestris

1Nº Acer japonicum 'Vitifolium'

200Nº. Narcissus pseudo-narcissus.

6Nº + 5Nº. Lavandula angustifolia.

· GRAVEL DRIVE.

PATIO

1Nº Magnolia x soulangiana.

50Nº. Tulipa (mixed).

HEDGE 'B'.
75Nº. Crataegus monogyna.
75Nº. " laviegata.
10Nº. Ilex aquifolium.
15Nº. Prunus spinosa.
10Nº. Ulmus carpinifolia.

1Nº Pyrus communis

1Nº Prunus 'Taihaku'

1Nº Gleditsia triacanthos 'Sunburst'

1Nº Acer rubrum 'Scanlon'

Cedrus atlantica Glauca.

1Nº Malus sylvestris

3Nº Betula pendula

9m ~~8m~~ Easement for I.D.B.

· WOODLAND GARDEN.

Existing trees & shrubs to be retained & interplanted with the following:
1Nº. Cornus mas.
1Nº. Cornus kousa chinensis.
10Nº. Anthyrium filix-femina.
10Nº. Dryopteris filix-mas.
10Nº. Asplenium scolopendrium.
500Nº. Hyacinthoides non-scripta (seed).
200Nº. Galanthus nivalis.

HEDGE 'C'.
10Nº. Corylus avellana.
10Nº. Crataegus monogyna.
10Nº. Ilex aquifolium.
5Nº. Prunus spinosa.
5Nº. Taxus baccata.
10Nº. Viburnum opulus.

Special Pollen + Nectar mix (EN1) by Emorsgate Seeds (440m² @ 4gms/m²).

HEDGE 'D'.
70Nº. Crataegus monogyna.
60Nº. " laviegata.
20Nº Prunus spinosa.

N.B. This planting plan has been prepared to satisfy conditions 5, 6 & 16 of the planning consent for the development of the site for residential (H13-1269-21). It should be read in conjunction with the Post-Planting Maintenance document and the accompanying Planting Schedule.

This scheme has been prepared without the benefit of information or drawings showing the location of all underground services & easements. It is therefore the responsibility of the main contractor identify these prior to landscape operations on site.

Please do not scale from this drawing.

REVISION 'A' 23 Sept. '22.
- Hedgerows 'B' + 'C' set back min of 9m for I.D.B. easement. Section of Hedge 'E' to North also set back + realigned.
- Silver birch in N.E. corner removed as requested by I.D.B.

JONATHAN BIGGADIKE PG Dip LA CMLI
CHARTERED LANDSCAPE ARCHITECT

Project: Planting plan for residential development.
Clients: Will & Amy Ravell.
Location: Land at Eaugate Road, Moulton Chapel, Lincs, PE12 0XJ.
Drawing No: RAV/22/01. **Date:** July '22.

M: 07772 509351 E: jbiggadike@outlook.com
Trading as Dragonfly Building Conservation & Landscape Design Ltd.