975.00 mE | 1000.00 mE | 1025.00 mE | 1050.00 mE

2050.00 mN

2025.00 mN

2000.00 mN

N

1800mm CLOSE BOARDED FENCE

1200mm POST & RAIL FENCE PLANTED WITH MIXED NATIVE HEDGING

Fuel Bund

BRADSTONE HONEYMEDE LIMESTONE PAVING SLABS TO ALL PATIOS & FOOTPATHS

GRAVEL

Tarmac

Farmhouse

Shed

STN04

STN03

Ridge9.07

1200mm RECLAIMED BRICK WALLS

NEW VEHICULAR ACCESS TO L.C.C. SPECIFICATION

Grass

Bourne Road

EP

O/H Line

Rev.	Details	Date
A	Access amended.	30-10-17

©This drawing is copyright

Contractors must check all dimensions on Site. Only figured dimensions are to be worked from. Any foundation depths indicated are indicative only and must be in accordance with the consulting engineers design and/or agreed on site with the local authority during excavations. Any discrepancies in the information contained herein must be reported to the Architect before work proceeds.

Drawings to be read with Engineers calculations / report where applicable.

Note: If drawing details existing structures, we have not inspected woodwork or other parts of the structure which are covered, unexposed or inaccessible and we are therefore unable to report that any such part of the property is free from defect.

Project	Proposed Barn Conversion at Dovehirne Farm,Bourne Rd., West Pinchbeck
Drwg.	PROPOSED SITE PLAN
Scale	1:200 @ A2
Date	Sept 17
Drg No.	16-2340-P-06
Rev.	A

architects • designers • planning consultants

Old School House · 36 Boston Road · Sleaford
Lincolnshire · NG34 7EZ · Tel: 01529 414141
Fax : 01529 415757

clive wicks associates

©