PLANTING SCHEDULE

Location: Land off Milestone Lane, Pinchbeck, Lincs, PE11 3XR.

Client: Postland Developments Ltd.

N.B. This schedule is to be read in conjunction with the detailed planting proposals shown on Drawing No: MLP/22/01.

SPECIMEN TREES

No.	Botanical Name	Common Name	Size/Form	Root
2	Acer campestre	Field Maple	L.S.	B.R.
1	Acer ginnala	Maple variety	175-200/FT	B.R.
1	Alnus glutinosa	Alder	L.S.	B.R.
1	Alnus glutinosa 'Imperialis'	Alder	L.S.	B.R.
4	Betula pendula	Silver birch	Feathered	B.R.
1	Betula pubescens	Downy birch	Feathered	B.R.
1	Crataegus monogyna Albinoplena	Ornamental thorn	L.S.	B.R.
1	Ilex x meserveae 'Blue princess'	Holly	60-80cm	10L.
1	Malus 'Mokum'	Ornamental crab	L.S.	B.R.
5	Malus 'Evereste'	Ornamental crab	L.S.	B.R.
1	Photinia x fraseri Red Robin	-	60-80cm	C10.
1	Prunus 'Accolade'	Japanese cherry	L.S.	B.R.
1	Prunus avium	Flowering cherry	L.S.	B.R.
1	Prunus hillieri x *'Spire'*	Flowering cherry	L.S.	B.R.
1	Prunus fruticosa Globosa	Flowering cherry	L.S.	B.R.
1	Prunus padus	Bird cherry	L.S.	B.R.
3	Salix caprea	Goat willow	L.S.	B.R.
1	Sorbus aria 'Lutescens'	Whitebeam	L.S.	B.R.
2	Sorbus aucuparia	Rowan	L.S.	B.R.
1	Sorbus commixta 'Embley'	Rowan variety	L.S.	B.R.

1	Sorbus 'Joseph Rock'	Rowan	L.S.	B.R.

SPECIMEN SHRUBS

1	Leycesteria Formosa	Himalayan balsam	40-60cm	C3.

NATIVE HEDGING

120	Crataegus monogyna	Hawthorn	1+1	B.R.
120	Crataegus laviegata	Midland Hawthorn	1+1	B.R.
70	Ilex aquifolium	Holly	30-40cm	1L.

ORNAMENTAL HEDGES

73	Lavandula angustifolia 'Hidcote Blue'	Lavender	15-20 cm	2 L
28	Ligustrum ovalifolium	Round-leafed privet	1+1	B.R.
42	Osmanthus x Burkwoodii	-	20-30cm	C3.

CLIMBERS

2	Jasminum nudiflorum	Winter jasmine	60-80cm	C2.

BULB PLANTING

50	Narcissus pseudonarcissus	Daffodils.

HERBACEOUS PERENNIALS

7	Carex pendula	Sedge	30-40cm	C2

GRASS SEEDING

All grass seed to be supplied by Emorsgate Seeds. To be sown in accordance with the supplier's recommendations at a rate of 25 g/m².

EG22c Strong lawn grass mixture & clover.

PLANTING NOTES

All specimen trees to be tied to a 70-90 mm diameter, straight, peeled and pointed softwood tree stake using a 450 mm long *Supersoft* adjustable rubber tree tie. The tree stake should finish no higher than 600 mm above finished ground level. All tree planting to be protected from weed competition using proprietary mulch mats (1 m^2) or, alternatively, organic mulch to a depth of 50 mm.

All trees, shrubs and hedges shall be planted in a 300 mm minimum depth of open friable loam topsoil with a high organic content and free of builders' rubble.

The mixed native hedgerows are to be planted in two staggered rows 300 mm apart and at 450 mm centres. Hollies are to be planted in groups of not less than three. Blackthorn is to be planted in groups of not less than five.

Ornamental hedges to be planted in a single row at the following centres:

Lavandula angustifolia 'Hidcote Blue'	600mm.
Ligustrum ovalifolium	450mm.
Osmanthus x Burkwoodii	450mm.

Hedges to be mulched with woodchip to a minimum depth of 50 mm.

Bulbs to be planted at a depth of 75-100 mm (3-4 inches) in lawned amenity areas.

N.B. For any discrepancies or clarifications please contact the landscape architect direct.

Jonathan Biggadike PG Dip LA CMLI

Chartered Landscape Architect

Dragonfly Building Conservation & Landscape Design Ltd.

M: 07772 509351 E: jbiggadike@outlook.com