

Notes & Specification

- Pavement construction shown below shall be generally carried out in accordance with the current Highways Agency Specification for Highway Works (MCHW) in particular series 600, 700, 800, 900 and 1000 clauses, BS 7533-3 Pavements constructed with clay, natural stone or concrete pavers. The precast concrete paving and kerb association.
- Bituminous materials shall be to BS EN 13108.
- Granular sub-base has not been designed to carry construction traffic. Any surface damage to the sub-base due to the construction traffic shall be repaired to the satisfaction of the Engineer prior to the placement of the bound materials.
- The subgrade CBR shall be measured and reported to the Engineer to check the pavement design prior to construction.
- Turning movements of loaded heavy goods vehicles may cause movements of blocks if jointing sand is lost. It is important therefore that jointing sand is replenished periodically to avoid movement of blocks.
- Where pavements are constructed on subgrades that have volume change potential and where roots vegetation penetrate below the pavement formation, there is a risk that movement may occur resulting in deformation being evident in the surface, particularly during prolonged periods of dry weather. To reduce this risk, the thickness of the subbase shall be increased.

Concrete Block Paving Physical properties tested in accordance with BS EN 1338

Pavement Construction:

- 30mm minimum thickness 100x200 precast concrete paving blocks to BS EN 1338: laid in 45° herring bone pattern with apex pointing in main direction of traffic with jointing sand to BS 7533-3 Annex D vibrated into joints. Refer to landscape architect's drawing for block colour and type
- 30mm compacted thickness of sand laying course. Material Category 1 to BS 7533-3 Annex D.
- 100mm minimum compacted thickness of AC 32 dense base 40/60 des to clause 929 of IAN 101/07.
- 325mm minimum compacted thickness of type 1 granular sub-base to MCHW clause 803 compacted to MCHW clause 602 (see Table 7)
- Varied thickness of 6F5 Capping Layer Granular Fill in accordance with table 6/1 of the Specification for Highway Works, and compacted to table 6/4 of the Specification for Highway Works. Capping layer required to build up levels from the proposed mechanically stabilised subgrade improvement layers to the sub base formation level.
- Tensar Mechanically Stabilised Subgrade Improvement Layers**
(To be designed by specialist, design below based on preliminary Tensar proposal: AS D-55714 Surfleet Road, Pinchbeck Lincolnshire. Detail design to be confirmed).
- 150mm 6F5 Capping Layer Granular Fill in accordance with table 6/2 of the Specification for Highway Works, and compacted to table 6/4 of the Specification for Highway Works. *
- Tensar InterAZ A-65474 L2 (Proprietary geogrid layer to be designed by a specialist).
- 250mm 6F5 Capping Layer Granular Fill in accordance with table 6/1 of the Specification for Highway Works, and compacted to table 6/4 of the Specification for Highway Works.
- Tensar InterAX A-65474 L1 (Proprietary geogrid layer to be designed by a specialist).
- *Following installation of the mechanically stabilised layers the Contractor is to undertake CBR testing on the capping layer and report the results to the Engineer and Lincolnshire County Council Highways Inspector. To confirm if an additional geogrid is required prior to installing the subbase and bituminous bound layers.
- Proprietary Geocomposite/geotextile separating layer.

Formation/ Subgrade:

- Subgrade
- Sub grade deemed frost susceptible and assumed to exhibit a CBR of less than 2% Subject to measurement on site (see note 4).

Surface Compaction:

Prior to placement of the sub-base the formation shall be trimmed and rolled to MCHW clause 609. Any soft areas shall be brought to the attention of the Engineer for selection of appropriate remedial measures.

Surface Tolerance:

Laid blocks shall be subject to passes of a vibrating plate compactor with a minimum plate area of 0.25m² which gives an effective force per unit area of plate of 75 kN/m² with a frequency of 65-100Hz with a minimum mass of 200kg, or as required by the block manufacturer. Sufficient passes shall be made to produce a level and even surface.


Formation +20mm, -30mm
Sub-base +5mm, -10mm
Road Base +5mm, -10mm
Laying course +10mm, -5mm
Surface course +6mm, -6mm

Flatness of pavement 10mm under 3m straight edge. Difference in level at the joint of adjacent paving units, 2mm.

Pavement Loading Limits:

- This pavement is unable to withstand jockey wheel loads.
- This pavement has been designed as a category II pavement as defined in BS 7533-2, table 2, to accept up to 0.5 million standard axles. Typical applications include highways, predetermined areas subject to regular heavy traffic, car parks receiving occasional heavy traffic, footways regularly overridden by vehicular traffic.
- No allowance made for construction traffic.

Private Non-Permeable Block Paved Shared Driveway



E: mail@jppuk.net
W: jppuk.net

Notes & Specification

- Pavement construction shown below shall be generally carried out in accordance with the current Highways Agency Specification for Highway Works (MCHW) in particular series 600, 700, 800, 900 and 1000 clauses, BS 7533-3 Pavements constructed with clay, natural stone or concrete pavers. The precast concrete paving and kerb association.
- Granular sub-base has not been designed to carry construction traffic. Any surface damage to the sub-base due to the construction traffic shall be repaired to the satisfaction of the Engineer prior to the placement of the bound materials.
- The subgrade CBR shall be measured and reported to the Engineer to check the pavement design prior to construction.
- Turning movements of loaded heavy goods vehicles may cause movements of blocks if jointing sand is lost. It is important therefore that jointing sand is replenished periodically to avoid movement of blocks.
- Where pavements are constructed on subgrades that have volume change potential and where roots vegetation penetrate below the pavement formation, there is a risk that movement may occur resulting in deformation being evident in the surface, particularly during prolonged periods of dry weather. To reduce this risk, the thickness of the subbase shall be increased.

Concrete Block Paving Physical properties tested in accordance with BS EN 1338

Pavement Construction:

- 30mm minimum thickness 100x200 precast concrete paving blocks, suitable for use in permeable paved areas. To be installed strictly in accordance with manufacturers requirements. Landscape Architect to confirm block colour and laying pattern.
- 30mm thick laying course. (No fines)
- Geosynthetic filter with 300mm laps.
- 225mm minimum compacted thickness of granular coarse graded aggregate material.
- Impermeable membrane. To be laid with nominal 1500 fall towards outfall. Impermeable membrane to be wrapped over all sides of the permeable paving area.
- Varied thickness of 6F5 Capping Layer Granular Fill in accordance with table 6/1 of the Specification for Highway Works, and compacted to table 6/4 of the Specification for Highway Works. Capping layer required to build up levels from the proposed mechanically stabilised subgrade improvement layers to the sub base formation level.
- Tensar Mechanically Stabilised Subgrade Improvement Layers**
(To be designed by specialist, design below based on preliminary Tensar proposal: AS D-55714 Surfleet Road, Pinchbeck Lincolnshire. Detail design to be confirmed).
- 150mm 6F5 Capping Layer Granular Fill in accordance with table 6/2 of the Specification for Highway Works, and compacted to table 6/4 of the Specification for Highway Works. *
- Tensar InterAZ A-65474 L2 (Proprietary geogrid layer to be designed by a specialist).
- 250mm 6F5 Capping Layer Granular Fill in accordance with table 6/1 of the Specification for Highway Works, and compacted to table 6/4 of the Specification for Highway Works.
- Tensar InterAX A-65474 L1 (Proprietary geogrid layer to be designed by a specialist).
- *Following installation of the mechanically stabilised layers the Contractor is to undertake CBR testing on the capping layer and report the results to the Engineer and Lincolnshire County Council Highways Inspector. To confirm if an additional geogrid is required prior to installing the subbase and bituminous bound layers.
- Proprietary Geocomposite/geotextile separating layer.

Formation/ Subgrade:

- Subgrade
- Sub grade deemed frost susceptible and assumed to exhibit a CBR of less than 2% Subject to measurement on site (see note 4).

Surface Compaction:

Prior to placement of the sub-base the formation shall be trimmed and rolled to MCHW clause 609. Any soft areas shall be brought to the attention of the Engineer for selection of appropriate remedial measures.


Laid blocks shall be subject to passes of a vibrating plate compactor with a minimum plate area of 0.25m² which gives an effective force per unit area of plate of 75 kN/m² with a frequency of 65-100Hz with a minimum mass of 200kg, or as required by the block manufacturer. Sufficient passes shall be made to produce a level and even surface.

Tolerance of the surface shall be :-
Surface Course ± 6mm
Laying Course ± 20mm
Sub-base ± 20mm
Formation +20mm, -30mm
Differences in levels at the joints of adjacent paving units not greater than 2mm.

Pavement Loading Limits:

- This pavement is unable to withstand jockey wheel loads.
- This pavement is designed to Traffic Category 3 - areas subject to car, light van and motorcycle access, in accordance with Interpave Guide to the design and construction of concrete block permeable pavements 7th Edition.
- No allowance made for construction traffic.

Private Permeable Block Paved Single Driveway




Notes and specification for permeable block paving

- Permeable block paving construction shall generally be carried out in accordance with the current Highways Agency Specification for Highway Works (MCHW) and BS7533. Guide to the design, construction and manufacture of concrete block permeable pavements produced by Interpave.
- The coarse graded aggregate subbase has not been designed to carry construction traffic. It is vital that subbase is kept free from traffic and construction debris. If the subbase is required to be used for construction traffic, the Engineer shall be consulted prior to trafficking.
- Due to the nature of the coarse graded aggregate, the Contractor shall construct a trial area (min. 10mx10m) and test typical construction plant on this area to determine suitability. The Contractor shall consult with all sub-contractors to ensure they are satisfied their plant can be used on the subbase materials prior to construction.
- Coarse graded aggregate shall comply with BS EN 13242 and shall be designated Type 4/20 and shall meet the following physical properties:-

Sieve Size mm (nearest UK equivalent)	Coarse aggregate 40mm to 5mm	Properties
40	100	Grading
31.5	98 - 100	Fines Content
20	90 - 95	Shape
10	75 - 79	Resistance to Fragmentation
5	0 - 15	Durability: Water Absorption to BS EN 1097-6:2000, Clause 7 - for WA > 2%
2	0 - 5	Magnesium Sulphate Soundness
		Resistance to Wear
		Acid Soluble Sulphate Content
		Aggregates other than air-cooled blast-furnace slag
		Air-cooled blast-furnace slag
		Total Sulphur
		Aggregates other than air-cooled blast-furnace slag
		Air-cooled blast-furnace slag
		Volume Stability of Blast-Furnace and Steel Slags
		Free from deleterious silicate and iron disintegration in accordance with BS EN 13242 - 2002, 6.4.2.2
		Leaching of Contaminants
		100% Fines
		Other Properties

- Bituminous materials shall be to BS EN 13108.
 - The laying course material shall comply with the requirements of a material of type 2/6.3 Gc 80/20 to BS EN 13242, graded as follows:-
- | BS Sieve Size (mm) | Percentage passing by mass (%) |
|--------------------|--------------------------------------|
| 14 | 100 |
| 10 | 98 - 100 |
| 6.3 | 85 - 92 |
| 2.0 | 0 - 20 |
| 0.75 | 0 - 5 |
| 0.075 | 0 - 2 (BS EN 12620 fines category 1) |
- A trial area (minimum 10m x 10m) shall be laid with blocks and compacted to determine suitability of material in order to achieve the required levels.
- Precast concrete blocks shall comply with BS EN 1338 and shall be suitable for use for permeable pavements. Precast concrete blocks shall have the following physical properties:-
- | Tensile Splitting Strength & Failure Level | Abrasion | Skid/Slip (pendulum value) | Freeze/Thaw (kg/m³) |
|---|----------|----------------------------|---------------------|
| No block shall have a tensile strength less than 3.6mPa for a failure load less than 250N/mm. | ≤ 20 | 45 min | ≤ 1.0 |
- The geosynthetic filter shall be a polyethylene mono-filament with the following properties:-
- | Mass / unit area | EN 965 | greater than 100g/m² |
|---------------------|--------------|------------------------------------|
| Tensile strength | EN ISO 10318 | Longitudinal - greater than 25kN/m |
| Elongation at break | EN ISO 10318 | Transverse - greater than 25kN/m |
| Opening size | EN ISO 15904 | Longitudinal - less than 25% |
| Water permeability | EN ISO 11058 | Transverse - less than 25% |
| | | Approx. 0.45mm |
| | | greater than 200 x 100 x 3 m/s |
- The tensile properties of the material shall be measured in accordance with EN ISO 10318. All vehicles shall be prevented from trafficking directly over the material. The material shall be protected from ultra violet light.
 - Where pavements are constructed on subgrades that have volume change potential and where roots vegetation penetrate below the pavement formation, there is a risk that movement may occur resulting in deformation being evident in the surface, particularly during prolonged periods of dry weather. To reduce this risk, the thickness of the subbase shall be increased.

Precast Concrete Footway Edging Detail



General Notes

- All dimensions are in metres unless otherwise stated.
- All levels are in metres.
- This drawing is to be read in conjunction with all relevant Engineers and Architect's drawings, Specifications, Reports and Engineering Details.
- Do not scale from this drawing.

Health, safety & the environment

In accordance with the Construction (Design and Management) Regulations 2015, the designs and details on this drawing have been the subject of a Designers Risk Assessment, to identify risks in the construction, use, or demolition of the scheme. It is not considered necessary for Designers to highlight obvious and/or common risks (such as deep excavations, manual handling and working around heavy plant) which Contractors should be familiar with, and be able to control by good management and site practice.

So far as is reasonably practicable, the risks inherent in the design have been eliminated. Where it has been considered that elimination of a risk (or part of a risk) is not reasonably practicable, it has been reduced.

This drawing has been based/developed using the following external drawings

Type	Company	Drawing date	Drawing title	Date received	Rev
Site Layout	JGA	02.05.2023	23001_1000-P02 GS-S00 Layout	02.05.2023	P02
Topographical survey	EMF	July 2022	1021_Pinchbeck Topographical Survey_Final	04.03.2023	P05
Utilities and Drainage survey	Survey Solutions	26.06.2023	48518NGUS-01 & 02	26.06.2023	B

GEOGRID REQUIRED TO ALL PAVED AREAS - TO BE DESIGNED BY A SPECIALIST

Table 1: Permeable Paving Construction Capping Thickness

- Where CBR values are less than 2% possible requirement for additional capping material and/or geogrid reinforcement subject to specialist design

CBR Value (%)	Total capping thickness required (mm)
Less than 2%	subgrade improvement *
2% - 3%	350
3% - 4%	250
4% - 5%	200
Greater than 5%	150

Table 2: Standard (non-permeable) Paving Construction Sub-base Thickness

CBR Values	Minimum thickness (mm) of sub-base (consolidated in accordance with MCHW Volume 1 clause 801, table 8/4)
Less than 2%	Subgrade requires improvement
2-3%	325
3-5%	250
5-7%	150
7-20%	100

Preventive measure	Description	Surface or sub-surface	Substrate	Prevented
Surface cleaning	Remove loose material, debris, dirt and other matter from the surface at least before laying the concrete, and maintain the surface clean and free from debris.	Surface	Yes	Yes
Managing vegetation	Control between blocks (use non toxic bonding agents) and prevent roots from penetrating the surface.	Surface	Yes	Yes
Re-capping	For continuous concrete permeable surfaces, replace ground units as necessary.	Sub-surface	Yes	Yes
Prevention of root growth	For continuous concrete permeable surfaces, replace ground units as necessary.	Sub-surface	Yes	Yes
Prevention of root growth	For continuous concrete permeable surfaces, replace ground units as necessary.	Sub-surface	Yes	Yes
Prevention of root growth	For continuous concrete permeable surfaces, replace ground units as necessary.	Sub-surface	Yes	Yes

Permeable Block Paving Maintenance Schedule

Rev B Driveway construction amended to show Tensar preliminary mechanical stabilised layers. Taken from Tensar preliminary proposal: AS D-55714. By SH Checked LC 12.09.2023
Rev A Drawing updated in accordance with Burmor Construction comments received 14.03.2023. By AD Checked LC 31.03.2023

- Infrastructure Design
- Geotechnical & Environmental
- Structural Engineering
- Surveying
- Development Planning
- Professional Advice

Drawn By:	AD	Client	Burmor Construction
Chkd By:	LC	Project	Land East of Surfleet Road Pinchbeck
Scale @ A0:	NTS	Title	Private Pavement Construction Details
Date:	February 2023		
Status:	FOR PLANNING		
Project No.:	26043	Drawing No:	120

Rev: B

