

JPP Consulting Ltd		Page 1
4, Ironstone Way Brixworth Northampton, NN3 9UD	Surfleet Road Pinchbeck	
Date 13/04/2023 File 26043 - SW and FW.MDX	Designed by JPP Checked by LC	
Innovyze Network 2019.1		

STORM SEWER DESIGN by the Modified Rational Method

Design Criteria for SW

Pipe Sizes STANDARD Manhole Sizes STANDARD

FSR Rainfall Model - England and Wales

Return Period (years)	2	PIMP (%)	100
M5-60 (mm)	19.000	Add Flow / Climate Change (%)	0
Ratio R	0.400	Minimum Backdrop Height (m)	0.000
Maximum Rainfall (mm/hr)	50	Maximum Backdrop Height (m)	0.000
Maximum Time of Concentration (mins)	30	Min Design Depth for Optimisation (m)	1.200
Foul Sewage (l/s/ha)	0.000	Min Vel for Auto Design only (m/s)	1.00
Volumetric Runoff Coeff.	0.750	Min Slope for Optimisation (1:X)	500

Designed with Level Soffits

Time Area Diagram for SW

Time (mins)	Area (ha)	Time (mins)	Area (ha)	Time (mins)	Area (ha)
0-4	0.086	4-8	0.525	8-12	0.120

Total Area Contributing (ha) = 0.731

Total Pipe Volume (m³) = 113.238

Network Design Table for SW

« - Indicates pipe capacity < flow

PN	Length (m)	Fall (m)	Slope (1:X)	I.Area (ha)	T.E. (mins)	Base Flow (l/s)	k (mm)	n	HYD SECT	DIA (mm)	Section Type	Auto Design
1.000	32.756	0.100	327.0	0.074	5.00	0.0	0.600		o	375	Pipe/Conduit	
1.001	66.047	0.202	327.0	0.199	0.00	0.0	0.600		o	375	Pipe/Conduit	
1.002	10.537	0.033	319.3	0.062	0.00	0.0	0.600		o	375	Pipe/Conduit	

Network Results Table

PN	Rain (mm/hr)	T.C. (mins)	US/IL E (m)	I.Area (ha)	E Base Flow (l/s)	Foul (l/s)	Add Flow (l/s)	Vel (m/s)	Cap (l/s)	Flow (l/s)
1.000	50.00	5.55	3.110	0.074	0.0	0.0	0.0	1.00	110.1	10.0
1.001	50.00	6.65	3.010	0.273	0.0	0.0	0.0	1.00	110.1	37.0
1.002	50.00	6.83	2.808	0.335	0.0	0.0	0.0	1.01	111.4	45.4

©1982-2019 Innovyze

JPP Consulting Ltd

4, Ironstone Way
Brixworth
Northampton, NN3 9UD

Date 13/04/2023
File 26043 - SW and FW.MDX

Innovyze

Surfleet Road
Pinchbeck

Designed by JPP
Checked by LC

Network 2019.1

Page 3

Micro
Drainage

Manhole Schedules for SW

MH Name	MH CL (m)	MH Depth (m)	MH Connection	MH Diam., L*W (mm)	PN	Pipe Out Invert Level (m)	Diameter (mm)	PN	Pipes In Invert Level (m)	Diameter (mm)
1	4.600	1.490	Open Manhole	1350	1.000	3.110	375			
2	4.450	1.440	Open Manhole	1800	1.001	3.010	375	1.000	3.010	375
3	4.185	1.377	Open Manhole	1350	1.002	2.808	375	1.001	2.808	375
HW1	3.625	0.850	Open Manhole	500	1.003	2.775	375	1.002	2.775	375
HW2	3.625	0.725	Junction		2.000	2.900	500			
HW3	3.625	0.804	Open Manhole	500	2.001	2.821	375	2.000	2.821	500
HW4	3.625	0.850	Open Manhole	1350	2.002	2.775	375	2.001	2.775	375
4	4.205	1.290	Open Manhole	1500	3.000	2.915	225			
5	4.050	1.223	Open Manhole	1350	3.001	2.827	225	3.000	2.827	225
HW5	3.625	0.850	Open Manhole	1200	3.002	2.775	225	3.001	2.775	225
HW6	3.625	1.000	Open Manhole	1350	1.004	2.625	450	1.003	2.625	375
								2.002	2.625	375
								3.002	2.625	225
6 (FC)	3.915	1.300	Open Manhole	1800	1.005	2.615	150	1.004	2.615	450
HW7	2.975	0.595	Open Manhole	500	1.006	2.380	500	1.005	2.530	150
Ditch	2.840	0.511	Open Manhole	0		OUTFALL		1.006	2.329	500

MH Name	Manhole Easting (m)	Manhole Northing (m)	Intersection Easting (m)	Intersection Northing (m)	Manhole Access	Layout (North)
1	524553.640	326628.948	524553.640	326628.948	Required	
2	524541.856	326598.385	524541.856	326598.385	Required	
3	524510.103	326540.472	524510.103	326540.472	Required	
HW1	524501.150	326534.916	524501.150	326534.916	Required	
HW2	524481.203	326606.293			No Entry	

©1982-2019

Innovyze

JPP Consulting Ltd		Page 6
4, Ironstone Way Brixworth Northampton, NN3 9UD	Surfleet Road Pinchbeck	
Date 13/04/2023 File 26043 - SW and FW.MDX	Designed by JPP Checked by LC	
Innovyze Network 2019.1		

Area Summary for SW

Pipe Number	PIMP Type	PIMP Name	PIMP (%)	Gross Area (ha)	Imp. Area (ha)	Pipe Total (ha)
1.000	-	-	100	0.074	0.074	0.074
1.001	-	-	100	0.199	0.199	0.199
1.002	-	-	100	0.062	0.062	0.062
1.003	-	-	100	0.041	0.041	0.041
2.000	-	-	100	0.211	0.211	0.211
2.001	-	-	100	0.000	0.000	0.000
2.002	-	-	100	0.000	0.000	0.000
3.000	-	-	100	0.110	0.110	0.110
3.001	-	-	100	0.034	0.034	0.034
3.002	-	-	100	0.000	0.000	0.000
1.004	-	-	100	0.000	0.000	0.000
1.005	-	-	100	0.000	0.000	0.000
1.006	-	-	100	0.000	0.000	0.000
				Total	Total	Total
				0.731	0.731	0.731

Simulation Criteria for SW

Volumetric Runoff Coeff	0.750	Additional Flow - % of Total Flow	0.000
Areal Reduction Factor	1.000	MADD Factor * 10m³/ha Storage	1.000
Hot Start (mins)	0	Inlet Coefficient	0.800
Hot Start Level (mm)	0	Flow per Person per Day (l/per/day)	0.000
Manhole Headloss Coeff (Global)	0.500	Run Time (mins)	60
Foul Sewage per hectare (l/s)	0.000	Output Interval (mins)	1

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	1	Number of Storage Structures	1	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Profile Type	Summer
Return Period (years)	2	Cv (Summer)	0.750
Region	England and Wales	Cv (Winter)	0.840
M5-60 (mm)	19.000	Storm Duration (mins)	30
Ratio R	0.400		

©1982-2019 Innovyze

JPP Consulting Ltd		Page 7
4, Ironstone Way Brixworth Northampton, NN3 9UD	Surfleet Road Pinchbeck	
Date 13/04/2023 File 26043 - SW and FW.MDX	Designed by JPP Checked by LC	
Innovyze	Network 2019.1	

Online Controls for SW


Hydro-Brake® Optimum Manhole: 6 (FC), DS/PN: 1.005, Volume (m³): 3.6

Unit Reference	MD-SHE-0073-2000-0600-2000
Design Head (m)	0.600
Design Flow (l/s)	2.0
Flush-Flo™	Calculated
Objective	Minimise upstream storage
Application	Surface
Sump Available	Yes
Diameter (mm)	73
Invert Level (m)	2.615
Minimum Outlet Pipe Diameter (mm)	100
Suggested Manhole Diameter (mm)	1200

Control Points	Head (m)	Flow (l/s)	Control Points	Head (m)	Flow (l/s)
Design Point (Calculated)	0.600	2.0	Kick-Flo®	0.397	1.7
Flush-Flo™	0.177	2.0	Mean Flow over Head Range	-	1.7

The hydrological calculations have been based on the Head/Discharge relationship for the Hydro-Brake® Optimum as specified. Should another type of control device other than a Hydro-Brake Optimum® be utilised then these storage routing calculations will be invalidated

Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)	Depth (m)	Flow (l/s)
0.100	1.9	1.200	2.7	3.000	4.2	7.000	6.3
0.200	2.0	1.400	2.9	3.500	4.5	7.500	6.5
0.300	1.9	1.600	3.1	4.000	4.8	8.000	6.7
0.400	1.7	1.800	3.3	4.500	5.1	8.500	6.9
0.500	1.8	2.000	3.5	5.000	5.3	9.000	7.1
0.600	2.0	2.200	3.6	5.500	5.6	9.500	7.3
0.800	2.3	2.400	3.8	6.000	5.8		
1.000	2.5	2.600	3.9	6.500	6.0		

JPP Consulting Ltd		Page 9
4, Ironstone Way Brixworth Northampton, NN3 9UD		
Surfleet Road Pinchbeck		
Date 13/04/2023 File 26043 - SW and FW.MDX		
Designed by JPP Checked by LC		
Innovyze		Network 2019.1

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for
SW

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	1.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs 0 Number of Offline Controls 0 Number of Time/Area Diagrams 0
Number of Online Controls 1 Number of Storage Structures 1 Number of Real Time Controls 0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.400
Region	England and Wales	Cv (Summer)	0.750
M5-60 (mm)	19.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm) 300.0
Analysis Timestep 2.5 Second Increment (Extended)
DTS Status OFF
DVD Status ON
Inertia Status ON

Profile(s) Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440
Return Period(s) (years) 1, 2, 30, 100
Climate Change (%) 0, 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	15 Winter	1	+0%	100/15 Summer				3.199
1.001	2	15 Winter	1	+0%	100/15 Summer				3.150
1.002	3	15 Winter	1	+0%	30/15 Winter				2.982
1.003	HW1	15 Winter	1	+0%	100/15 Summer				2.905
2.000	HW2	15 Winter	1	+0%					3.060
2.001	HW3	15 Winter	1	+0%					2.957
2.002	HW4	15 Winter	1	+0%					2.897
3.000	4	15 Winter	1	+0%	30/15 Summer				3.016
3.001	5	15 Winter	1	+0%	30/15 Summer				2.949
3.002	HW5	15 Winter	1	+0%	100/15 Summer				2.867
1.004	HW6	960 Winter	1	+0%	100/360 Winter				2.738
1.005	6 (FC)	960 Winter	1	+0%	2/480 Winter				2.741
1.006	HW7	960 Winter	1	+0%					2.424

©1982-2019 Innovyze

JPP Consulting Ltd		Page 10
4, Ironstone Way Brixworth Northampton, NN3 9UD	Surfleet Road Pinchbeck	
Date 13/04/2023 File 26043 - SW and FW.MDX	Designed by JPP Checked by LC	
Innovyze	Network 2019.1	

1 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for SW

PN	US/MH Name	Surcharged		Flooded		Pipe		Level Exceeded
		Depth (m)	Volume (m ³)	Flow / Cap.	Overflow (l/s)	Flow (l/s)	Status	
1.000	1	-0.286	0.000	0.10		9.5	OK	
1.001	2	-0.235	0.000	0.29		29.8	OK	
1.002	3	-0.200	0.000	0.44		35.4	OK	
1.003	HW1	-0.245	0.000	0.26		39.2	OK	
2.000	HW2	-0.565	0.000	0.04		26.6	OK	
2.001	HW3	-0.239	0.000	0.28		24.3	OK	
2.002	HW4	-0.253	0.000	0.23		24.3	OK	
3.000	4	-0.124	0.000	0.41		14.3	OK	
3.001	5	-0.103	0.000	0.57		18.2	OK	
3.002	HW5	-0.133	0.000	0.35		18.2	OK	
1.004	HW6	-0.337	0.000	0.02		2.2	OK	
1.005	6 (FC)	-0.024	0.000	0.15		2.0	OK	
1.006	HW7	-0.551	0.000	0.00		2.0	OK	

JPP Consulting Ltd		Page 11
4, Ironstone Way Brixworth Northampton, NN3 9UD	Surfleet Road Pinchbeck	
Date 13/04/2023 File 26043 - SW and FW.MDX	Designed by JPP Checked by LC	
Innovyze Network 2019.1		

2 year Return Period Summary of Critical Results by Maximum Level (Rank 1) for
SW

Simulation Criteria

Areal Reduction Factor 1.000	Additional Flow - % of Total Flow 0.000
Hot Start (mins) 0	MADD Factor * 10m³/ha Storage 1.000
Hot Start Level (mm) 0	Inlet Coefficient 0.800
Manhole Headloss Coeff (Global) 0.500	Flow per Person per Day (l/per/day) 0.000
Foul Sewage per hectare (l/s) 0.000	

Number of Input Hydrographs 0	Number of Offline Controls 0	Number of Time/Area Diagrams 0
Number of Online Controls 1	Number of Storage Structures 1	Number of Real Time Controls 0

Synthetic Rainfall Details


Rainfall Model	FSR	Ratio R 0.400
Region England and Wales Cv (Summer)	0.750	
M5-60 (mm)	19.000 Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep 2.5 Second Increment (Extended)	
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins) 15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440	
Return Period(s) (years) 1, 2, 30, 100	
Climate Change (%) 0, 0, 0, 40	

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	15 Winter	2	+0%	100/15 Summer				3.215
1.001	2	15 Winter	2	+0%	100/15 Summer				3.172
1.002	3	15 Winter	2	+0%	30/15 Winter				3.012
1.003	HW1	15 Winter	2	+0%	100/15 Summer				2.925
2.000	HW2	15 Winter	2	+0%					3.081
2.001	HW3	15 Winter	2	+0%					2.978
2.002	HW4	15 Winter	2	+0%					2.915
3.000	4	15 Winter	2	+0%	30/15 Summer				3.033
3.001	5	15 Winter	2	+0%	30/15 Summer				2.972
3.002	HW5	15 Winter	2	+0%	100/15 Summer				2.881
1.004	HW6	960 Winter	2	+0%	100/360 Winter				2.765
1.005	6 (FC)	960 Winter	2	+0%	2/480 Winter				2.769
1.006	HW7	720 Winter	2	+0%					2.425

©1982-2019 Innovyze

JPP Consulting Ltd		Page 13
4, Ironstone Way Brixworth Northampton, NN3 9UD	Surfleet Road Pinchbeck	
Date 13/04/2023 File 26043 - SW and FW.MDX	Designed by JPP Checked by LC	
Innovyze Network 2019.1		

30 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for SW

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	1.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	1	Number of Storage Structures	1	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.400
Region	England and Wales	Cv (Summer)	0.750
M5-60 (mm)	19.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440
Return Period(s) (years)	1, 2, 30, 100
Climate Change (%)	0, 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	15 Winter	30	+0%	100/15 Summer				3.313
1.001	2	15 Winter	30	+0%	100/15 Summer				3.288
1.002	3	15 Winter	30	+0%	30/15 Winter				3.187
1.003	HW1	15 Winter	30	+0%	100/15 Summer				2.998
2.000	HW2	15 Winter	30	+0%					3.150
2.001	HW3	15 Winter	30	+0%					3.049
2.002	HW4	15 Winter	30	+0%					2.976
3.000	4	15 Winter	30	+0%	30/15 Summer				3.193
3.001	5	15 Winter	30	+0%	30/15 Summer				3.102
3.002	HW5	15 Winter	30	+0%	100/15 Summer				2.942
1.004	HW6	960 Winter	30	+0%	100/360 Winter				2.900
1.005	6 (FC)	960 Winter	30	+0%	2/480 Winter				2.909
1.006	HW7	960 Summer	30	+0%					2.425

©1982-2019 Innovyze

JPP Consulting Ltd		Page 15	
4, Ironstone Way Brixworth Northampton, NN3 9UD		Surfleet Road Pinchbeck	
Date 13/04/2023 File 26043 - SW and FW.MDX		Designed by JPP Checked by LC	
Innovyze		Network 2019.1	

100 year Return Period Summary of Critical Results by Maximum Level (Rank 1)
for SW

Simulation Criteria

Areal Reduction Factor	1.000	Additional Flow - % of Total Flow	0.000
Hot Start (mins)	0	MADD Factor * 10m³/ha Storage	1.000
Hot Start Level (mm)	0	Inlet Coefficient	0.800
Manhole Headloss Coeff (Global)	0.500	Flow per Person per Day (l/per/day)	0.000
Foul Sewage per hectare (l/s)	0.000		

Number of Input Hydrographs	0	Number of Offline Controls	0	Number of Time/Area Diagrams	0
Number of Online Controls	1	Number of Storage Structures	1	Number of Real Time Controls	0

Synthetic Rainfall Details

Rainfall Model	FSR	Ratio R	0.400
Region	England and Wales	Cv (Summer)	0.750
M5-60 (mm)	19.000	Cv (Winter)	0.840

Margin for Flood Risk Warning (mm)	300.0
Analysis Timestep	2.5 Second Increment (Extended)
DTS Status	OFF
DVD Status	ON
Inertia Status	ON

Profile(s)	Summer and Winter
Duration(s) (mins)	15, 30, 60, 120, 180, 240, 360, 480, 600, 720, 960, 1440
Return Period(s) (years)	1, 2, 30, 100
Climate Change (%)	0, 0, 0, 40

PN	US/MH Name	Storm	Return Period	Climate Change	First (X) Surchage	First (Y) Flood	First (Z) Overflow	Overflow Act.	Water Level (m)
1.000	1	15 Winter	100	+40%	100/15 Summer				3.912
1.001	2	15 Winter	100	+40%	100/15 Summer				3.847
1.002	3	15 Winter	100	+40%	30/15 Winter				3.440
1.003	HW1	15 Winter	100	+40%	100/15 Summer				3.238
2.000	HW2	15 Winter	100	+40%					3.246
2.001	HW3	15 Winter	100	+40%					3.187
2.002	HW4	1440 Winter	100	+40%					3.142
3.000	4	15 Winter	100	+40%	30/15 Summer				3.755
3.001	5	15 Winter	100	+40%	30/15 Summer				3.494
3.002	HW5	15 Winter	100	+40%	100/15 Summer				3.183
1.004	HW6	1440 Winter	100	+40%	100/360 Winter				3.141
1.005	6 (FC)	1440 Winter	100	+40%	2/480 Winter				3.154
1.006	HW7	720 Winter	100	+40%					2.425

©1982-2019 Innovyze

