


Amenity

Rydal 3CCT Wallpack 15W/22W/30W



Rydal Wallpack 3CCT Multi Wattage 15W/22W/30W Asymmetric Optics perfect for Outdoor Lighting Secure dual sided Conduit cable entry points Hinged front provides quick access & ease of installation IK10



General Data

Technology	LED
Mounting options	Surface-Mounted
Electrical Connector Type	Push terminal
Install Options	70mm diameter Besa rear concealed cutout.
Input Electrical Connection	Live Neutral Earth P Live
General Application	Residential Commercial Industrial
Operating Temperature Range °C	-20 - +45
Warranty (Years)	5

431139

Technical Specification

Optical Data

LED Manufacturer / Type	BMTC3030
Fixture Luminous Flux (Lm)	2250 3300 4500
Luminaire Efficacy @4000K (lm/W)	150
LOR %	100
Colour Selectable	Yes
Beam Angle°	70 x 140
Optics	Asymmetric
Photobiological Risk Group	RGO

Light Source Data

Energy Class	C
Colour Temperature (K)	3000 4000 5000
Light Colour	Warm Light Cool White Natural Light
CRI Ra	>80

431139

Technical Specification

Electrical Data

Wattage (W)	15W 22W 30W
Mains voltage (V)	220-240
Lamp power factor	>0.9
Electrical protection	Class I
Driver Output (V)	25-38
Driver Output Current (mA)	750
Control Gear Type CC or CV	Constant Current
SVM	0.002
PstLM	0.032
Driver Brand	AGT
Nominal Frequency (Hz)	50 60

Lifetime Data

Lifespan L70 B50 @25°C (Hrs)	>60,000
Lifespan L80 B20 @25°C (Hrs)	60,000
Lifespan L90 B10 @25°C (Hrs)	48,000

Sensor Data

Sensor Technology	Photocell
Sensor Type	ON/OFF

431139

Technical Specification

Physical Data

Housing Colour	Black
Body Material	Aluminium Alloy
IP Rating	65
IK Rating	10
Diffuser Material	Polycarbonate Optical lens
Nominal Product Length (mm)	248
Nominal Product Width (mm)	225
Nominal Product Height (mm)	108
Weight (kg)	2.5

Standards and Approvals

Manufactured In Accordance To	EN 60598-1
--------------------------------------	------------

