

existing pantiles on 50 x 25  
treated tile battens on 50 x 25  
counter battens

Triso Super 10 multifoil  
insulation 30mm thick  
fixed as manufacturers  
instructions to top of  
rafters  
U Value 0.19Wm2K

12.5 plasterboard & skim on  
25mm sw batten between rafters

new floor construction  
beyond

existing boarded partition  
including door to be retained  
(fixed shut) boards cleaned &  
painted

Lounge

75mm Celotex FF 4000  
see general notes  
for total construction  
U Value 0.19Wm2K

SECTION D - D

© This drawing is copyright  
Contractors must check all dimensions on Site. Only figured dimensions are to  
be worked from. Any foundation depths indicated are indicative only and must  
be in accordance with the consulting engineers design and/or agreed on site  
with the local authority. Any dimensions shown on this drawing are for information  
contained herein must be referred to the Architect before work proceeds.  
Drawings to be read with Engineers calculations / report where applicable.  
Note: If drawing details existing structures, we have not inspected woodwork  
and we are therefore unable to report that any such part of the property is  
free from defect.

Project  
Barn Conversion and Extension at  
Swift Farm Bourne Rd, West Pinchbeck

| DWG.                            | Scale     | Date    |
|---------------------------------|-----------|---------|
| Existing Retained Timber Screen | 1:10 @ A1 | July 11 |
| Dwg No.                         | Rev.      |         |
| 10-2011-WD-17                   | -         |         |

architects • designers • planning consultants  
Old School House • 36 Boston Road • Stedford  
Leicestershire • NG34 7EZ • Tel: 01529 414141  
Fax: 01529 419757

