BS5837 Survey Data

Ref.	Species	Measurements	General Observations	Category	Recommendations
T001	Wild Cherry (Prunus avium)	Height (m): 8 Stem Diam(mm): 330 Spread (m): 4.5N, 4E, 4S, 5W Crown Clearance (m): 2 Lowest Branch (m): 2(NW) Life Stage: Early Mature Rem. Contrib.: 40+ Years	Recent canopy lifts to allow for unobstructed mowing Additional Comments: All physiological condition assessments are confirmed by Arborcheck testing on-site.	C1 RPA Radius: 4.0m. Area: 50 sq m.	Pre construction: Localised pruning for clearance to enable installation of PoP. During construction: Protect trees with protective barriers - as shown on plans.
T002	Sycamore (Acer pseudoplatanus)	Height (m): 9 Stem Diam(mm): 160 Spread (m): 2.5N, 2.5E, 2.5S, 2.5W Crown Clearance (m): 4 Life Stage: Young Rem. Contrib.: 20+ Years	Self set in fence line Recent canopy lift Additional Comments: All physiological condition assessments are confirmed by Arborcheck testing on-site.	C1 RPA Radius: 1.9m. Area: 11 sq m.	During construction: Protect trees with protective barriers - as shown on plans.
T003	Wild Cherry (Prunus avium)	Height (m): 8 Stem Diam(mm): 310 Spread (m): 4.5N, 3.5E, 4S, 5W Crown Clearance (m): 2 Lowest Branch (m): 1.5(NW) Life Stage: Early Mature	All physiological condition assessments are confirmed by Arborcheck testing on-site.	C1 RPA Radius: 3.7m. Area: 43 sq m.	During construction: Protect trees with protective barriers - as shown on plans.
T004	Wild Cherry (Prunus avium)	Height (m): 8 Stem Diam(mm): 310 Spread (m): 4N, 4.5E, 4S, 4.5W Crown Clearance (m): 2 Lowest Branch (m): 2.5(N) Life Stage: Early Mature	Canopy lifts Additional Comments: All physiological condition assessments are confirmed by Arborcheck testing on-site.	C1 RPA Radius: 3.7m. Area: 43 sq m.	During construction: Protect trees with protective barriers - as shown on plans.

Ref.	Species	Measurements	General Observations	Category	Recommendations
T005	Wild Cherry (Prunus avium)	Height (m): 8 Stem Diam(mm): 310 Spread (m): 4N, 4.5E, 5S, 5.5W Crown Clearance (m): 2.5 Lowest Branch (m): 1.5(NW) Life Stage: Early Mature	All physiological condition assessments are confirmed by Arborcheck testing on-site.	C1 RPA Radius: 3.7m. Area: 43 sq m.	During construction: Protect trees with protective barriers - as shown on plans.
T006	Wild Cherry (Prunus avium)	Height (m): 8 Stem Diam(mm): 350 Spread (m): 5N, 4.5E, 4.5S, 5W Crown Clearance (m): 2.5 Lowest Branch (m): 2(SE) Life Stage: Early Mature	All physiological condition assessments are confirmed by Arborcheck testing on-site.	C1 RPA Radius: 4.2m. Area: 55 sq m.	During construction: Protect trees with protective barriers - as shown on plans.
T007	Wild Cherry (Prunus avium)	Height (m): 8 Stem Diam(mm): 310 Spread (m): 4N, 4.5E, 4.5S, 2.5W Crown Clearance (m): 2 Lowest Branch (m): 1.5 Life Stage: Early Mature	Suppressed canopy Additional Comments: All physiological condition assessments are confirmed by Arborcheck testing on-site.	C1 RPA Radius: 3.7m. Area: 43 sq m.	During construction: Protect trees with protective barriers - as shown on plans.
T008	Wild Cherry (Prunus avium)	Height (m): 8 Stem Diam(mm): 430 Spread (m): 4.5N, 3.5E, 5.5S, 5W Crown Clearance (m): 2 Lowest Branch (m): 1.5(NW) Life Stage: Early Mature Rem. Contrib.: 40+ Years	All physiological condition assessments are confirmed by Arborcheck testing on-site.	C1 RPA Radius: 5.2m. Area: 85 sq m.	Pre construction: Localised pruning to enable installation of the PoP. During construction: Protect trees with protective barriers - as shown on plans.