

1. For details of gradients and routes of house drainage connections refer to house drainage layout drawings.
2. This drawing to be read in conjunction with the standard Details, Schedules and the specification for this project.
3. All manholes and gullies are to be positioned at the chainages given on the long sections.
4. All connections for house drainage shall be 100mm unless stated and must extend a minimum of 500mm behind the back of the footpath. All connections when laid shall be plugged, protected as necessary and marked with a stake for future use.
5. Connections into all sewers to be "SOFFIT TO SOFFIT" unless noted, otherwise on the longitudinal sections.
6. The contractor is to check the level of existing sewers to be used as out-fall immediately they are exposed PRIOR to laying of pipes. Any discrepancies are to be reported to the Engineer.

S232 — Adoptable SW System (under site S104)

F231 — Adoptable FW System (under site S104)

Road Gulley (Ø150 Connection)

Site Boundary

Bellway

Bellway Homes Limited (Eastern Counties)
3 Percy Road
Huntingdon
Cambridgeshire
PE29 6SZ

REV	DESCRIPTION	REV	DESCRIPTION	DATE
		A	Planning Layout updated.	24.6.21

STATUS: Subject to Technical Approval

SCALE: 1:500
DATE: May 2021
DRAWN: IDL

TITLE: S104 Drainage Layout

PROJECT: Wardentree Lane, Pinchbeck

DRG. No: 1044-03-01 Rev A

iD LTD
INFRASTRUCTURE DESIGN LIMITED
33 The Point
Market Harborough
Leicestershire LE16 7QU
Tel: 01858 411570 Fax: 01858 411571