NORTH

pens

refurbish existing wall

enclosed yard

form gateway

gardener

TBM 10000 THRESHOLD

existing wall rebuild & raise height on new footing

glasshouse

glasshouse

1500

1500

2000

1500

grass

roses

GARDEN LAYOUT & LEVELS TO BE CONFIRMED BY CLIENT. ASSUME FOOTPATH LEVEL OF 9550

grass

roses

um

1500

roses

roses

grass

grass

1500

EXISTING TIMBER POST

GRAVELLED FOOTPATHS WITH EDGING

new wall approx 19600 by suit bricks

END OF WALL TO LINE THROUGH WITH EXISTING WOODEN SCREEN.

PART SITE PLAN

10000

9550

MOVEMENT JOINT

SOUTH ELEVATION

MOVEMENT JOINT

glasshouse

WEST ELEVATION

REMOVE EXISTING RIDGE TILE & BRICK COPINGS & REPLACE WITH YORKSTONE COPING TO MATCH THOSE ON NEW WALL

TAKE DOWN SECTION OF COMMON BRICK TO TOP OF WALL & REBUILD USING RECLAIMED BRICK. BRICK, MORTAR & BOND TO MATCH EXISTING

FORM GATEWAY TO DIMENSIONS SHOWN SEGMENTAL ARCH OVER BRICKS TO MATCH EXISTING. TIMBER GATE OPENING VERTICAL TEG BOARDING. METAL HINGES COACH BOLT TO GATE & PAINT FINISH. HORN REVERSIBLE GATE HANGER. RING GATE TYPE LATCH. 750 x 300 VERTICAL METAL GRILL VISION PANEL IN GATE. PAINT FINISH TO GATE. NEW BRICK PIERS TO REAR OF WALL UP TO UNDERSIDE OF ROOF GUTTERING

CUT OUT & REPLACE ANY DAMAGED BRICKS.

COMPLETE WALL TO BE REPOINTED

BRICK KNEELER WALL AT END OF GLASSHOUSE ON NEW FOUNDATION

underside coping approx 12500 to suit bricks

spring point

approx 2000 to suit bricks

9550 to be confirmed by client

NEW WALL ELEVATION

1·5 brick thick

1·5 brick thick

2 brick long

approx 1050 to suit brick size

EXISTING WALL

to match existing 1·5 brick thick

NEW WALL PLAN

50mm YORKSTONE COPING WITH THROAT TO MATCH THOSE ON EXISTING WALL AT REAR OF HOUSE

1 BRICK THICK WALL AS EXISTING

FEATURE REDUCTION IN WALL THICKNESS TO MATCH EXISTING

FACE BRICK, BRICK BOND, MORTAR MIX & COPING ALL TO MATCH EXISTING

1·5 BRICK THICK WALL REINFORCED

RED ENGINEERING BRICK DPC

NEW WALL SECTION

Planning & Development
26 JUN 2003
Ref 0816/03

DETERMINED PLAN

Contractor To Check All Dimensions On Site Before Work Commences.

Rev.	Date.	Init.	Revision Details.

PODDINGTONS
Architectural Design Consultants
Rabbit Hollow, Church Lane, North Rauceby, Sleaford, Lincs. NG34 8QU
Tel. (01529) 488033 Fax. (01529) 488044

Project.
MR & MRS C. SIMS.
OTWAY HOUSE, SPALDING ROAD, PINCHBECK.

Drawing.
PLAN AS PROPOSED

Scale.	Drawing. No.
1-100	3135-2
Drawn.	
Date. APRIL 2003	Rev.