



Bellway

Bellway Homes Limited (Eastern Counties)

3 Percy Road

Huntingdon

Cambridgeshire

PE29 6SZ

1- "The specification in all respects shall be in accordance with the current development road and sustainable Drainage Specification and Construction publication in force in the county at the time of construction"

2- "The minimum longitudinal fall for highways, without channel blocks shall be 1 in 350, and with channel blocks in 1 in 350" see clause 10.1 of development road and Sustainable Drainage Specification and Construction. In addition, ensure that the first section of any side road falls away from the road to which it is connecting. If general topography requires it to rise, this change of direction should take place after the first set of gullies. This is to ensure a 'false channel' with associated drainage problems is not created in the bellmouth of junctions

3- "General deterioration of the existing highway/footway/verges created through construction of the new section 38 development will be reinstated to the Development Road and Sustainable Drainage Specification and Construction at the developers' own cost at the agreement of inspecting Highway and Flood Authority Officer"

4- "No Private surface water shall discharge onto the adoptable highway"

5- "No private structural features shall overhang the adoptable highway"

6- "No private retaining walls exceeding 1.37 metres shall be within 3.66 metres of the highway boundary"

REV

DESCRIPTION

REV

DESCRIPTION

DATE

STATUS:

Subject to
Technical Approval

SCALE: 1:500

DATE: May 2021

DRAWN: IDL

TITLE :

Section 38 Highway
Kerbing & Construction
Layout

PROJECT :

Wardentree Lane, Pinchbeck

DRG. No:

1044-02-03 Rev H

iDLTD

INFRASTRUCTURE DESIGN LIMITED

33 The Point
Market Harborough
Leicestershire LE16 7QU
Tel: 01858 411570 Fax: 01858 411571