



SOUTH ELEVATION



EAST ELEVATION



WEST ELEVATION



NORTH ELEVATION

MATERIALS LIST

DEMOLITIONS / ITEMS TO BE REMOVED SHOWN DASHED BROWN LINES

ROOF:
 Profiled metal composite cladding panels - colour Goosewing Grey (10 A 05)
 Profiled metal gutter and trims - colour Merlin Grey (18 B 25)

WALLS
 Render to a height of 2100mm above floor level, with blue engineering brick plinth
 Kingspan Microbri metal insulated composite panels - colour Silver
 Fixed horizontally to South & East Elevations fronting the mains road
 Fixed vertically to North & West Elevations full height

WINDOWS
 Polyester powder coated aluminium frames with grey tinting, colour Dark Grey (18 B 25)

DOORS
 Sectional overhead doors, and personnel doors, Polyester powder coated aluminium frames, colour Dark Grey (18 B 25)

EXTERNAL STAIRCASE:
 Galvanised steel spiral staircase, including landing section, balustrade and handrails

