


A		
	Date	Revisions

© copyright

East Midlands Design Associates

"Willow Lodge",
Horseshoe Road,
Spalding,
Lincs. PE11 3JA
Tel: Spalding (0775) 767968

Client

Job Title

Extension to Dwelling at

Dozens Bank
W. Pinchbeck
Spalding


Drawing Title

Block Plan


Scale 1:250

Date July 00 | Drawn by AR


Drg. No. 00/24/03 | Rev A




south




west




north




east





plan



section

Construction to be generally as specified for dwelling.

DETERMINED PLAN

SOUTH HOLLAND DC
HOUSING & PLANNING
-5 OCT 2001
Ref: 1182/01

A		
	Date	Revisions

© copyright

East Midlands Design Associates
"Willow Lodge",
Horseshoe Road,
Spalding.
Lincs PE11 3JA
Tel: Spalding (0775) 767966

Client
R CHAPPEL & SONS


Job Title
EXTENSION & ALTERATIONS AT THE BUNGALOW
BOSTONS BANK
WEST PINCHBECK SPALDING

Drawing Title
PLAN, SECTION and ELEVATIONS OF GARAGE & GARDEN STORE


Scale 1:50 & 1:100

Date Oct 01 | Drawn by AL


Drg. No 00124/06 | Rev




east




north



west



south



STAGE 1
Planning permission ref H14/0945/00
Building regulation ref B14/0481/00

FOUNDATIONS

Foundations to be ST4 grade concrete

For 265mm walls foundations to be 700 x 230mm
For 100mm " " " 450 x 230mm

Foundations to be taken down to a firm loadbearing strata, a min. 1.0m if in shrinkable sub soil, in accordance with the requirements of the Local Authority Building Control Dept. and in accord with the NHBC guidelines for building near trees.
Site soil surveys are recommended in respect of foundations to establish specific site conditions before foundation work is undertaken.
Any investigation work relating to exig foundations should be carried out prior to the commencement of any works.

FLOOR CONSTRUCTION

Ground
65mm sand/cement screed reinforced with chicken wire mesh
500g polythene separating membrane
50mm Jablite 6D floor insulation (k = 0.037W/m°C)
100mm ST4 grade oversite concrete
1200g polythene damp proof membrane
25mm sand blinding
100mm compacted hard-core - if in excess of 100mm fill, to a max. 800mm, the hard-core is to be laid and compacted in layers not exceeding 150mm.
Where 100mm internal walls are constructed off the floor slab the slab is to be thickened to 230mm for a min width of 450mm
Strip off all vegetable soil beneath proposal.

WALL CONSTRUCTION

Below Ground
To be 100mm Class A concrete blocks
Cavity to be filled to 225mm below lowest dpc level with lean mix concrete

Above Ground
To be 265mm o/a constructed as follows :-

100mm facing brick (to be FL quality below dpc level)
65 mineral wall insulation i.e. Dritherm (k = 0.038)
100mm loadbearing insulation blocks i.e. Hemelite (k = 0.44)

All to be tied together using stainless steel wall ties positioned at distance not exceeding 900mm horizontally, 450mm vertically and staggered. To be at every block course vertically at all returns and reveals.

Internal finish to be 12mm render with gypsum plaster skim finish to give a 'U' value of 0.414W/mK

Internal Walls
To be 100mm blockwork constructed off a dpc off the floor slab

DPC in Walls
To be a min. 150mm above finished ground level
An insulating vertical cavity closer and dpc, i.e. Thermabate, is to be provided to all cavity closures.
A dpc cavity tray, stepped as applicable, is to be constructed within the wall immediately above an abutment

LINTELS

Lintels to be Catnic, or similar and equivalent, to have a min. 150mm end bearing and be installed in strict accordance with manufacturers instructions with a dpc cavity tray over where applicable.

Lintels over internal openings to be Catnic CN102 lintels unless specified otherwise.

Lintels to be protected with min. 15mm gypsum plaster skim finish to give a min. half hour fire protection.

WINDOWS & DOORS

Windows and doors to be purpose made UPVC double glazed with 12mm air gap to sealed units and weather stripped.

Windows to habitable rooms are to incorporate a controllable trickle vent of 8000mm², 4000mm², to non habitable rooms

Glazing to windows less than 800mm and doors (include sidelights to doors) less than 1500mm above floor level is to be laminated or toughened glass in accord with BS6206 : 1981.

WINDOW/DOOR & LINTEL SCHEDULE

Location	window/door ref. Width x height	lintel ref. & length
1	3000 x 2100 French doors and sidelights	CGH50/100 3300
2	Exig window reused	CGH50/100 3900
3	1770 x 1200	CG50/100 2100
4	1770 x 1200	" 2100
5	1770 x 1200	" 2100
6	1770 x 1200	" 2100
7	900 x 2100	" 1200
8	1770 x 1200	" 2100
9	1770 x 1200	" 2100
10	1200 x 1200	" 1500

All internal doors to rooms other than cup'ds etc. are to be 838mm wide

VENTILATION

All habitable rooms are to have windows containing opening vents, the combined total of which is equal to not less than 1/20th of the floor area of the room.

All bath and shower rooms are to be mechanically ventilated direct to the external air. The capacity of the extractor is to be 15 litres/sec

SMOKE DETECTION

Self contained smoke alarms complying with BS5446 : Pt 1 : 1990 are to be installed where indicated SD on the drawing. An alarm must be positioned within 3.0m of bedroom doors.

The alarms are to be permanently wired to a separately fixed circuit at the distribution board operating at a low voltage via a mains transformer.

Where more than one smoke alarm is required the units are to be interconnected so that the detection of smoke by one unit operates the alarm signal in all units.

The wiring installation is to comply with the I.E.E. Regulations.

ELECTRICAL INSTALLATION

The Electrical Contractor is to ensure that the electrical installation is in full compliance with the latest edition of the I.E.E. Regulations
Any electrical fitting indicated on the drawing in a position contravening these regulations must be relocated in order to achieve full compliance.

All switches, sockets, tv points and telephone jackpoints are to be located at a height between 450 and 1200mm above finished floor level.

HOT WATER SYSTEM

A room thermostat or radiator valves are to be installed

All pipes not contributing to useful heat requirements are to be insulated using an insulation material with a thermal conductivity not exceeding 0.45W/mk and a thickness equal to the external diameter of the pipe up to a max. of 40mm.

DETERMINED PLAN

	Date	Revisions
A		

© copyright

East Midlands Design Associates
"Willow Lodge"
Horseshoe Road,
Spalding.
Lincs PE11 3JA
Tel. Spalding (0775) 767988

Client
R CHAPPELL & SONS

Job Title
EXTENSION & ALTERATIONS AT
THE BUNGALOW
DOZENS BANK
WEST PINCHBECK. SPALDING

Drawing Title
PLAN & ELEVATIONS

SOUTH HOLLAND DC
HOUSING & PLANNING
-5 OCT 2001
Ref: 1182/01

Scale 1:50, 1:100

Date OCT 01 | Drawn by RL

Drg. No. 00124104 | Rev