NORTH FACING.

SPALDING

HEDGING AND BANKING TO BE A MINIMUM OF 9.000m FROM DRAINAGE BOARD DRAIN

PROPOSED 4.000m HIGH BANK SET INSIDE EXISTING HEDGE AND BANK

EXISTING DOUBLE ROW OF NATIVE SPECIES AND HEDGE

HEDGE SET ON EXISTING 2.000m HIGH BANK

3.000m HIGH ACOUSTIC TIMBER FENCE TO BE ERECTED BETWEEN EXISTING AND NEW BUILDING.

EXISTING DOUBLE ROW OF NATIVE SPECIES AND HEDGE

HEDGE SET ON EXISTING 2.000m HIGH BANK

7500

PROPOSED 4.000m HIGH BANK SET INSIDE EXISTING HEDGE AND BANK

RESERVOIR No.1

RESERVOIR No.2

BLUE GOWT DRAIN

DOZENS BANK.

EXISTING WORKSHOP

EXISTING REFRIGERATED POTATO STORE.

5000

REFRIGERATED POTATO STORE.

24.40m

24.40m

3050

3000

EXISTING S.W. DRAIN

CONCRETE PAVED AREA

COMMERCIAL VEHICLE HOLDING / PARKING

ELECTRIC SUB-STATION

PRIMARY SETTLEMENT RESERVOIR

CAR PARKING

WEIGH-BRIDGE

EXISTING OFFICES & STORE.

LOADING CANOPY.

EXISTING POTATO FACTORY & STORE.

POTATO PROCESSING/ HANDLING BUILDING

U/G ELECTRIC CABLE 0.75 DEEP

FOURTH DISTRICT MAIN DRAIN.

STAFF CANTEEN

CAR PARKING

Langwith Design Associates

Architectural Design Consultants
registered office
72 Church Street
Holbeach
Spalding
Lincolnshire PE12 7LL
telephone: Holbeach (01406) 425766
fax: Holbeach (01406) 425766

Amendments

A	24/07/00	ACOUSTIC FENCE ADDED, CONDENSERS RE-POSITIONED TO FRONT OF BUILDING.
B	26/07/00	RESERVOIRS, BANKING, EXISTING HEDGING ETC. ADDED.

PLANNING PLAN

RECEIVED 25 JUL 2000

Ref: 0587/00

© Copyright Reserved.

Client
D.G.M. GROWERS LTD.

Project
PROPOSED REFRIGERATED POTATO STORE.

Drawing
BLOCK PLAN.

Scale		Drawn	Checked
1:500		A.D.H.	C.J.P.
Date	No.		Ref.
MAY.'00	LDA/1077/02		B