Do not scale this drawing
Landscape Architects to be notified of all discrepancies to figured dimensions from site
This drawing is copyright

amendments

A. Amended following Costain Comments Sept 08 JP

DETERMINED PLAN

ENTRANCE ROADWAY AND ROUNDABOUT BY OTHERS

LIMIT OF WORKS

ENTRANCE ROADWAY AND ROUNDABOUT BY OTHERS

LIMIT OF WORKS

CAR PARK - 30 SPACES

SPALDING ROAD

SHARP'S BRIDGE

VERNATTS DRAIN

Key

- Building & structures
- Softworks
- Maintenance access route - Grasscrete
- Car park bays - Red concrete block paving
- Footpaths - Seeded tarmacadam
- Seating areas - Tumbled concrete block paving
- Street furniture - Hardwood timber
- Decking - Hi-grip european redwood
- Cafe area - Clay cobbles
- Leaf feature - Resin bound aggregate (5 colours)
- Main entrance - Quality ground concrete
- Frontage - Textured concrete slabs
- Courtyards - Natural Stone Paving Slabs
- Play area - Coloured wetpour rubberised play surface
- Tree grilles - Heavy duty mild steel grilles with guards
- Slate aggregate - Loose laid
- Paddlestones - Loose laid
- Red Porphyry aggregate - Loose laid
- Hazard warning paving

SHDC Planning & Development - 5 DEC 2008 Ref: 1244/08

COSTAIN REVISED 12/11/08

Drawing status: Planning

project: South Holland Community Hospital

Job number: LP1589

drawing title: External paving materials

drawing number: LA/SH/WS/L/90/02

revision	scale	date
A	1:250@A0	Sep 08

	drawn	built	date
for information	gil	jp	Sep 08
for construction			

fira
The Jewellery Business Centre
99 Vyse Street
BIRMINGHAM, B18 6JA.
Tel: 0121 523 1010
Fax: 0121 523 1004
fira landscape architecture and urban design