

Date: 22.04.16		Site: Quadring												Surveyor: MGP				Client: ACD Developments				Job no: A.0307					
Ref	Species	Height	Est	Stem dia	Est	Spread								Crown clearance height					Life stage	General observations Physiological and structural condition. Preliminary management recommendations	Structural Condition	Physiological Condition	ULE	Quality grading	RPA radius	RPA area	
						N	Est	S	Est	E	Est	W	Est	1st branch	Est	1st branch direction	Canopy	Est									
T1	Ash (Common)	4.0	-	90	-	1.0	-	1.0	-	1.0	-	1.0	-	N/A	-	N/A	0.5	-	Y	Self set no obvious defects	Fair	Fair	10+	C1	1.1	4	
T2	Sycamore	8.0	-	100	-	0.5	-	2.5	-	1.0	-	1.5	-	N/A	-	N/A	N/A	-	SM	Suppressed canopy to north and north-east, leans to south, poor canopy shape	Fair	Fair	10+	C1	1.2	5	
T3	Ash (Common)	11.5	-	380	-	1.0	-	5.5	-	6.0	-	5.0	-	N/A	-	N/A	N/A	-	M	Supressed by willow to the north, Ivy on stem, leans to the south, reasonably dense canopy	Fair	Fair	20+	C1	4.6	65	
T4	Willow	12.0	-	700	#	4.0	-	8.0	-	4.0	-	8.0	-	N/A	-	N/A	N/A	-	M	Willow stem has failed and split apart, limbs spreading from snapped stem and have regrowth, Ivy on collapsed stem	Poor	Fair	10+	C1	8.4	222	
T5	Willow	12.0	-	700	-	5.0	-	5.5	-	5.5	-	3.5	-	N/A	-	N/A	N/A	-	M	Off site adjacent ditch, limb failure from stem on western side. Unable to access.	Poor	Fair	10+	B1	8.4	222	
T6	Elder	4.0	-	220	-	0.5	-	1.5	-	5.0	-	0.0	-	N/A	-	N/A	N/A	-	M	Leans to the east, heavily supressed by neighbouring trees. Poor quality	Poor	Poor	<10	U	2.6	22	
G7	Elder, sycamore	5.5	-	150	#	As on plan								N/A	-	N/A	N/A	-	EM	Predominantly dead elder with one self set young sycamore a some dying elder. Poor quality	Poor	Poor	<10	U	1.8	10	
G8	Cypress, sycamore, hawthorn, apple	14.0	-	300	#	As on plan								N/A	-	N/A	N/A	-	M	Row of cypress with a sycamore, hawthorn and apple within. Offsite set behind ditch. No access.	Fair	Good	20+	B2	3.6	41	
G9	Elder, bramble	5.0	-	80	#	As on plan								N/A	-	N/A	N/A	-	EM	Dense elder and bramble, scrubby, unmanaged,	Poor	Fair	<10	U	1.0	3	
G10	Sycamore, birch, goat willow	6.0	-	100	#	2.0	-	1.5	-	0.0	-	0.0	-	N/A	-	N/A	N/A	-	SM	Self set adjacent barn, 6 stems, low quality	Fair	Fair	10+	C2	1.2	5	
T11	Ash (Common)	4.0	-	120	-	1.5	-	1.5	-	1.5	-	1.5	-	N/A	-	N/A	N/A	-	SM	Self set adjacent barn, twin stem with low union. Low quality	Poor	Fair	10+	C1	1.4	7	
T12	Sycamore	5.0	-	100	-	1.0	-	1.0	-	1.0	-	1.0	-	N/A	-	N/A	N/A	-	Y	Self set adjacent derelict barn.	Fair	Fair	10+	C1	1.2	5	
T13	Ash (Common)	12.5	-	450	#	5.5	-	5.5	-	4.0	-	5.5	-	1.5	-	South west	1.0	-	M	Good shape, dense ivy on stem and into canopy, ditch to south, minor pruning wounds, some branch loss, rubbish and waste materials around base, remove ivy and re-inspect	Fair	Fair	20+	B1	5.4	92	
T14	Sycamore	14.0	-	566	-	4.0	-	4.0	-	4.5	-	4.5	-	N/A	-	N/A	3.0	-	M	Dense ivy on stem and into canopy, twin stem on bank of ditch, elder at base along with rusting oil drums, reasonably good shape	Fair	Fair	20+	B1	6.8	145	
G15	Sycamore	3.5	-	50	-	1.0	-	1.0	-	1.0	-	1.0	-	N/A	-	N/A	N/A	-	Y	Self set, multiple stems	Fair	Fair	10+	C1	0.6	1	
G16	Elder	4.0	-	75	-	1.0	-	1.0	-	1.0	-	1.0	-	N/A	-	N/A	N/A	-	SM	Self set elder bushes, low quality	Fair	Fair	10+	C1	0.9	3	
T17	Elder	6.0	-	180	#	2.5	-	0.5	-	2.0	-	2.0	-	N/A	-	N/A	0.5	-	M	Supressed to south by barn, self set, low quality	Fair	Fair	<10	C1	2.2	15	
G18	Sycamore	16.0	-	450	#	As on plan								N/A	-	N/A	0.5	-	M	Four sycamore trees, two are multi-stems, Ivy on all stems, drawn up, some have had previous branch loss. Two multi-stemmed trees are adjacent ditch, western has lost some stems in past with decay at loss point. Canopies are reasonably dense.	Fair	Fair	20+	B2	5.4	92	
T19	Apple	7.0	-	340	#	4.0	-	3.0	-	4.5	-	4.0	-	N/A	-	N/A	1.5	-	M	Set within garden, pruned lower canopy, some deadwood,	Fair	Fair	10+	C1	4.1	52	
T20	Sycamore	7.0	-	200	-	2.0	-	2.0	-	2.0	-	2.0	-	N/A	-	N/A	3.0	-	SM	Suppressed lower canopy, Ivy on stem, elder at base, low quality	Fair	Good	10+	C1	2.4	18	
T21	Elder	5.0	-	200	-	2.0	-	1.5	-	2.5	-	2.0	-	N/A	-	N/A	0.5	-	M	Dense Ivy on stems and into canopy, past branch loss, moderate deadwood	Poor	Fair	<10	U	2.4	18	
T22	Apple	5.0	-	320	-	2.5	-	1.0	-	1.5	-	3.0	-	N/A	-	N/A	1.5	-	M	Major deadwood, limited leaf bearing structure, in irreversible decline	Fair	Poor	<10	U	3.8	46	
T23	Holy	2.5	-	60	-	0.5	-	1.0	-	2.0	-	0.5	-	N/A	-	N/A	1.0	-	SM	Poor canopy shape, low quality	Poor	Fair	<10	U	0.7	2	
T24	Elder	5.0	-	200	-	2.0	-	1.5	-	3.5	-	2.5	-	N/A	-	N/A	1.5	-	M	Moderate deadwood, pruned in past, Ivy on stems	Fair	Fair	10+	C1	2.4	18	
T25	Ash	11.0	-	220	-	3.0	-	4.0	-	4.0	-	4.0	-	N/A	-	N/A	1.0	-	EM	Multiple ash stems, drawn up, adjacent garden shed, ivy on stems,	Fair	Fair	10+	C2	2.6	22	

Date: 22.04.16		Site: Quadring												Surveyor: MGP					Client: ACD Developments					Job no: A.0307					
Ref	Species	Height	Est	Stem dia	Est	Spread								Crown clearance height				Life stage	General observations Physiological and structural condition. Preliminary management recommendations	Structural Condition	Physiological Condition	ULE	Quality grading	RPA radius	RPA area				
						N	Est	S	Est	E	Est	W	Est	1st branch	Est	1st branch direction	Canopy									Est			
G26	Hawthorn	4.0	-	75	-	0.0	-	0.0	-	1.0	-	1.0	-	N/A	-	N/A	0.0	-	SM	Hawthorn group on boundary, thin and gappy, low quality	Fair	Fair	10+	C2	0.9	3			
T27	Cherry	7.5	-	300	-	3.0	-	3.0	-	3.0	-	3.0	-	N/A	-	N/A	1.5	-	M	Dead, dense Ivy on stem and into canopy.	Poor	Poor	<10	U	3.6	41			
T28	Ash (Common)	11.5	-	300	#	5.0	-	5.0	-	5.0	-	5.0	-	N/A	-	N/A	N/A	-	EM	Growing from within derelict building, elder and Ivy and fallen down shed preventing access. Good shape	Fair	Fair	10+	C1	3.6	41			
T29	Ash (Common)	8.0	-	150	-	2.0	-	2.0	-	2.0	-	2.0	-	N/A	-	N/A	N/A	-	SM	Self set adjacent derelict building	Fair	Fair	10+	C1	1.8	10			
G30	Sycamore, elder, ash	9.5	-	150	-	As on plan								N/A	-	N/A	0.5	-	SM	Self set mixed species growing within ditch and adjacent derelict barn,	Fair	Fair	10+	C2	1.8	10			
T31	Sycamore	9.0	-	200	-	2.0	-	1.5	-	0.0	-	3.0	-	N/A	-	N/A	0.5	-	SM	Lean to west and suppressed by ash to east. Low quality	Poor	Fair	10+	C1	2.4	18			
T32	Ash (Common)	10.0	-	340	-	3.0	-	3.0	-	4.0	-	3.0	-	N/A	-	N/A	0.5	-	EM	Growing adjacent barn and electricity pole, reasonably good shape	Fair	Fair	10+	C1	4.1	52			
G33	Ash, sycamore	6.0	-	60	#	1.5	-	1.5	-	0.0	-	0.0	-	N/A	-	N/A	N/A	-	Y	Set along by are fence, bramble within	Fair	Fair	10+	C2	0.7	2			
T34	Polar	14.0	-	1,300	-	4.5	-	4.5	-	4.0	-	5.5	-	N/A	-	N/A	2.5	-	M	Pollarded, dense Ivy on stem, regrowth from pruning points,	Fair	Fair	20+	B1	15.0	707			
T35	Sycamore	13.0	-	600	-	5.0	-	4.0	-	5.0	-	4.5	-	N/A	-	N/A	1.5	-	M	Ivy on stem and into canopy, pruned in the past, some deadwood,	Fair	Fair	20+	B1	7.2	163			
T36	Sycamore	11.0	-	800	#	5.5	-	6.0	-	6.0	-	5.5	-	N/A	-	N/A	0.5	-	M	Off site, limited access, pruned in past, thin internal canopy, spreading limbs, pruned in past	Fair	Fair	20+	B1	9.6	290			
G37	Sycamore	11.5	-	350	-	As on plan								N/A	-	N/A	N/A	-	EM	Two multi stem sycamore with elder scrub, ivy on stems which are drawn up, low quality, limited access.	Fair	Fair	10+	C2	4.2	55			
T38	Sycamore	12.0	-	360	-	4.0	-	4.0	-	4.0	-	4.0	-	N/A	-	N/A	N/A	-	M	Offsite, no access, thin canopy, past branch loss	Fair	Fair	20+	C1	4.3	59			