FOR AMENITY WOODLAND PROPOSALS SEE KEY SHEET, DWG. 233/33/8A

SCHEDULE OF TREES AND SHRUBS

Trees:

25	C	Betula pendula	120-150 feat harvest
13	MT	Malus tschonoskii	Standard
8	PA	Prunus avium	Standard
9	S	Sorbus aucuparia 'Joseph Rock'	Standard

Specimen Shrubs:

16	am	Amelanchier canadensis	90-120 cg
5	cc	Colonnester 'Cornubia'	90-120 cg

Shrubs in beds:

105	CA	Cornus alba 'Elegantissima'	60-90 cg, 1600p/s
78	CV	Cornus alba 'Variegata'	90 cg, 1000p/s
212	PL	Prunus laurocerasus 'Otto Luyken'	30-45 cg, 800p/s
62	SG	Senecio greyi	45-60 cg, 900p/s
86	W	Weigela 'Bristol Ruby'	45-60 cg, 800p/s

All trees to be adequately staked and tied, and half a bag of peat free tree and shrub planting compost incorporated into the backfill for each treehole.

A topdressing of 'Enmag' fertiliser shall be made to all shrub areas and trees following planting strictly in accordance with manufacturer's instruction

ALLISON HOMES

DETERMINED PLAN

WOOLRAM WYGATE 6 SOFT LANDSCAPE

SOUTH HOLLAND DC HOUSING & PLANNING -7 JAN 1997 Ref: 0018/97

DWG 233/56/10 1:200 Dec 96

Planning, Architecture, Landscape Architecture
Robert Doughty Consultancy
32 High Street, Helpringham, Sleaford NG34 0RA Tel: (01529) 421846 Fax: (01529) 421338