FOR AMENITY WOODLAND PROPOSALS SEE KEY SHEET, DWG. 233/33/8A

SCHEDULE OF TREES AND SHRUBS

Trees:

25	C	Betula pendula	120-150 feathered
13	MT	Malus tschonoskii	Standard
8	PA	Prunus avium	Standard
9	S	Sorbus aucuparia 'Joseph Rock'	Standard

Specimen Shrubs:

16	am	Amelanchier canadensis	90-120 cg
5	cc	Cotoneaster 'Cornubia'	90-120 cg

Shrubs in beds:

105	CA	Cornus alba 'Elegantissima'	60-90 cg, 1000/s
78	CV	Cornus alba 'Variegata'	90 cg, 1000/s
212	PL	Prunus laurocerasus 'Otto Luyken'	30-45 cg, 800/s
62	SG	Sarrocka grayii	45-60 cg, 900/s
68	W	Weigela 'Bristol Ruby'	45-60 cg, 800/s

All trees to be adequately staked and tied, and half a bag of peat free tree and shrub planting compost incorporated into the backfill for each treehole.

A topdressing of 'Enmag' fertiliser shall be made to all shrub areas and trees following planting strictly in accordance with manufacturer's instruction

ALLISON HOMES

WOOLRAM WYGATE 6
SOFT LANDSCAPE

DETERMINED PLAN

SOUTH HOLLAND DC
HOUSING & PLANNING
-7 JAN 1997
Ref: 0020/97

DWG 233/56/10 1:200 Dec 96

Planning
Architecture
Landscape Architecture
Robert Doughty Consultancy
32 High Street, Helpringham, Sleaford NG34 0RA Tel (01529) 421646 Fax (01529) 421358