ALLISON HOMES



PUBLIC OPEN SPACE PLANTING

TREES

F 8 Nº Fraxinus excelsior 8-10 Std.

B 23 Nº Betula pendula 180-240 10L c.g.

SA 18 Nº Sorbus aucuparia 8-10 Std.

REV. A. 6.3.96. TODDLERS PLAY AREA MOVED TO SOUTH-WEST CORNER OF OPEN SPACE.

REV. B. 13.3.96. TODDLERS PLAY AREA MOVED AWAY FROM NEAR PLOT 53 IN N.W. DIRECTION, TREES REPLANTED ALONG SOUTHERN BOUNDARY.

REV. C. 25.3.96. MATEX PLANTING REMOVED FROM ALONG NORTHERN BOUNDARY OF P.O.S.

A... PLAN
Ref. A1

DRAWING
28 MAR 1996
ISSUED

ESTABLISHMENT NOTES

All trees are to be adequately staked and tied and half a bag of peat free tree and shrub planting compost incorporated into the backfill for each treehole.

A topdressing of 'Enmag' fertilizer shall be made to all shrub areas and trees following planting strictly in accordance with manufacturer's instructions.

PLANTING ADJACENT TO THE P.O.S. ON THE SOUTH & EAST SIDE REFER TO DRG.Nº 233/54/5.

...PLANNING
01 APR 1996
Ref: 0081/96

PUBLIC OPEN SPACE LANDSCAPING PROPOSALS.
PHASES 5 AND 7, WOOLRAM WYGATE, SPALDING.
DRAWING Nº 233/54/1 SCALE 1:200 NOV. 1995.

Robert Doughty Consultancy
Planning
Landscape Architecture
Architecture
32 High Street, Helpringham, Sleaford NG34 0RA Tel: (01529) 421646 Fax: (01529) 421358
Lincoln House, 56/58 Clasketgate, Lincoln LN2 1JZ Tel: (01522) 542330 Fax: (01522) 542331

ALLISON HOMES

DRG.Nº 233/54/3

Senecio greyi 'Sunshine' at 750 centres along a single row.
Similarity planting between the circle and boundary Senecio greyi 'Sunshine' at 750 centres.

Gametime Park Bench and Pull Tunnel and Steering Wheel.

1 metre high chainlink fence with wooden posts every 2 metres and strainers where required. Tarmac base with wetpour rubber surfacing to S.H.D.C. requirements.

PUBLIC OPEN SPACE AND TODDLERS PLAY AREA.

PLOT 52

PLOT 56

PLOT 55

PLOT 54

PLOT 53

PLOT 72

PLOT 73

PLOT 74

NORTH

11 JAN 1996

Ref: 0030/96

DRAWING - 8 JAN 1996 ISSUED

ESTABLISHMENT NOTES

All trees are to be adequately staked and tied and half a bag of peat free tree and shrub planting compost incorporated into the backfill for each treehole.

A topdressing of 'Enmag' fertilizer shall be made to all shrub areas and trees following planting strictly in accordance with manufacturer's instructions.

PLANTING ADJACENT TO THE P.O.S. ON THE SOUTH & EAST SIDE REFER TO DRG.Nº 233/54/5.

PUBLIC OPEN SPACE PLANTING

TREES

F 7 Nº Fraxinus excelsior 8-10 Std.

B 15 Nº Betula pendula 180-240 10L c.g.

SA 16 Nº Sorbus aucuparia 8-10 Std.

PUBLIC OPEN SPACE LANDSCAPING PROPOSALS.
PHASES 5 AND 7, WOOLRAM WYGATE, SPALDING.
DRAWING Nº 233/54/1 SCALE 1:200 NOV. 1995.

Robert Doughty Consultancy
Planning
Landscape Architecture
Architecture
32 High Street, Helpringham, Sleaford NG34 ORA Tel: (01529) 421846 Fax: (01529) 421358
Lincoln House, 56/58 Clasketgate, Lincoln LN2 1JZ Tel: (01522) 542330 Fax: (01522) 542331

DRG.Nº 233/54/3. SCALE 1:100

DRG.Nº 233/54/4. SCALE 1:100.

DRG.Nº 233/54/2. SCALE 1:100

DRG.Nº 233/54/1. SCALE 1:200

NORTH

11 JAN 1996
Ref: 0030/96

DRAWING
- 8 JAN 1996
ISSUED

KEY SHEET FOR DETAILED PLANTING PLANS
PHASE 5AND7 WOOLRAM WYGATE, SPALDING.
DRAWING Nº 233/54/0 SCALE 1:500 NOVEMBER 199

Robert Doughty Consultancy
Planning
Landscape Architecture
Architecture
32 High Street, Helpringham, Sleaford NG34 0RA Tel: (01529) 421846 Fax: (01529)
Lincoln House, 56/58 Clasketgate, Lincoln LN2 1JZ Tel: (01522) 542330 Fax: (01522)