

On inspection it was noted that the trees' proximity to the main wall alongside the loading bay area could begin to negatively impact the structural integrity of this asset as the roots continue to grow. Furthermore, their location in regards the bulk water tank could also have similar implications.

Traffic Management:

- Manufacture, Install, Hire Of Advanced Warning Signage
- Letterdrop For Residents Affected By Road Closures (Up To 100 Properties Including businesses Consulted)
- Road Closure Diversion Up To 40 Signs. Deliver, Install, Maintain & Remove. 1no TM
- Operative With 3.5t Vehicle. Inclusive Of All Associated Signage & Equipment According to Chapter 8.

Tree Works:

- T1: Mature Alder (*Alnus glutinosa*), approximately 12-15 metres in height, with approximate crown spread of 6 metres to be sectionally dismantled to ground level, stump to be treated with EcoPlugs
- T2-7: Six Mature Alders, approximately 6-8 metres in height, with approximate crown spread of 4-5 metres to be pollarded to approximately 4-6 metres in height and 3-4 metres crown spread respectively. Arborist to pollard to appropriate points to safeguard continued health of trees.



