

Above: Disturbance of former electrical wiring intervention allowed measurement of depth of vault topping and vault thickness at crown. Topping was 300mm and vault thickness 450mm.

Below: Shows the oak battens/ joists inserted into the lime mortar vault topping to carry the 18th century floor boards.



Ayscoughfee Hall Spalding: Room F 13
© Anderson and Glenn February 2004