WINSOVER ROAD

ALDI STORE

AC AC AC AC

38 Nº LONICERA PILEATA 500 ℄

42 Nº COTONEASTER MICROPHYLLUS 500 ℄

BP

38 Nº PYRACANTHA 'RED CUSHION' 600 ℄

ST. THOMAS'S ROAD

SCHEDULE OF PLANTING

TOTAL Nº	SPECIES	SIZE	POT SIZE
42	COTONEASTER MICROPHYLLUS	30/45	2
38	LONICERA PILEATA	30/45	2
38	PYRACANTHA 'RED CUSHION'	45/60	3
TREES			
4	ALNUS CORDATA (AC)	E.H.S. 18/20	C.G.
1	BETULA PENDULA (BP)	E.H.S. 18/20	C.G.

GROUNDWORKS / TOPSOILING

- TOPSOILING TO BE CARRIED OUT BY THE LANDSCAPE CONTRACTOR AS FOLLOWS:
  SHRUB PLANTING 450 MM
  TREE PITS IN SHRUB AREAS 1.2 x 1.2 x 900 DEEP.
  TREE PITS IN PAVED AREAS 1.5 x 1.5 x 900 DEEP.
  (- IN ACCORDANCE WITH ALDI LANDSCAPE SPECIFICATION REVISED NOV '98 - SECTION 3.2.)
- * THE MAIN CONTRACTOR IS TO CARRY OUT PREPARATORY EARTHWORKS AS DESCRIBED IN SECTION 3.1 OF THE ALDI L'SCAPE SPECN.
- THE LANDSCAPE CONTRACTOR AND MAIN CONTRACTOR ARE TO LIAISE OVER TIMING OF WORKS, ACCESS ETC., AND CONFIRM POSITIONS OF ALL SERVICES (EXTG AND 'AS BUILT')

NOTES:

- UPON COMPLETION OF ALL PLANTING, FOREST BARK MULCH (TO APPROVED SAMPLE) IS TO BE SPREAD TO ACHIEVE A SETTLED DEPTH OF 50 MM FOLLOWING WATERING-IN (ALDI LANDSCAPE SPECN SECTION 4.5.3.)
- FOR DETAILS OF 'HARD' LANDSCAPING, WALLS, PAVINGS, FENCES ETC, SEE SEPARATE ARCHITECTS DRG.
- MAINTENANCE FOLLOWING PRACTICAL COMPLETION TO BE AS DESCRIBED IN SPECN SECTION 5.0.

SOUTH HOLLAND DC
HOUSING & PLANNING
31 MAR 2000
Ref: 0378/00

30 MAR 2000

DETERMINED
PLAN

RETAIL FOOD STORE
WINSOVER ROAD
SPALDING
LINCS
FOR ALDI

LANDSCAPE
PLANTING DETAILS

1:200 MARCH '00 DRG No 1

WHITING LANDSCAPE

WILDMOOR LANE • BROMSGROVE • WORCESTERSHIRE B61 0RH
Telephone: (0527) 36292 Fax: (0527) 575117

ADVANCING THE ENVIRONMENT