

DETERMINED
PLAN 434/01
's Drain
Path (um)
ANGELICA DRIVE
CAMPION CL
CLOVER WAY
LUCERNE CLOSE
Gas Governor
Drain
THE HAYFIELDS
MARIETTE WAY
RIVERSIDE
LAW COURT
VYGATE PARK
WESTERLY WAY
Spalding Grant Maintained
Primary School
CLAUDETTE WAY
GALWAY CLOSE
WEDGEWOOD DRIVE
CLAUDETTE AVE
GREVEL CL
GEORGETTE GDNS
VYGATE MEADOWS
ANNETTE CLOSE
NICOLETTE WAY
LUCETTA GARDENS

This drawing is copyright and may not be altered, traced, copied, photographed or used for any purpose other than that for which it is issued without consent of Mark Dennis Architectural Services.



PROPOSED ELEVATIONS

ROOF CONSTRUCTION
Concrete interlocking tiles to be of suitable type for pitch and installed in accordance with manufacturer's specification.
Installation to be to BS 5534 PART 1: 1978 with tiles laid to 75mm min. head lap. Dependant on tiles.
38 x 25mm preservative treatment s.w. Battens on underfelt to BS 747 felt to be lapped 150mm min.
Trussed rafter roof to be specialist designed and supplied by Twinaplate Ltd. in accordance with BS 5268 PART 3: 1985.
Trusses to be installed at 600mm ctrs.
100 x 75mm wall plate strapped to walls at 2.0m ctrs. Max. Using 30 x 5mm galvanised steel straps of not less than 1.0m in length.
Provide 30 x 5mm galvanised steel straps at 2.0m CRTs max. From rafter and ceiling chord members to gable walls.
Span 3 no. Trusses with noggings and pack not less than 38mm thick and not less than 2 depth of roof truss member restrained.
Roof bracing is to be in accordance with the BS 5268 PART 3 1985.
25 x 100mm ridge node binder, 25 x 100mm ceiling binders, 25 x 100mm 45 diagonal bracing sections.
25 x 175mm P.S.E. fascia and bargeboards (where applicable) with 6mm ply soffit.
All timber to be C16 (SC3) structural grade minimum.
200mm min. approved insulation quilt to entire roof space
Provide cross ventilation of insulated roof space with 10mm min. continuous
(or equivalent C.S. area) gap at opposing eaves. Insect mesh to be provided.
Ensure insulation does not obstruct airflow.

INTERNAL WALLING
Internal walling to be 100mm-timber studwork.
Stud partitions to comprise 50 x 75mm head and sole plate with 50 x 75mm studs at 400mm ctrs.
Install 75mm thick approved insulation quilt. 12.5mm gyproc plasterboard and skim to both faces.Nogging at 1200mm vertical ctrs.
Where partitions runs parallel to floor joist span provide doubled up joists directly below partition -see joist plan for details.
Provide sole plate where partition occurs at right angles to joist span. All doubled up joists to be bolted at 600mm ctrs.

LINTELS
Lintels to be I.G. galvanised steel or similar approved lintel to BS 5977.
Selection and installation to be in strict accordance with manufacturer's instructions.
Provide 150mm-min. end bearing to all lintels with bit. Felt d.p.c. Cavity tray provided in accordance with
BS 5628 PART 3: 1985 to all external wall conditions except where protected by eaves overhang.

WINDOWS AND DOORS
All windows to be double glazed and capable of providing not less than 1/20th floor area 'rapid' ventilation of habitable room served.
In addition, all habitable rooms to have proprietary trickle vents installed to window frame at high level providing not less than
8000 sq. mm of 'background' ventilation. To kitchen, utility, bathrooms and en-suites provide not less than 4000 sq. mm
Glazing to be in accordance with Part N Building Regulations 1991.
All external doors and opening lights to windows to be draught sealed.

GLAZING
To be in accordance with Part N1 Building Regulations and BS 6206: 1981
All glazing to internal doors where fitted to be toughened / laminated safety glass.
All glazing to external doors to be toughened / laminated safety glass except solid doors incorporating
small glazing area not exceeding 250mm width and 0.5m area, e.g. cottage style.
Double-glazing to all external doors and windows.
Each safety glazed panel to incorporate the British Standard Kite Mark, as means of identification.


FIRST FLOOR CONSTRUCTION AND CEILING FINISHES
19mm Weyroc decking to floor construction.
12.5mm plasterboard and artex to ground and first floors.
All timber to be C16 (SC3) structural grade minimum.
Provide 30 x 5mm galvanised steel lateral restraint straps at 2.0m ctrs. Max.
With pack and noggings not less than 38mm thick and not less than 2 depth of joist.
Straps to span 3no. Joists minimum.
Ensure equivalent number of floor restraint straps at trimmers adj. to stairwell opening.
38 x 38mm herringbone strutting required if span is 2.5 to 4.5m mid span. If more than 4.5m
then two rows are required at a third of the span position.

GARAGE CEILING FINISHES
Provide 12.5mm fireline boarding with artex / skim finish to ceiling, fixed to manufacturer's specification.
Where habitable room above, provide 150mm approved insulation quilt between joists.
All exposed lintels to be encased in 6mm masterboard.


HEATING
Existing boiler situated in garage.
All hot water and heating pipes to be insulated in accordance with REG. L1 Building Regulations
Room thermostat / thermostat valves to radiators installed to control heat output from boiler system.

DRAINAGE - SURFACE WATER
112.5mm dia. half round u.p.v.c. Gutters to discharge into 68mm dia. downpipes.
Below ground pipework to be 82mm dia. u.p.v.c. Flexible with 100mm-min. pea gravel bed and surround.
Pipes to be laid 1: 70 fall and to discharge into existing sw sewer or soakaways.
All work to comply with Part H3 Building Regulations 1991.


EXTERNAL WALLS
290mm cavity wall construction to comprise: -
100mm facing brick (to B.S.3921: 1974 for clay brick, BS 187: for calcium silicate brick)
60mm insulated cavity
Inner leaf to be 100mm Tarmac Hemelite or similar approved insulating blockwork.
13mm s/c render and skim to internal face.
Provide galvanised or stainless steel wall ties to BS 1243: 1978 installed at 900mm ctrs. Max. Horizontally,
450mm ctrs. Vertically. Ties at 225mm ctrs. Max. Vertically within 225mm of reveals at unbonded jambs to all openings.
Cavity to be closed at all openings and in roof space incorporating horizontal and vertical d.p.c s. Damcor insulating verbcal d.p.c.




SECTION




GROUND FLOOR PLAN




FIRST FLOOR PLAN



JOIST PLAN



ROOF PLAN



BLOCK PLAN 1:500

MARK DENNIS
architectural services
90 STATION ROAD - SURFLEET - SPALDING
LINCOLNSHIRE - PE11 4DB
TEL: 01775 680183 FAX: 01775 680183

PROJECT TITLE

PROPOSED FIRST FLOOR EXTENSION AT
16 CLAUDETTE AVENUE,
SPALDING, LINCS.

FOR MR M CORNELL

DETERMINED
PL

SOUTH HOLLAND DISTRICT COUNCIL
-8 JAN 2001
Ref: 01/34101

WORKING DRAWINGS

REV	DESCRIPTION	DATE	BY

SCALE 1:50, 1:100
DRAWN MD
DATE MAR 01
DRAWING No. 01.020/01