


Calculation Summary							
Label	CalcType	Units	Avg	Max	Min	Min/Avg	Min/Max
Parking Area 1	ILLuminance	Lux	5.05	9.6	0.9	0.18	0.09
Parking Area 2	ILLuminance	Lux	4.89	9.7	0.8	0.16	0.08
Parking Area 3	ILLuminance	Lux	4.36	9.5	0.8	0.18	0.08
Parking Area 4	ILLuminance	Lux	4.02	9.2	0.9	0.22	0.10
Roadway	ILLuminance	Lux	4.96	13.1	0.8	0.16	0.06



Spec TBC Prior To Order



<p>This scheme has been designed to:</p> <p>BS EN 13201-2:2015 Road lighting - Part 2: Performance requirements</p>	<p>P4 Adjusted for 1.5 SP Ratio: 3.75 - 5.63lux Av 0.75lux Min</p>
---	--

Please note that this proposed lighting scheme is a lighting solution that has been designed with information provided by the client. The solution does not include site, installation engineering and risk assessment considerations.



Client:	Reliant Building Contractors Ltd	Contact:	Hisham Shibl
Project Management:	Sophie Bunce	Lighting Design:	Michael Walker

All measurements in metres and lux.
Do not scale from this drawing. Product images are indicative.

Date: 25/04/16 Scale: 1:300 @ A1

Project Number:
Page: 1 of 1

12742-1-A