

PLANNING AMENDMENT

For office use only

Application No.

H16/0512/95

Date Registered

26 MAY 1995

Case Officer

PU

1. Please complete in block letters

NAME AND ADDRESS OF APPLICANT

FOUNDAHS
SPRING BR PRIMARY SCHOOL
WOOLMAN WYCKE, SPRING
PE11 1PB

Tel. No. 01775 769445

NAME AND ADDRESS OF AGENT

(if form completed by agent)

DR CAPPEL
HARTSHORN

Tel. No.

(Contact)

Please complete in block letters

FULL POSTAL ADDRESS OF THE APPLICATION SITE

SPRING BR PRIMARY SCHOOL
WOOLMAN WYCKE, SPRING, PE11 1PB

Please complete

APPLICATION No.

This amendment cannot be considered
unless the relevant reference is stated

H16/0512/95

Building Regulation reference relating to
same development (if any)

2. Please tick one box only

Amendment is proposed where
permission already granted

If yes, submit two forms and two plans.

A

☐

or

Amendment is to a proposal
currently being considered

If yes, submit four forms and four plans.

B

☒

Please complete

I attach the necessary plans and request that the changes described below be accepted as an amendment.
I understand that the Council may require a fresh application, together with fee if appropriate. If the
amendment relates to a current application, I agree to an extension of the terminal date.

Signed Date 26.5.95

3. Please complete in block letters

FULL DESCRIPTION OF DEVELOPMENT IN ORIGINAL APPLICATION

INSTALLATION OF NOISE CLASSROOM

State details of amendments proposed

(Give a full detailed list of the changes, and
also mark these clearly on the accompanying plans.
Only the changes listed here will be considered.)

NOISE TO BE SUPPLIED BY DIFFERENT
MANUFACTURER.
RAW ENCLOSURE.

State drawing no's of the current submission

Has this amendment been requested by the Council?
(If so, state Officer dealing with the application)

YES / NO


Describe any part of the original development
which is excluded by virtue of the amendment,
and state any alteration to plot numbers

Has a similar amendment been submitted under Building Regulations?

Yes / No

Housing & Planning Services Department
Council Offices,
Priory Road, Spalding,
Lincolnshire. PE11 2XE

Telephone: (01775) 761161
Fax: (01775) 710772



Application no: H16/0512/95

Applicant: Governors of Spalding G M
Primary School
Woolram Wygate
Spalding, Lincs
PE11 1PB

Agent: Headteacher
Spalding G M Primary School
Woolram Wygate
Spalding, Lincs
PE11 1PB

Description: Site temporary mobile
classroom

Location: Spalding G M Primary School
Woolram Wygate
Spalding
Lincs

Amendment: Mobile to be supplied by different manufacturer

13-JUN-95

Dear Sir/Madam

TOWN AND COUNTRY PLANNING ACT 1990
NOTICE OF ACCEPTANCE OF AMENDMENT

The amended details submitted in respect of the above proposal have now been considered, and I am able to inform you that the changes are able to be incorporated into application, which will now be considered only in its amended form. You are reminded that revision may also be needed to any submission made under the Building Regulations.

In view of the need to repeat certain procedures as a result of the amendment, the terminal date for the Authority to determine the application will now be extended to 21-JUL-95, based on the date of receipt of the amendment, and your rights of appeal remain as explained on the original acknowledgement. It will not necessarily take that length of time to reach a decision of course.

If you do not agree to this extension of time and wish instead to have your application dealt with more quickly but on the basis of the original submission, please let me know in writing within the next 5 days.

Yours faithfully

Director of Housing and Planning Services

AMENDMENT RECORD SHEET - LIVE APPLICATION

Admin

Validation:

Inadequate/Inappropriate ☐

Clarification/Details required:

Appears valid ☒

Registered ☒

Terminal date/committee updated ☐

DC Procedural Assessment

Is the information given correct?

Yes/No (If No, state above what details are needed)

Has this amendment been requested?
If Yes, is it what was asked for?

Yes/No *
Yes/No *

Who do you need to reconsult as a result of this amendment?

PC None ☒
WM
Press
Residents
Other -

Is it an amendment in principle?

Yes/No

Is it the same character/description for fee purposes?

Yes/No (Refer to Admin ?)

If No, but Yes to (*) requested :-

Do development objectives outweigh financial objectives?

Yes/No Confirmed.....

REJECTED as an amendment - new application needed

Confirmed:

Notes/Advice/Rejection Reason:

☐ Tick if you wish this note to be a paragraph in the Rejection Notice

AUTHORISED to treat as amendment

Confirmed: ☒

Superseded details removed ☒

Give a revised description if the details accepted are different to the submission:

Acceptance issued: ☒
Public register updated: ☒

DC Professional Assessment

NOTES:

AMENDED PLAN

Ref.

GENERAL SPECIFICATION OF NEW MOBILE CLASSROOM UNIT

SOUTH HOLLAND DC
HOUSING & PLANNING

21 MAY 1995

0512/95

SPALDING G.M. PRM.
WOOLRAM WYGATE
SPALDING
LINCS. PE11 1PB

Roof

The roof shall be finished in one layer elastomeric membrane bonded to 9mm wbp plywood deck, on ex. 125 x 38mm s.w. joists at 400mm centres spanning between purpose made stressed skin plywood box beams.

The ceiling shall be finished in 12.5mm plasterboard with taped joints and two coat emulsion paint finish, fixed to ex. 100 x 38mm s.w. joists at 400mm centres spanning between plywood box beams.

The roof shall be insulated with 100mm thick glassfibre quilt in order to achieve a "U" value in excess of current building regulation requirements.

The fascia shall be 9mm wbp plywood sheet with resin based textured paint finish, fixed to 45 x 45mm s.w. frame.

Floor

The floor finish shall be bonded directly onto 16mm flooring grade plywood, on ex. 125 x 47mm s.w. joists at 400mm centres all bolted to painted, welded and braced lattice steel skid chassis.

Floor shall be insulated between joists in 80mm glassfibre quilt hung in "Netlon" pvc netting in order to achieve a "U" value in excess of current building regulation requirements.

The floor is designed to withstand an imposed load of 3kN/m².

Walls

Walls shall be lined internally in 12.5mm plasterboard with taped joints and two coat emulsion paint finish (prefinished vinyl faced to wet areas), fixed to ex. 75 x 38mm s.w. framing (vertical studs at 400mm centres), clad externally in 9mm wbp plywood sheet with resin based textured paint finish.

Walls shall be insulated between framing in 60mm glassfibre quilt in order to achieve a "U" value in excess of current building regulation requirements.

Architrave, skirtings and all general woodwork trims shall be black satin finished softwood.

Miscellaneous

Internal doors shall be prefinished polished sapele effect.

External doors to be glazed with safety glass. Face fixed aluminium framed windows, single glazed in 4mm clear float glass.

Each classroom to be complete with fire exit and panic latch.

Each classroom to be complete with chalkboard and pinboard.

Each store room to be complete with 3 tier shelving 300mm wide.

Suitable number of coat hooks at required height to cloakroom / entrance.

Rainwater goods in square section black upvc.

Full electrical specification to IEE regulations.