

5.0 ADDITIONAL PLAY AREA SPECIFICATION:

5.1 Bench Seats. (As per main specification – but not variation to concrete base for LAP)

Supply and fix Glasdon ‘Phoenix’ seats as per the drawings. (Glasdon – Tel 01253 600410). The seats will black *enviropol* material with brown *enviropol* slats. No armrests are required. The seats will be centred on insitu concrete slabs measuring approximately 2100 x 800mm and 200mm deep and finished level with the adjacent footpath. (Where safety play surface is proposed in the LAP play area – fix the seats to smaller individual blocks (550x300 x 300mm) to be located under each bench leg. Concrete and play surface shall be finished flush level). The concrete shall be poured into temporary formwork on 100mm compacted Type 1 sub-base. Before the concrete is dry brush with a stiff broom to expose the aggregate. When the concrete base slab has cured for at least 10 days fix the seats using four stainless steel ground fixing bolts to be supplied by the seat manufacturer (indicatively 120mm M8 bolts). Remove concrete formwork, make up ground levels around the seat with fine soil and sow grass seed around any areas disturbed. (See also clause 3.10)

5.2 LAP Railings.

Supply and fit Jacksons 1.0m tall ‘anti-trap’ bow top fencing (colour - green) or similar approved, as shown located on the plans. All sections lengths and post centres to be set-out to fit the site situation and plans, and as per manufacturers instructions. Supply and fit a matching standard 1100mm self-closing pedestrian gate with posts. Supply and fit a matching double leaf gate for vehicular maintenance access (clear opening 2.6 metres). Supply with gate posts, dropbolts and tube receivers for both gates, (open and closed) and a slide latch. Supply a padlock with two sets of keys. Padlocks should be external quality – eg an Abus 70IB/45 Aquasafe.

5.3 LAP Play Surface.

Supply and lay wet pour recycled bonded rubber safety play surface (provisional colour - green). The thickness will be 50mm, or as required to achieve critical fall height recommendations for equipment (eg the swings). The rubber surface will be laid on a minimum 75mm compacted Type 1 stone sub-base with 150x50mm precast concrete edging kerbs. Ensure all levels marry with adjacent pavements and are 25mm higher than surrounding planting beds. From Fenland Leisure Products, Wisbech, PE14 9PJ, (Telephone 01354 638359), or similar approved.

5.4 LAP Play Equipment.

Supply and fix the following play equipment as per manufacturers instructions.

1 No. Wicksteed 2 Seat Viking Swings (Ref 6040-103) with 1 flat seat and one cradle seat. (Allow to provide one Mirage seat as an alternative to the standard cradle seat as per the schedule – final choice to be confirmed by client).

1 No Wicksteed Spiro-whirl Roundabout (Ref 6020-053)

All from Wicksteed Leisure, Kettering, NN16 8YJ; Telephone number 01536 517028.

1 No. Sutcliffe Play House (Ref DZW268)

From Sutcliffe Play, Pontefract, WF9 1JS; Telephone number 01977 653217.

Supply and arrange 6 flat boulders (each indicatively 500-700mm in width), and bed in with mortar to ensure they are rigid before pouring the safety surface around them. These shall be a flat, smooth stone type (eg York stone). Approve samples with client before delivery.