

Trees				
1	D	Acer platanoides 'Drummondii'	8-10	Standard
1	C	Acer platanoides 'Royal Red'	8-10	Standard
1	B	Betula pendula	180-240	10L c.g
3	F	Fraxinus angustifolia 'Raywood'	180-240	Feathered
4	MP	Malus 'Profusion'	6-8	1/2 Standard
3	P	Prunus avium 'Plena'	8-10	Standard
1	A	Sorbus 'Cardinal Royal'	8-10	Standard
1	S	Sorbus ana 'Majestica'	8-10	Standard
Specimen Shrubs				
3	Ag	Acer negundo 'Flamingo'		10L c.g. 3/4 breaks in lower 1/3
4	a	Amelanchier lamarkii		10L c.g. ms in lower 1/3
6	cv	Cotinus coggygria 'Royal Purple'		10L c.g. 3 breaks in lower 1/3
14	C	Cotoneaster 'Cornubia'	90-120	Bush, 2 c.g. breaks in lower 1/3
3	hV	Hedera denata 'Variegata'	100	2L c.g. caned
4	m	Mahonia japonica		10L c.g. main leader well branched
4	ph	Parthenocissus henryana	90	3L c.g. caned
3	pt	Phormium tenax	45-60	min. 8 spears
4	p	Prunus triloba 'Multiplex'		10L c.g
3	sm	Syringa 'Madame Lemonie'		10L c.g.
7	t	Taxus baccata	60-90	10L c.g.
2	vb	Viburnum x bodnantense 'Dawn'	45-60	3L c.g. 3 strong breaks in lower 1/3
7	v	Viburnum tinus		10L c.g. bushy 3 breaks in lower 1/3
3	vc	Vitis coignetiae	80	2L c.g. caned
3	yB	Yucca filamentosa 'Variegata'	30-40	3L c.g. min 5 spears
Shrubs in Beds				
83	CS	Cornus alba 'Spatheli'	40-60	2L c.g. @ 750 cs
82	EW	Escalonia 'Omond Star'	45-60	3 c.g. @ 600 cs
30	ES	Eunonymus 'Silver Queen'	15-20	2L c.g. 5 breaks in lower 1/3 @ 600 cs
83	PL	Prunus laurocerasus 'Otto Luyken'	30-40	2L c.g. min 3 strong brks in lower 1/3 @ 900 cs
50	FG	Senecio 'Sunshine'	30-45	3 strong brks in lower 1/3 @ 750 cs
23	AB	Spiraea x bumalda 'Anthony Waterer'		2L c.g. bushy 5 strong brks in lower 1/3 @ 600 cs
93	ST	Spiraea x nipponica 'Snowmound'	30-45	Bushy 2L c.g. 5 brks in lower 1/3 @ 750 cs
10	V	Viburnum tinus	30-45	3L c.g. @ 900 cs

PLANTING AND ESTABLISHMENT NOTES
All trees shall be adequately staked and tied. Stakes shall be peeled, round, softwood and min 75mm dia. Ties shall be rubber and be complete with spacers. 2 no. ties shall be used per tree, 1 no 100mm from the top of the stake and 1 no. 330mm from ground level. 40 litres of peat free tree and shrub planting compost and 50g slow release fertilizer (Enmag) per tree shall be incorporated into the backfill for each tree hole.

Shrubs shall be planted into well cultivated soil and a topdressing of 25g Enmay per sq metre shall be made after planting. All climbers shall be fixed to walls or fences by the use of appropriate fixings to encourage their climbing habit.

All plants shall be well watered before and after planting.

DRAWING
24 MAR 1998
ISSUED

SOUTH HOLLAND DC,
HOUSING & PLANNING
26 MAY 1998
Ref: 0538198

NORTH

A-plots 22, 23, 25, 26 amended with footpath, June 1997 to
+ additional tree planting

B-plots 22, 23 trees removed from road frontage. Planting amended
outside service margin plots 34-35, March 98.

C amend units plots 35-36. 3/98 GJ

WOODRUM WYATT
Phases Three &
Soft Landscapes Details

233/61-62/LD1c Scale 1:200 FEBRUARY 1997

Town & Country
Planning

Landscape Architecture

Robert
Doughty
Consultancy

32 High Street, Helpringham, Sleaford NG34 0RA Tel: (01529) 421646 Fax: (01529) 421358