

Site Plan showing Landscape Proposals.

LANDSCAPE KEY.

Proposed specimen multi-stemmed tree. Minimum 3 no breaks from base. 4.5-5.0m high. Rootballed/ containerised. Underground guyed. Extra-heavy standard treee 18-20cm girth Rootballed/ containerised. Underground guyed.
T2 Pyrus calleryana 'Chanticleer'.

Existing trees/ hedges retained.

Proposed specimen shrubs.
Generally 90-120cm high/ spread. Containerised, minimum12 L pot. Spot planted at approx. 1m centres within ground cover in groups of 3/5.
Species to include the following:
Acer palmatum dissectum Atropurpureum, Amelanchier lamarkii, Choisya ternata Sundance, Cotinus coggyria Royal Purple, Hydrangea in Var.

Proposed climbers 60-90 high 3L pot, consisting of Hydrangea anomala subsp. petiolaris 'Silver Lining'

Proposed Groundcover shrub planting.
20-35cm ht/sprd. Minimum3L pot. Planted at 4-5no. per m2 in minimum groups of 10 no. Species to include the following:
Cotoneaster dammeri, Euonymus fortunei 'Emerald and Gold', Pachysandra terminalis, and Hebe Sutherlandii.

Proposed Herbaceous planting, spot planted into ground cover. Species to include Astilbe, Alium 'Purple Sensation' Hosta in Var, Heuchera in Var.

Ornamental bulb planting consisting of Narcissus beneath existing trees.

Proposed ornamental grade turf.

Artificial Turf. Nomow Luxury Plus or similar approved. Laid onto Geotextile onto 50 sand bed onto 100 depth type 1 sub base. Subgrade free draining. Pinned into place as required. Installation to upper Terrace to architect's detail.

Proposed low informal hedge planting. 40-60cm high. Containerised 3L pot. Planted at 5no per metre. Species to include Hebe and Lavendula.

Proposed Beech hedge planting. Planted 90-120cm high. Containerised or rootballed. Planted in double staggered rows.

Patio and general areas to be Brett paving Yorktone colour Natural 600x300x50. Staggered joints.

Bark. Topsoiled to 400 depth where planting shown.

Pedestrian areas to be Brett paving Yorktone colour Charcoal 600x300x50. Staggered joints.

Upper Terrace area to be Brett paving Yorktone colour Charcoal, 450x450x50, laid onto pedestals to architect's detail. grid pattern.

Upper Terrace area to be Brett paving Yorktone colour Natural, 450x450x50, laid onto pedestals to architect's detail. grid pattern.

Hardwood benches and wall top seat from Woodscape Ltd.

6nr garden screens 2.1mx0.90m. Posts to have base plates. Style to be confirmed.

5nr 'Branches' Decorative Corten steel Screening Fence Panels from S3i group. Supplied with posts, clamps and end caps.

Corten steel garden sculptures. Consisting of 9nr Silhouetted Cow Parsley, 2nr running Hare and 2nr Pheasant sculptures.

5nr 1800x1500 Trellis panels with 750 arch. Each fitted with 2nr 70sq posts with cap and ball finial. Painted Gorse green. From the Garden Trellis company Ltd.

SCHEDULE OF PROPOSALS.

A. PATIO AREAS. To be bounded by low informal hedging and Trellis to define the space whilst allowing views out. Brett Yorktone slab paving surfacing colour Natural.300x600x50 in staggered bond.
B. TERRACES. Selected areas demarcated with Charcoal colour slabs.
C. SCULPTURE GARDEN. Corten steel sculptures to add interest.

E. INFORMAL GARDEN AREA. Tree and bulb planting.
F. RAISED TIMBER PLANTERS. Formed with Tanalised Timber Sleepers. Height as shown. To contain sensory Herb planting.

PLANTING NOTES:

Topsoil should generally be a minimum of 400mm depth over planting beds and graded to fall. Imported topsoil to be to BS3882:2007
Herbicide and cultivation: Existing Topsoil is to be treated with selected, non-residual, translocated herbicide prior to planting or screefed to remove unwanted Vegetation, removing from site. All planting areas to then have 50mm depth planting compost spread evenly over surface and worked into top 150mm, with Ericaceous compost added to Rhododendron species. removing all stones greater than 50mm dia. roots and other debris. Ensure subsoil is free-draining, if necessary carrying out ripping to a suitable depth, although avoid areas beneath existing protected trees.
Trees: To be planted in pits 900x900x600mm or dimensions of rootball, whichever is greater.with a addition 25L planting compost.All trees to be underground- guyed. Where planted in grass areas to have 900mm dia. area free of turf and mulched.Native hedge and trees to be rabbit proofed.
Mulch: Immediately following planting, areas are to be watered to field capacity and muched with 50mm depth pulverised bark.
Grass: All turf/seeded areas to be cultivated to a fine tilth and levelled, removing any stones greater than 25mm dia, together with any other debris. Pre-seeding fertilizer applied at 35gms per m2 to ornamental turfed areas. Prior to hand over areas are to managed to create a uniform and dense sward, free of weeds. All planting areas are to be maintained reasonably free of weed growth and litter, with all dead, dying and otherwise defective plant material to be replaced prior to handover.
Poisonous plants: Please note that we have made every effort to avoid use of poisonous plant materials on the site; however, it should be noted that consumption of any ornamental plant may lead to adverse symptoms.

Planting Schedule

Proposed Tree planting

Nr	Key	Plant Name	Form	Ht(cm)	Girth(cm)	CStem(cm)	Root	Ctnr
1	T2	Acer griseum	Multistemmed	300-350	-	-	C	20L
9	T3	Prunus avium 'Plena'	EHS	-	18-20	-	RB	

Proposed specimen shrubs.

Nr	Key	Species	Ht(cm)	Root	Cntr
4	ApDP	Acer palmatum Dissectum Purpureum	60-80	C	15L
4	ApB	Acer palmatum 'Bloodgood'	175-200	C	25L
10	Ic	Ilex crenata 'Ball'	50 dia.	C	15L
10	Fj	Fatsia japonica	120-150	C	15L
3	CIS	Choisya ternata Sundance	90-120	C	15L
3	CoRP	Cotinus coggygria 'Royal Purple'	90-120	C	15L
6	SnBT	Sambucus nigra 'Black Tower'	90-120	C	15L
3	HA	Hydrangea 'Annnablle'	90-120	C	15L
12	PiT	Pittosporum tenuifolium 'Tom Thumb'	90-120	C	15L
6	Vr	Viburnum rhytidophylum	60-90	C	15L

Proposed hedge planting.

Nr	Key	Plant Name	Ht(cm)	Root	Cntr
Hedge planting double staggered rows @ 5no. per m2 :					
585	Fs	Fagus sylvatica	90-120	C	3

Proposed Shrub and herbaceous planting.

Nr	Key	Species	Ht(cm)	Root	Cntr	Density(nr/m2)
30	APS	Alium Purple Sensation.	30-40	C	2L(or Bulbs)	5-7
30	An	Athyrium niponicum 'Silver Falls'	20-30	C	3L	5
25	Df	Dryopteris filix-mas	20-30	C	3L	4
80	CoE	Carex oshimensis 'Everillo'	15-20	C	3L	4
35	CSS	Carex 'Silver Sceptre'	15-20	C	3L	4
18	HaR	Hebe albicans 'Red edge'	30-40	C	3L	4
30	HGG	Hebe 'Green Globe'	30-40	C	3L	5
20	Hr	Hebe rakaiensis	30-40	C	5L	4
100	Ej	Euonymus japonicus 'Green Spire',	20-30	C	3L	4
15	EE	Euonymus 'Emerald and Gold'	20-30	C	3L	4
20	HO	Heuchera 'Obsidian'	20-30	C	3L	5
30	HL	Heuchera 'Lime marmalade'	20-30	C	3L	5
55	HfE	Hosta fortunei 'Elegans'	20-30	C	3L	4
30	HGS	Hosta 'Gold Standard'	20-30	C	3L	4
150	Pt	Pachysandra terminalis	30-40	C	3L	5
30	PmSC	Philadelphus maculatas 'Sweet Clare'	45-60	C	5L	4
15	PB	Perovskia 'Blue Spire'	30-40	C	3L	4
5	Pa	Pennisetum alopecuroides 'Goldstrich'	30-40	C	3L	4
5	SIP	Stipa tenuissima 'Pony Tails'	60-90	C	5L	4
33	Sn	Salvia nemorosa 'Caradonna'	30-40	C	3L	4
45	Sin	Santolina incana 'Nana'	30-40	C	3L	5
30	SIB	Stachys lanata Big Ears	30-40	C	3L	4

Proposed Climbers.

Nr	Key	Species	Ht(cm)	Root	Cntr	Density(nr/m2)
6	Hp	Hydrangea petiolaris 'Silver Lining'	60-90	C	2L	-

Proposed Herb planting.

Nr	Key	Species	Ht(cm)	Root	Cntr	Density(nr/m2)
10	SP(A)	Salvia officianalis 'Purpurascens'.	20-30	C	2L	5
20	APC(B)	Artemisia 'Powis Castle'	20-30	C	2L	5
5	RGG(C)	Rosmarinus 'Green Ginger'	20-30	C	2L	5
10	TA(D)	Thymus 'Aureus'	20-30	C	2L	5
20	MC(E)	Mentha x piperita 'Chocolate'	15-20	C	2L	5
30	LH(F)	Lavendula 'Hidcote'	15-20	C	2L	5

Proposed Bulb planting.

Nr	Key	Species	Density(nr/m2)
6000	B1	Narcissus 'Dutch Master'	60

	Date	Revision	
A	19.12.18	Issued for planning	CD
B	30.11.20	Layout updated. Planting quantities added.	CD
C	03.02.21	Generally amended following comments	RT
D	26.02.21	Width of path amended	RT
E	22.03.21	Rear garden amended	TE
F	29.03.21	Rear garden amended	TE
G	24.05.21	AS RECORDED ISSUE	TE

AS RECORDED

PDP Ltd. Landscape architecture, urban design.
Popeshead Court Offices, Peter Lane, York, North Yorkshire. YO1 8SU.
Tel. 07921 663628. chris.dykes@pdpland.com
www.pdplandscapeandurbandesign.co.uk

Client
Life property construction Ltd. for Glenhome.

Project
Former Birds Public House.

Drawing Title
Landscape proposals.

Scale 1:200 @ A1
Date Dec. 2018
Drawn by CD

Job No. BPH
Drawing No. BPH L1
Rev. G.