



254
255
256
257
258
259
300
240000
239
238
237
236
Works
DETERMINED PLAN
063201
Depot
Drain
Store
B M 13·03
A 1106
West Elloe Bridge
Bascule
Ward Bdy
Drl
505
442
16
WEST MARSH ROAD
Builder's Yard
Welland House
FULNEY
Lansdowne Court
B M 16·30
MARSH ROAD
CROWN DRIVE
Drain
Builder's Yard
Garage
A 151
Chapel (site of)
Lords Drain
HOLBEACH ROAD
PH
MP
PO
CB
The Foundry Hall
B M 13·80
B 1165
Sewage Pumping Station
El Sub Sta
ROYCE ROAD
B M 12·90
ASH COURT
BURNUM GROVE
BANKS AVENUE
FULNEY AVENUE
MEADOW CLOSE




west




south

east



block plan



section

FOUNDATIONS

Foundations to be ST4 grade concrete

For 265mm walls foundations to be 700 x 230mm

Foundations to be taken down to a firm loadbearing strata, a min. 1.0m if in shrinkable sub soil, in accordance with the requirements of the Local Authority Building Control Dept. and in accord with the NHBC guidelines for building near trees.
Site soil surveys are recommended in respect of foundations to establish specific site conditions before foundation work is undertaken.

FLOOR CONSTRUCTION

Ground
65mm sand/cement screed reinforced with chicken wire mesh
500g polythene seperating membrane
80mm Jablite SD floor insulation (k = 0.037W/m°C)
100mm ST4 grade oversite concrete
1200g polythene damp proof membrane
25mm sand blinding
100mm compacted hard-core - if in excess of 100mm fill, to a max. 600mm, the hard-core is to be laid and compacted in layers not exceeding 150mm.
Where 100mm internal walls are constructed off the floor slab the slab is to be thickened to 230mm for a min. width of 450mm
Strip off all vegetable soil beneath proposal.

WALL CONSTRUCTION

Below Ground
To be 100mm Class A concrete blocks
Cavity to be filled to 225mm below lowest dpc level with lean mix concrete

Above Ground
To be 265mm o/a constructed as follows :-

- 100mm facing brick (to be FL quality below dpc level)
- 65 mineral wall insulation i.e. Dritherm (k = 0.036)
- 100mm loadbearing insulation blocks i.e. Hemelite (k = 0.44)

All to be tied together using stainless steel wall ties positioned at distance not exceeding 900mm horizontally, 450mm vertically and staggered. To be at every block course vertically at all returns and reveals.

Internal finish to be 12mm render with gypsum plaster skim finish to give a 'U' value of 0.414W/mK

Internal Walls
To be 100mm blockwork constructed off a dpc off the floor slab

DPC in Walls
To be a min. 150mm above finished ground level
An insulating vertical cavity closer and dpc, i.e. Thermabate, is to be provided to all cavity closures.
A dpc cavity tray, stepped as applicable, is to be constructed within the wall immediately above an abutment.

LINTELS

Lintels to be Catnic, or similar and equivalent, to have a min. 150mm end bearing and be installed in strict accordance with manufacturers instructions with a dpc cavity tray over where applicable.

Lintels over internal openings to be Catnic CN102 lintels unless specified otherwise.

Lintels to be protected with min. 19mm gypsum plaster skim finish to give a min. half hour fire protection.

WINDOWS & DOORS

Windows and doors to be purpose made UPVC double glazed with 12mm air gap to sealed units and weather stripped.

Windows to habitable rooms are to incorporate a controllable trickle vent of 8000mm², 4000mm². to non habitable rooms.

Glazing to windows less than 800mm and doors (include sidelights to doors) less than 1500mm above floor level is to be laminated or toughened glass in accord with BS6206 : 1981.

WINDOW/DOOR & LINTEL SCHEDULE

Location	window/door ref. : width	depth	lintel ref. &	length
1	wc window re-used		CG50/100	900
2	extg door re-used		CG50/100	1200
3	1200 x	1050	CG50/100	1500
	EXTG RE-USED		cg50/100	2100

VENTILATION

The kitchen is to be mechanically ventilated direct to the external air. The capacity of the extractor is to be 60 litres/sec or 30 litres/sec if in a cooker hood.

The utility is to be mechanically ventilated direct to the external air. The capacity of the extractor is to be 30 litres/sec.

SMOKE DETECTION

Self contained smoke alarms complying with BS5446 : Pt 1 : 1990 are to be installed where indicated SD on the drawing. An alarm must be positioned within 3.0m of bedroom doors.

The alarms are to be permanently wired to a separately fixed circuit at the distribution board operating at a low voltage via a mains transformer.

Where more than one smoke alarm is required the units are to be interconnected so that the detection of smoke by one unit operates the alarm signal in all units.

The wiring installation is to comply with the I.E.E. Regulations.

HOT WATER SYSTEM

A room sealed gas fired central heating boiler is to be installed where indicated complete with fan assisted flue and combustion air vent, the area of which is to comply with the manufacturers recommendations. The flue is to be guarded externally with a stainless steel guard.
An electrical timing device is to be provided to control the operating periods of the boiler which in turn is to be controlled by room thermostat and should only fire the boiler when space heating or the hot water cylinder thermostat calls for heat.

A room thermostat or radiator valves are to be installed.

The hot water system is to be vented.

All pipes not contributing to useful heat requirements are to be insulated using an insulation material with a thermal conductivity not exceeding 0.45W/mk and a thickness equal to the external diameter of the pipe up to a max. of 40mm.

DRAINAGE

Surface
Excavate for and lay in where indicated 100mm diam. flexible jointed UPVC drains on 100mm pea gravel bed from 100mm diam. upturned bend at base of downpipe to surface water soakaway.

Form soakaway where indicated a min. 5.0m from the nearest building. Excavate 1200 x 1200 x 1200mm deep, backfill with brick rubble to 300mm below ground level, lay in sheet polythene and make up with vegetable soil.

Foul
Supply and install proprietary upvc inspection chambers on 100mm pea gravel bed in strict accordance with manufacturers instructions. Inspection chambers to conform to the following sizes : -

Depth	Internal diam	Cover diam
.6m or less	190mm	190mm
1.0m or less	450 mm	450mm
1.5m or less	1050mm	600mm
over 1.5m	1200mm	600mm

Excavate for and lay in where indicated 100mm diam. flexible jointed upvc drains on 100mm pea gravel bed at a gradient of 1 : 70.

Where flexible pipes are not under a road and have less than 600mm cover they are to have concrete paving slabs laid as bridging above the pipes for protection and are to have a min. 75mm granular material between the top of the pipe and the underside of he slab.

Install where indicated 100mm diam. stub soil stack jointed to 100mm diam. upturned bend at base. Provide removable screw on lid/air admittance veive at head.

Install where indicated trapped (rodddable) gullies - waste pipes to discharge below grating level and above water level.

Install 40mm diam. pvc waste to sinks, 32mm diam. pvc waste to hand basins all with 75mm deep traps *Unless specified other wise on plan.*
All waste pipes to have rodding access at each change of direction and be readily accessible throughout their length.

Above ground drainage to comply with BS5272 : 1978
Below ground drainage to comply with BS8301 : 1985

All drainage items are to be installed in strict accordance with the manufacturers instructions.


FLAT ROOF CONSTRUCTION

12.5mm white spar chippings bitumen bedded on
3 layer built up roofing felt, bottom layer to be astos based, dressed up abutments a min 150mm and up adjecent pitched roof a min. 450mm.
18mm exterior grade plywood decking
Firrin pieces to give a fall of 1 : 80
200 x 50mm SC3 grade joists at 400mm cts
150mm glassfibre insulation laid between joists
12.7mm foil backed plasterboard and skim finish


Where joists run parallel to walls they are to be strapped at 1800mm cts with 30 x 6mm galv m.s. straps fixed to a min 3No. joists, having nogged between beforehand, and securely fixed to walls. Similar straps to be used at 1800mm cts to hold down the wall plate.

Supply and install 115mm pvc gutters and fix to falls on fascia with all necessary brackets, stop ends, outlets etc.
Supply and install 64mm downpipes securely clipped to walls at 1800mm cts together with all necessary offsets, swannecks, adaptors etc. and taken into 100mm diam. upturned bend at base.

Provide a 25mm ventilation gap to soffit to provide cross ventilation to the roof space.



existing



proposed

SOUTH HOLLAND DC
HOUSING & PLANNING
23 MAY 2001
Ref: 0632/01
DETERMINED
PLAN

A		
	Date	Revisions

© copyright

East
Midlands
Design
Associates

"Willow Lodge",
Horseshoe Road,
Spalding,
Lincs PE11 3JA
Tel: Spalding (0775) 767968

Client
Mr. & Mrs Davis

Job Title
Utility Extension At
53 Crown Drive
Spalding
Lincs

Drawing Title
Plans. Section
&
Elevations

Scale 1:50 . 1:100 . 1:500

Date March 01 | Drawn by AL

Drg No. 01/18/01 | Rev.