
OFFICE COPY




1:500

Ref:0657/95


Proposed Garage to 5 Neville Ave Spalding 95·27 Sq.m

OFFICE COPY

SOUTH ... HOUSING
... 1995
Ref: 0657/95




Frontal View



Scale 1 50

Side Elevation

Side facing garden : not to scale



DOORS @ 2m x 0.8m


NOTE : ROOF TO BE OF FELT AND TILE FINISH.

Trusses every 600mm.

Garage to be built of Brick & Block

Footings to be as required by your selfs.


SOU... HOUSIN... ...NG
29 JUL 1995
Ref: 0657 | 95




End View

Scale 1:50


SOUTH... AND DC
HOUSING ... PLANNING
23 JUN 1995
0657/95




WEST ELEVATION 1:100 SOUTH ELEVATION



NORTH ELEVATION 1:100 EAST ELEVATION





SCALE 1:100

CONSTRUCTION

ROOF: Preformed roof trusses at 600 c/s - 22½° pitch - with grey concrete interlocking roof tiles on 25 x 32 treated battens on unbreathable felt.

WALLS.
Red facings to match existing externally with 50 mm Dritherm insulation cavity batts and 100 mm concrete blocks internally

WINDOWS & DOORS
windows and doors as shown on drawing with Catnic (or equal & approved) lintols over openings

RAINWATER GOODS
P.V.C. rainwater goods with R.W. disposal to soakaway

FASCIAS ETC.
Softwood fascias with stained finish to match existing

FLOOR
100 mm concrete slab on 1200 g. d.p.m. on sand blinding on min 150 m hardcore bed.

SOUTH HOLLAND DISTRICT COUNCIL
HOUSING & PLANNING
21 JAN 1995
Ref 657/95

PROPOSED REPLACEMENT GARAGE AT
5, NEVILLE AVENUE, SPALDING