



Reproduced from Ordnance Survey Map with the permission of the controller of HM Stationery Office.
Crown Copyright reserved.
Robert Doughty Consultancy Licence No. AR 100010613

PLANTING NOTES

General notes:

All topsoil to comply with BS 3882:2007.

Landscape scheme to be implemented during the first planting season after completion of the development.

Shrub planting:

All shrubs to conform to BS 3936 part 1 or part 2 as appropriate.
All shrub planting to be planted into a minimum depth of 300mm topsoil.
Topsoil to be cultivated to a fine tilth. All stones over 50mm, rubble, rubbish, lumps of clay, roots and all other extraneous material to be removed.
50mm layer peat free compost to be incorporated into top 150mm.
Enmag slow release fertiliser to be incorporated into planting beds at manufacturer's recommended rates.
Planting beds to be mulched with 50mm consolidated depth of bark mulch.
Planting to be watered as necessary to ensure healthy establishment.
Planting beds to be maintained free of weeds.

Tree planting:

Trees to be planted into 900x900x900mm tree pits.
Tree pit bases to be broken up to ensure adequate drainage.
Tree pit backfill to consist of 3 parts topsoil to 1 part peat free compost, 50g Enmag fertiliser to be mixed within backfill.
Trees to be double staked and tied.
Trees to be watered as necessary to ensure healthy establishment.
600mm diameter area to be kept weed free around each tree.

Grass areas:

Grass to be established over minimum of 150mm depth topsoil.
Topsoil to be cultivated to a fine tilth. All stones over 50mm, rubble, rubbish, lumps of clay, roots and all extraneous materials to be removed.
Preparation for sowing shall comply with BS4428:1989 and shall be carried out not less than 1 week prior to seeding.
Pre-seeding preparation to be applied.
Grass seed mix as indicated on the dwg, sown at manufacturer's recommended rates.
Grass seed mix shall comply with BS4428:1989.
Grass areas to be maintained between 30 and 70mm height.

Hedges:

Once mature, hedges to be maintained at a height of 1.0m.

PLANT SCHEDULE

Trees						
Qty	Abbr	Species	Girth (cm)	Height (cm)	Root Zone	Specification
4	BJ	Betula jacquemontii		200-250	RB	Multi Stemmed
2	MSy	Malus sylvestris	10-12	300-350	RB	Selected Standard
4	PC	Pyrus calleryana 'Chanticleer'	10-12	300-350	RB	Selected Standard
1	SA	Sorbus aria 'Lutescens'	10-12	300-350	RB	Selected Standard

Specimen Shrubs						
Qty	Abbr	Species	Height (cm)	Pot Size (Litres)	Specification	Density (No./m ²)
2	AJ	Aucuba japonica 'Crotonifolia'	40-60	10L	Bushy; 4 breaks	as shown
1	DB	Daphne bholua 'Jaqueline Postill'	40-60	10L	Branched; 4 breaks	as shown
2	MS	Magnolia x soulangeana	60-80	10L	Branched; 3 breaks	as shown
1	PF	Photinia x fraseri 'Red Robin'	60-80	10L	Branched; 8 breaks	as shown
1	SV	Syringa vulgaris 'Charles Joly'	60-80	10L	Branched; 3 breaks	as shown

Shrubs						
Qty	Abbr	Species	Height (cm)	Pot Size (Litres)	Specification	Density (No./m ²)
43	Bs	Brachyglottis 'Sunshine'	30-40	3L	Branched; 4 breaks	4
75	Cx	Caryopteris x clandonensis 'Heavenly Blue'	30-40	3L	Branched; 4 breaks	4
48	Ct	Choisya ternata	40-60	5L	Bushy; 5 breaks	3
56	Er	Escallonia 'Red Elf'	40-60	3L	shy; 3 breaks	3
294	Efe	Euonymus fortunei 'Emerald & Gold'	30-40 (D)	3L	Bushy; 7 breaks	4
160	Hm	Hebe 'Mrs Winder'	30-40	3L	Bushy; 5 breaks	4
225	Hr	Hebe rakaiensis	30-40	3L	Bushy; 5 breaks	3
387	Hre	Hebe 'Red Edge'	20-30	2L	shy; 3 breaks	5
68	Hh	Hypericum 'Hidcote'	30-40	3L	shy; 5 breaks	4
206	Pt	Pachysandra terminalis	15-20	3L	shy; 9 breaks	6
22	PI	Prunus laurocerasus 'Otto Luyken'	30-40	3L	shy; 3 breaks	4
28	Ro	Rosmarinus officinalis	30-40	3L	Bushy; 4 breaks	4
109	Sa	Santolina chamaecyparissus	20-30	3L	Bushy; 7 breaks	5
21	Scl	Skimmia confusa 'Isabella'	30-40	3L	shy; 3 breaks	3
56	Sc	Skimmia confusa 'Kew Green'	30-40	3L	shy; 3 breaks	3
110	Sk	Skimmia japonica	30-40	3L	shy; 3 breaks	4
50	Sj	Spirea japonica 'Goldflame'	30-40	3L	shy; 3 breaks	4
334	Sj	Spirea japonica 'Little Princess'	30-40	3L	shy; 3 breaks	4
35	Vd	Viburnum davidii	20-30	3L	shy; 3 breaks	5

Hedges						
Qty	Abbr	Species	Height (cm)	Pot Size (Litres)	Specification	Density (mm/ctrs)
120	Ef	Euonymus fortunei 'Emerald Gaiety'	40-60	5L	Bushy; 9 breaks	300ctrs double staggered rows, 300 between rows
415	Lo	Ligustrum ovalifolium 'Aureum'	40-60	3L	Branched; 7 breaks	300ctrs double staggered rows, 300 between rows
117	LV	Ligustrum vulgare	40-60	3L	Branched; 3 breaks	300ctrs double staggered rows, 300 between rows
216	Ps	Prunus x cistena	40-60	3L	Branched; 3 breaks	300ctrs double staggered rows, 300 between rows

Perennials					
Qty	Abbr	Species	Pot Size (Litres)	method of propagation	Density (mm/ctrs)
37	Bc	Bergenia cordifolia	1.5-2L	S or V	6
16	Gr	Geranium macrorrhizum	1.5-2L	S or V	6
37	Hp	Hebe bore purpurascens	1.5-2L	S or V	6

Climbers						
Qty	Abbr	Species	Height (cm)	Pot Size (Litres)	Specification	Density (mm/ctrs)
41	Lp	Lonicera periclymenum 'Belgica'	60-80	3L	3 breaks; caned	2 per lin. m

Ferns						
Qty	Abbr	Species		Pot Size (Litres)	method of propagation	Density (mm/ctrs)
71	Pse	Polystichum setiferum		1.5-2L	S or V	4

Ferns						
Qty	Abbr	Species				Density (mm/ctrs)
64	Ab	Anemone blanda				8
64	Gn	Galanthus nivalis				8

Planting

- Proposed Trees
- Proposed Specimen Shrubs
- Proposed Shrub Planting
- Proposed Hedge
- Proposed Grass Area. British Seed Houses: A22, (Low Maintenance) mix
- Climbing plant
- Bulb planting in grass
- Proposed Grass Area. British Seed Houses: RE2, Lowland Meadow mix
- Boundary Treatments
- Proposed Picket Fence
- Proposed Railings
- Proposed Brick Wall
- Paving
- Charcoal Block Paving
- Brindle Block Paving
- Blacktop

rdc
Robert Doughty
Consultancy

32 High Street, Helpringham
Sleaford, Lincolnshire NG34 0RA
Tel: 01529 421646
Fax: 01529 421358
Email: admin@rdc-landplan.co.uk
Web: www.rdc-landplan.co.uk

Client:
ALLISON HOMES EASTERN LTD

Project:
Woolram Wygate South West Quadrant

Drawing title:
Landscape Details - Sheet 2 of 6

Drawing No:
520 / 214 / LD02

Rev:
D

Drawn:
HR

Scale:
1:250 @ A1

Date:
21 / 06 / 11

Checked:

Rev.

By

Notes

Date

2/12/11

29/11/11

27/07/11

07/07/11

Rev.

By

Notes

Date

2/12/11

29/11/11

27/07/11

07/07/11

All measurements should be checked against on site conditions and any discrepancies should be brought to the attention of the