

PLANT SCHEDULE

Trees

Qty	Abbr	Species	Girth (cm)	Height (cm)	Root Zone	Specification
2	PC	Pyrus calleryana 'Chanticleer'	10-12	300-350	RB	Selected Standard
4	TC	Tilia cordata 'Greenspire'	12-14	350-425	RB	Heavy Standard

Specimen Shrubs

Qty	Abbr	Species	Height (cm)	Pot Size (Litres)	Specification	Density (No./m²)
1	AJ	Aucuba japonica 'Crotonifolia'	40-60	10L	Bushy; 4 breaks	as shown
4	MS	Magnolia x soulangeana	60-80	10L	Branched; 3 breaks	as shown
5	PF	Photinia x fraseri 'Red Robin'	60-80	10L	Branched; 6 breaks	as shown
3	SV	Syringa vulgaris 'Charles Joly'	60-80	10L	Branched; 3 breaks	as shown

Shrubs

Qty	Abbr	Species	Height (cm)	Pot Size (Litres)	Specification	Density (No./m²)
184	Bs	Brachyglottis 'Sunshine'	30-40	3L	Branched; 4 breaks	4
83	Cx	Caryopteris x clandonensis 'Heavenly Blue'	30-40	3L	Branched; 4 breaks	4
44	Ct	Choisya ternata	40-60	5L	Bushy; 5 breaks	4
6	Er	Escallonia 'Red Elf'	40-60	5L	Bushy; 5 breaks	3
101	Efe	Euonymus fortunei 'Emerald & Gold'	40-60	3L	Bushy; 3 breaks	3
43	Hm	Hebe 'Mrs Winder'	30-40 (D)	3L	Bushy 7 breaks	3
56	Hr	Hebe rakaiensis	30-40	3L	Bushy; 5 breaks	4
139	Hre	Hebe 'Red Edge'	30-40	3L	Bushy; 5 breaks	4
153	Hh	Hypericum 'Hidcote'	20-30	2L	Bushy; 3 breaks	3
20	La	Lavandula angustifolia 'Hidcote'	30-40	3L	Bushy; 5 breaks	5
78	Pt	Pachysandra terminalis	20-30	3L	Bushy; 5 breaks	4
98	Pl	Prunus laurocerasus 'Otto Luyken'	15-20	3L	9 breaks	4
11	Ro	Rosmarinus officinalis	30-40	3L	Bushy; 3 breaks	6
142	Sa	Santolina chamoecyparissus	30-40	3L	Bushy; 4 breaks	4
41	Sk	Skimmia japonica	20-30	3L	Bushy 7 breaks	4
68	Sjg	Spirea japonica 'Goldflame'	30-40	3L	Bushy; 3 breaks	5
107	Sj	Spirea japonica 'Little Princess'	30-40	3L	Bushy; 3 breaks	4
79	Vd	Viburnum davidii	30-40	3L	Bushy; 3 breaks	4
			20-30	3L	Bushy; 3 breaks	4
			20-30	3L	Bushy; 3 breaks	5

Hedges

Qty	Abbr	Species	Height (cm)	Pot Size (Litres)	Specification	Density (mm/ctrs)
144	Ef	Euonymus fortunei 'Emerald Gaiety'	40-60	5L	Bushy: 9 breaks	300ctrs double staggered rows, 300 between rows
439	Lo	Ligustrum ovalifolium 'Aureum'	40-60	3L	Branched; 7 breaks	300ctrs double staggered rows, 300 between rows
273	Ps	Prunus x cistena	40-60	3L	Branched; 3 breaks	300ctrs double staggered rows, 300 between rows

Perennials

Qty	Abbr	Species	Pot Size (Litres)	method of propogation	Density (mm/ctrs)
24	Bc	Bergenia cordifolia	1.5-2L	S or V	6
27	Gr	Geranium macrorrhizum	1.5-2L	S or V	6
12	Hp	Hellebore purpurascens	1.5-2L	S or V	6

Climbers

Qty	Abbr	Species	Height (cm)	Pot Size (Litres)	Specification	Density (mm/ctrs)
11	Lp	Lonicera periclymenum 'Belgica'	60-80	3L	3 breaks:caned	2 per lin.m

PLANTING NOTES

General notes:

All topsoil to comply with BS 3882:2007.

Landscape scheme to be implemented during the first planting season after completion of the development.

Shrub planting:

All shrubs to conform to BS 3936 part 1 or part 2 as appropriate.
All shrub planting to be planted into a minimum depth of 300mm topsoil.
Topsoil to be cultivated to a fine tilth. All stones over 50mm, rubble, rubbish, lumps of clay, roots and all other extraneous material to be removed.
50mm layer peat free compost to be incorporated into top 150mm.
Enmag slow release fertiliser to be incorporated into planting beds at manufacturer's recommended rates.
Planting beds to be mulched with 50mm consolidated depth of bark mulch.
Planting to be watered as necessary to ensure healthy establishment.
Planting beds to be maintained free of weeds.

Tree planting:

Trees to be planted into 900x900x900mm tree pits.
Tree pit bases to be broken up to ensure adequate drainage.
Tree pit backfill to consist of 3 parts topsoil to 1 part peat free compost, 50g Enmag fertiliser to be mixed within backfill.
Trees to be double staked and tied.
Trees to be watered as necessary to ensure healthy establishment.
600mm diameter area to be kept weed free around each tree.

Grass areas:

Grass to be established over minimum of 150mm depth topsoil.
Topsoil to be cultivated to a fine tilth. All stones over 50mm, rubble, rubbish, lumps of clay, roots and all extraneous materials to be removed.
Preparation for sowing shall comply with BS4428:1989 and shall be carried out not less than 1 week prior to seeding.
Pre-germination fertiliser to be applied.
Grass seed mix as indicated on the dwg, sown at manufacturers recommended rates.
Grass seed mix shall comply with BS4428:1989.
Grass areas to be maintained between 30 and 70mm height.

Hedges:

Once mature, hedges to be maintained at a height of 1.0m.

Planting

Climbing plant

Proposed Grass Area British SeedHouses: A22, (Low Maintenacnce) mix

Proposed Shrub Planting

Proposed Hedge

Proposed Trees

Proposed Specimen Shrubs

Boundary Treatments

Proposed Picket Fence

Proposed Railings

Proposed Brick Wall

Paving

Charcoal Block Paving

Brindle Block Paving

Blacktop

Reproduced from Ordnance Survey Map with the permission of the controller of HM Stationery Office.
Crown Copyright reserved
Robert Doughty Consultancy Licence No. AR 100010613

Rev.	By	Notes	Date
A	KG	Amendments to CSH area plan, schedule and key	29-11-11

rdc Robert Doughty Consultancy
32 High Street, Helpringham
Sleaford, Lincolnshire NG34 ORA
Tel: 01529 421646
Fax: 01529 421358
Email: admin@rdc-landplan.co.uk
Web: www.rdc-landplan.co.uk

Client: ALLISON HOMES EASTERN LTD

Project: Woolram Wygate South West Quadrant

Drawing title: Landscape Details - Sheet 4 of 6

Drawing No. 520 / 214 / LD04 | Rev. A | Drawn HR

Scale 1:250 @ A1 | Date | Checked

SHDC PLANNING & DEVE
06 JAN
Ref. 07 0
AMEN
Ref. A1