WORKS TO PRESERVED TREES – H16-0721-19
TANGLEWOOD CARE HOMES LTD
CEDAR FALLS, LITTLE LONDON, SPALDING, PE11 2UA

Please read this in conjunction with plan 3524-19-01A

1 to 6 - Sliver Birches – Crown lift with 7-8ft head clearance

7 – Horse Chestnut – Crown lift with 7-8ft clearance
Possible tidy up of damaged branches
Potentially weak South East branch take weight off by 2m length &
Height & curve in
Potentially tidy up damaged branch

8 – Horse Chestnut – Remove ivy off base of trunk

9 – Rowan – Remove rubbing branches

10 – Prunus Plum – Crown lift clearance 7-8ft, remove deadwood & possible rubbing branches

11 – Norway Maple – Clear branches 2m from lamp post & remove deadwood.
Crown lift clearance 7-8ft

12 – Willow – 7-8ft clearance to footpath, reduce upper crown accordingly
Check any faults with branches to the North
Prune back to previous cuts

13 – Willow – Same as 12 and clean out fallen branches within trunk

14 – Cherry – Clear deadwood

15 – Silver Birch – Crown lift to 7-8ft head clearance

16 – Whitebeam – Crown lift to 7-8ft and clear rubbing branches

17 – Variegated Sycamore – Remove rubbing branches & deadwood

18 – Ash – Take weight off to the East, shape & balance to relieve pressure approx. 1/3 of branch to remove
Tidy up over neighbour & trim back deadwood
Take approx 2m off length from neighbours at growth points privet hedge

19 & 20 – Amalanka – General tidy up

21 – Rowan – Protect base with guard from strimming & remove deadwood
Water occasionally at dry spells

22 – Lime – Selective crown lifting at 7-8ft to previous cuts to remove from parked cars.
Clear rubbing branches, ivy & deadwood

23 – Ash – Remove deadwood

24 – Sycamore – Clear rubbing branches & prune back from neighbours hedge & clear deadwood

25 – Norway Maple – Clear rubbing branches & deadwood

26 – Poplar (Variegated) – Remove deadwood

27 – Rowan – Remove rubbing branches

Permission given to remove and tidy up overhanging branches from neighbours trees to again give a head clearance of 7-8ft.