FENCE TO EXTEND ACROSS ENTIRE BOUNDARY WITH No 3 BRAMBLE GRANGE

NOTE: FENCE IS TO BE INSTALLED AT START OF CONTRACT

No 3 BRAMBLE GRANGE

No 2 BRAMBLE GRANGE

LEVEL PLATFORM LAID TO WEATHERING FALL ONLY

1:12 FALL FROM PLATFORM

10.000

10.150

NEW TARMAC FEATHERED INTO EXISTING

EXISTING KERB REMOVED

TARMAC REPLACED FEATHERED INTO EXISTING

10.050

GRASS RE LAID TO MEET PATH

PATH LAID AT 1:60 WEATHERING FALL

EXISTING KERB REMOVED

EXTERNAL WALKWAY LAID TO 1:20 FALL

SEE DETAIL (9-)C2

SEE DETAIL (9-)C1

EXISTING TARMAC

10.100

NEW TARMAC FEATHERED INTO EXISTING

EXISTING WALL REMOVE

EXISTING SHED TO BE RELOCATED

EXTENT OF NEW FENCE

EXISTING SHED

EXISTING GRASS

SOIL LEVEL 10.000

DOOR RESTRAINT

SEE DETAIL (9-)C3

WEATHERING FALL TO PLANTER

EMH

SWMH

EXISTING PATH

DOOR RESTRAINT

WEATHERING FALL TO EXISTING PATH

EXISTING TARMAC CAR PARK

No dimensions are to be scaled off this drawing all dimensions governing dimensions and levels are to be checked on site before starting work

EXISTING TREES TO BE REMOVED

SOUTH HOLLAND DC
HOUSING & PLANNING
20 JUL 1998
Ref: 0143/98

rev	date	by	revision

Lyster Grillet & Harding

Architects

London House 271-273 King Street London W6 9LZ 0181-741 0814
1 Pemberton Place Cambridge CB2 1XB 01223-351626

client: SPALDING PRIMARY SCHOOL

job: NEW CLASSROOM BLOCK & HALL EXTENSION

drawing: EXTERNAL WORKS

DETERMINED
PLAN

date	drawn	scale
JAN 98	DWS	1:100
	( )	

job no	dwg no.	rev
1560	(9-) L1	