

Donna Robinson - 2 Aalsmeer Rise, Spalding, PE11 3JD

MCS 020(a) - Heat Pump Sound Calculator

Assessment Details

Heat pump model is Cosy9 and it is 9.0 metres from the assessment window.

There are 2 reflecting surfaces including the floor and it is not seen.

The assessment position is one metre perpendicular to the centre of the closest habitable room.

Step	Instructions	MCS contractor results/notes
1	Assessment Date	24/08/2026
2	Assessment Position	first floor assessment window of No.1 Haarlem Court, side elevation looking north
3	A-weighted sound power level of the heat pump dBA	57.0
4a	Determine the directivity 'Q' of the heat pump noise.	Q4
4b	Measure the distance from the heat pump to the assessment position in metres	9.0
5	Determination of barrier correction - select barrier type	Fence <18mm
6	Determination of barrier correction - select line of sight	Not seen
7	Calculate Sound Pressure Level	27.9
8	Final Result?	Pass

Final Sound Pressure Level: 27.9 dB(A) - COMPLIANT

This assessment follows the MCS 020 planning standard for heat pumps.
Maximum permitted sound level at assessment position: 37 dB(A)

Annotated Planning Application Photo

